

**Name of work :- Repairs to Various Road by Asphalt Patch work under
Jurisdiction of R & B Division, DevBhumi Dwarka (ARC) 2026-27 .**

S C H E D U L E 'B'

Sr. No	Description of Item	Unit	Rate	Rs. In Words
1	2	3	4	5
199	Providing and laying 50mm thick B.M. With BT Aggregate VG-30 grade bitumen for Tack coat @ 2.50 kg/10 sqm using crushed stone aggregate 0.66 cum/MT as per MORTH&H Specification & VG-30 grade bitumen for mixing @34.00 Kg/1 MT i.e. 3.4% of by weight of total mix incl. heating and mixing by drum mix plant and spreading the same with paver finisher consolidation with vibratory roller including cost of fuel, hire charges, all necessary equipments, tools and plant, fire wood, oil, kerosene labour changes etc complete.(Using contractor's own Machinery)			
A	Lead 0/00 to 15/00 KM	M.T.		
B	Lead 15/00 to 30/00 KM	M.T.		
C	Lead 30/00 to 50/00 KM	M.T.		
D	Lead 50/00 to 100/00 KM	M.T.		
200	Providing and laying 50mm thick B.M. With BT Aggregate VG-30 grade bitumen for Tack coat @ 2.50 kg/10 sqm using crushed stone aggregate 0.66 cum/MT as per MORTH&H Specification & VG-30 grade bitumen for mixing @34.00 Kg/1 MT i.e. 3.4% of by weight of total mix incl. heating and mixing by drum mix plant and spreading the same without paver finisher consolidation with vibratory roller including cost of fuel, hire charges, all necessary equipments, tools and plant, fire wood, oil, kerosene labour changes etc complete.(Using contractor's own Machinery)			
A	Lead 0/00 to 15/00 KM	M.T.		
B	Lead 15/00 to 30/00 KM	M.T.		
C	Lead 30/00 to 50/00 KM	M.T.		
D	Lead 50/00 to 100/00 KM	M.T.		

1	2	3	4	5
201	Providing and laying 20 mm thick average for patchwork Mix seal surface using stone chips @66% by weight, gradation as per MORTH specification and using bitumin VG 30 grade for tack coat @ 2.50 Kg/10Sqm and for mixing rate not less than 50.90KG/MT on BT surface using stone chips as per MORTH specification including heating the asphalt and aggregates by hot mix plant and spreading the same with paver finisher including consolidation with vibratory roller and providing, operating plant machineries, equipments, tools, plants, oil, fire wood, kerosene and all labour charges etc. complete.			
A	Lead 0/00 to 15/00 KM	M.T.		
B	Lead 15/00 to 30/00 KM	M.T.		
C	Lead 30/00 to 50/00 KM	M.T.		
D	Lead 50/00 to 100/00 KM	M.T.		
202	Providing and laying 20 mm thick average for patchwork Mix seal surface using stone chips @66% by weight, gradation as per MORTH specification and using bitumin VG 30 grade for tack coat @ 2.50 Kg/10Sqm and for mixing rate not less than 50.90KG/MT on BT surface using stone chips as per MORTH specification including heating the asphalt and aggregates by hot mix plant and spreading the same without paver finisher including consolidation with vibratory roller and providing, operating plant machineries, equipments, tools, plants, oil, fire wood, kerosene and all labour charges etc. complete.			
A	Lead 0/00 to 15/00 KM	M.T.		
B	Lead 15/00 to 30/00 KM	M.T.		
C	Lead 30/00 to 50/00 KM	M.T.		
D	Lead 50/00 to 100/00 KM	M.T.		
203	Providing and laying asphalt painting on BT surface with Bitumin grade VG-30 at the rate of 5.00 kg/10 sqm by mechanical sprayer and spreading the stone dust on prepared surface at the rate 0.03 cum/10 sqm and rolling with PTR roller & brushing etc. complete.			
A	Lead 0/00 to 15/00 KM	Sqm		
B	Lead 15/00 to 30/00 KM	Sqm		
C	Lead 30/00 to 50/00 KM	Sqm		
D	Lead 50/00 to 100/00 KM	Sqm		

1	2	3	4	5
204	Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam as per MORTH specification including premixing the material with water at OMC in mechanical mixer Plant, carriage of mixed material by tipper to site, laying in uniform layers in sub-base/base course on a well prepared sub-base and compacting with vibratory roller to achieve the desired density etc comp.			
A	Lead 0/00 to 15/00 KM	Cum		
B	Lead 15/00 to 30/00 KM	Cum		
C	Lead 30/00 to 50/00 KM	Cum		
D	Lead 50/00 to 100/00 KM	Cum		
205	Engaging the comprssor for the different type of work on road side with machineries, oil, fuel, driver ,labour etc. complete (ra)	day		
206	Carting the mix materials from plant site to road site by agency Truck/Dumper with lead upto 20.00 Km and spreading the mix materials for patch work on road site, rolling & consolidation comp.	M.T.		
207	Carting the mix materials from plant site to road site by agency Truck/Dumper with lead 21.0 to 40.0 and spreading the mix materials for patch work on road site, rolling & consolidation complete.	M.T.		
208	Engaging the 82.50 KV Generator Set for Govt. Drum Mix Plant site with machinery oil. fuel, deriver etc. complete.	Hours		

Deputy Executive Engineer
Dwarka (R&B) Sub-Division
Dwarka