

Providing VVIP/VIP Mandap on hire basis for Govt. functions to be held under jurisdiction of R & B Division, Morbi for Year 2026-27

Item No.	Item Description	Qty	Unit
1	Providing and erecting German Alluminium Fabricated Structural Dome having width upto 150 feet and minimum central apex hight of 36 feet from G.I. roof covered with Blue and Grey SRF Fabric (Waterproof and Fire Resistant) using snow white or colourful cloth ceiling has to be provided below the cover including colourful "Zalar" on each ring and tricolour or colourful facia on the front of the dome including every vertical pillar of dome should be supported with bottom plate support arrange as per structural stability as per design structural engineer with efficient rain water drainage system and dome side as directed by engineer in charge, side height 20' so as to accomodate stage light truss inside including submission of the structural stability certificate for dome from Govt. approved structural engineer prior to function day to Engineer in charge. as directed by engineer in charge.	1.0	Sq.mt
2	Providing and Fixing/Fitting of Mandap with approved Coloured neat-clean Cloth for sealing Patta, Zool, with Mandap from Cross Bressing by using 2" to 3" thick long Balles / Bamboo and any other Required Material .	1.0	Sq.mt
3	Providing and Fixing/Fitting of Mandap with approved Coloured neat-clean Cloth for sealing Patta, Zool, with water proof Mandap from Cross Bressing by using 2" to 3" thick long Balles / Bamboo and any other Required Material .	1.0	Sq.mt
4	Providing and Fixing/Fitting of Pipe Mandap with steel structure Single Height mandap upto 12 ft height (including zool, vali, patta neat clean) including necessary excavation fitting, up to 16' height etc. complete as per instruction.	1.0	Sq.mt
5	Providing and Fixing/Fitting of Pipe Mandap with steel structure Single Height water proof mandap 12 ft (Incl. zool, vali patta) neat-clean including necessary excavation fitting, etc. complete as per instruction.	1.0	Sq.mt
6	Providing and Fixing/Fitting of Pipe Mandap with steel structure-Double Height (including Zool, Vali Patta neat-clean) Height above 3.00 Mtr. To 6.00 Mtr.	1.0	Sq.mt
7	Providing and Fixing/Fitting of Pipe Mandap with steel structure-Double Height water proof mandap (including Zool, Vali Patta). The cloth utilize in zool etc. should be neat-clean. Height above 3.00 Mtr. To 6.00 Mtr.	1.0	Sq.mt
8	Providing and Fixing/Fitting of Pillar less mandap (Dom Mandap) with zool on Ballies / Bamboos or iron pipe structure zool as directed in mandap etc. complete including necessary excavation fitting, above 16' ft height etc. complete as per instruction. The Zool and cloth should be used is neat and clean and good quality. (upto 90ft width)	1.0	Sq.mt
9	Providing and Fixing/Fitting of Complete steel structure dome mandap upto 35' ft height with RCC foundation Base plate Nut-Bolt fitting complete structure with zool in selected cloth in ceiling. Top sided etc. as per instruction & requirement. The Zool and cloth should be used is neat and clean and good quality.including submission of the structural stability certificate for dome from Govt. approved structural engineer prior to function day to Engineer in charge. as directed by engineer in charge.	1.0	Sq.mt
10	Providing and Fixing/Fitting of Complete steel structure dome mandap upto 35' ft height with RCC foundation Base plate Nut-Bolt fitting complete structure with zool in selected cloth in ceiling. In and Top (Double sided) etc. as per instruction & requirement.The Zool and cloth should be used is neat and clean and good quality.(150ft with) including submission of the structural stability certificate for dome from Govt. approved structural engineer prior to function day to Engineer in charge. as directed by engineer in charge.	1.0	Sq.mt
11	Providing and Fixing/Fitting of Complete steel structure dome mandap upto 35' ft height with RCC foundation Base plate Nut-Bolt fitting complete structure with zool in selected inside cloth in ceiling.and Top side plastic / Tadptri (Water Proof) etc. as per instruction and requirement.	1.0	Sq.mt
12	Providing and Fixing/Fitting of Complete steel structure dome mandap upto 35' ft height with RCC foundation Base plate Nut-Bolt fitting complete structure with zool in selected .In and Top side (Double sided)cloth and plastic or tadptri and net jali in ceiling. with water proof Mandap etc. as per instruction & requirement. including submission of the structural stability certificate for dome from Govt. approved structural engineer prior to function day to Engineer in charge. as directed by engineer in charge.	1.0	Sq.mt
13	Providing and Fixing/Fitting of selected cloth and jute flooring or green net flooring with different color as per instruction & requirement. and destory the debris and grade and levelling of the ground. The Zool and cloth should be used is neat and clean and good quality.	1.0	Sq.mt
14	Providing and Fixing/Fitting of selected cloth and P.V.C. net flooring on stage and on floor as per instruction & requirement. and destory the debris and Gradd and levelling of the ground.	1.0	Sq.mt
15	Providing and Fixing/Fitting of Stage having shape of Square / Rectangular / Round including flooring of Kantan / Green Net / Cloth with wooden steps including cloth zool around the stage. The Zool and cloth should be used is neat and clean and good quality. (A) Upto 1 Mtr. Height	1.0	Sq.mt
16	Providing and Fixing/Fitting of Stage having shape of Square / Rectangular / Round including flooring of Kantan / Green Net / Cloth with wooden steps including cloth zool around the stage. The Zool and cloth should be used is neat and clean and good quality. (B) Upto 1 to 1.5 Mtr. Height	1.0	Sq.mt
17	Providing and Fixing/Fitting of Stage having shape of Square / Rectangular / Round including flooring of Kantan / Green Net / Cloth with wooden steps including cloth zool around the stage. The Zool and cloth should be used is neat and clean and good quality. (C) Upto 1.5 to 3.0 Mtr. Height	1.0	Sq.mt
18	Providing and Fixing/Fitting of Stage back screen Wall of wooden or M.S. framing covering good approved colour & quality shartin cloth providing proper wooden or M.S. supports for stability etc. complete as directed. The satin cloth should be used is neat and clean and good quality.(A) Upto 3 Mtr. Height.	1.0	Sq.mt
19	Providing and Fixing/Fitting of Stage back screen Wall of wooden or M.S. framing covering good approved colour & quality shartin cloth providing proper wooden or M.S. supports for stability etc. complete as directed. The satin cloth should be used is neat and clean and good quality.(A) Upto 3 Mtr. Height (Both side).	1.0	Sq.mt

20	Providing and Fixing/Fitting of Stage back screen Wall of wooden or M.S. framing covering good approved colour & quality shartin cloth providing proper wooden or M.S. supports for stability etc. complete as directed. The satin cloth should be used is neat and clean and good quality. (B) Above 3 Mtr. Height.	1.0	Sq.mt
21	Providing and Fixing/Fitting of Stage back screen Wall of wooden or M.S. framing covering good approved colour & quality shartin cloth providing proper wooden or M.S. supports for stability etc. complete as directed. The satin cloth should be used is neat and clean and good quality. (B) Above 3 Mtr. Height (Both side).	1.0	Sq.mt
22	Providing and Fixing/Fitting of plywood stage flooring in square / rectangel / or any shape complete as directed. avg 8 to 12 mm thick	1.0	Sq.mt
23	Providing plywood stage flooring in square / rectangel / or any shape complete as directed. avg 19 mm thick	1.0	Sq.mt
24	Providing and Fixing/Fitting of selected Colour cloth Kachi Wall around shamiyana, etc. complete as directed. The cloth utilise in wall should be neat and clean and good quality. (A) Height upto 1.85 Mtr.	1.0	Rmt.
25	Providing and Fixing/Fitting of selected Colour cloth Kachi Wall around shamiyana, etc. complete as directed. The cloth utilise in wall should be neat and clean and good quality. (B) Height above 1.85 Mtr.	1.0	Rmt.
26	Providing and Fixing/Fitting of wooden Framing wall Vertical support of M.S. or wooden member all four Side wooden batten patti (2" x 1/2" size) framing fixing fency cloth / kantan including providing decorative Gamthi Toran or Sartin zool on top of wall etc. complete as directed. The cloth utilise in wall should be neat and clean and good quality. (A) Height upto 1.85 Mtr. One side cloth wall.	1.0	Rmt.
27	Providing and Fixing/Fitting of wooden Framing wall Vertical support of M.S. or wooden member all four Side wooden batten patti (2" x 1/2" size) framing fixing fency cloth / kantan including providing decorative Gamthi Toran or Sartin zool on top of wall etc. complete as directed. The cloth utilise in wall should be neat and clean and good quality. (B) Height upto 1.85 Mtr. & both side Cloth wall.	1.0	Rmt.
28	Providing and Fixing/Fitting of wooden Framing wall Vertical support of M.S. or wooden member all four Side wooden batten patti (2" x 1/2" size) framing fixing fency cloth / kantan including providing decorative Gamthi Toran or Sartin zool on top of wall etc. complete as directed. The cloth utilise in wall should be neat and clean and good quality. (C) Height above 1.85 Mtr. & 3 Mtr. One side Cloth wall.	1.0	Rmt.
29	Providing and Fixing/Fitting of wooden Framing wall Vertical support of M.S. or wooden member all four Side wooden batten patti (2" x 1/2" size) framing fixing fency cloth / kantan including providing decorative Gamthi Toran or Sartin zool on top of wall etc. complete as directed. The cloth utilise in wall should be neat and clean and good quality. (C) Height above 1.85 Mtr. & 3 Mtr. Both side Cloth wall.	1.0	Rmt.
30	Providing Box type Designed Gate(15' x 12' x 2') of wooden framing covering all four Side selected shartin cloth Providing required support for proper stability etc complete as directed of size 10' wide and 8' height.	1.0	Rmt.
31	Fency Decorative Gate (Full size) ring / triangle / square / rectangle above 15 ft height including necessary fitting, framing, etc. Complete. as per requirement and instruction.	1.0	Rmt.
32	Providing Fency patti Gate.	1.0	Rmt.
33	Providing Fency partition Gate.	1.0	Rmt.
34	Providing Fency round Gate (Ring Gate).	1.0	Rmt.
35	Providing and Fixing/Fitting of Red Carpet or any color as per instruction.	1.0	Sq.mt
36	Providing and Fixing/Fitting of Coirmat Carpet.	1.0	Sq.mt
37	Providing and Fixing/Fitting of Jute Mat Carpet (Full Size).	1.0	Sq.mt
38	Providing and Fixing/Fitting of Gadi gadla with cover (6' x 3').	1.0	Nos.
39	Providing and Fixing/Fitting of Carpet (Shetranji) all various size	1.0	Sq.mt
40	Providing and Arranging in Raw of wooden Moulded Chair neat and clean and good quality. as per the instruction of Engineer-in-charge.	1.0	Nos.
41	Providing and Arranging in Raw of Steel Moulded Chair neat and clean and good quality.as per the instruction of Engineer-in-charge.	1.0	Nos.
42	Providing and Arranging in Raw of Plastic Moulded Chair neat and clean and good quality. as per the instruction of Engineer-in-charge. 0 to 10000 Chairs	1.0	Nos.
43	Providing and Arranging in Raw of Plastic Moulded Chair neat and clean and good quality. as per the instruction of Engineer-in-charge. (10000 to 25000 Chairs)	1.0	Nos.
44	Providing and Arranging in Raw of Plastic Moulded Chair neat and clean and good quality. as per the instruction of Engineer-in-charge. (25000 and above Chairs)	1.0	Nos.
45	Providing and Arranging in Raw of Plastic Moulded Chair Red and Blake for VVIP/VIP cleaning and arranging on site as per the instruction of Engineer-in-charge.	1.0	Nos.
46	Providing and Arranging in Raw of Wooden Decorative Chair neat and clean and good quality with U-Form Sit (V.V.I.P.)	1.0	Nos.
47	Providing and Arranging in Raw of SS Frame and wooden chair for Press / Media persons with cushion including arranging on site as per the instruction of Engineer-in-charge.	1.0	Nos.
48	Providing and Arranging in Raw of Three Seat Sofa Shankheda Brass ,Alluminium or steel framing with small pillow neat and clean and good quality etc. complete with Siphon Cover.	1.0	Nos.
49	Providing and Arranging in Raw of Two Seat Sofa Shankheda Brass Alluminium or steel framing with small pillow neat and clean and good quality etc. complete with Siphon Cover.	1.0	Nos.
50	Providing and Arranging in Raw of One Seat Sofa Shankheda Brass Alluminium or steel framing with small pillow neat and clean and good quality etc. complete with Siphon Cover.	1.0	Nos.
51	Providing and Arranging in Raw of good quality One Seater Soft in Leather or Good Quality Tapestry with small pillow for V.V.I.P.S.	1.0	Nos.
52	Providing and Arranging in Raw of good quality Two Seater Soft in Leather or Good Quality Tapestry with small pillow for V.V.I.P.S.	1.0	Nos.
53	Providing and Arranging in Raw of good quality Three Seater Soft in Leather or Good Quality Tapestry with small pillow for V.V.I.P.S.	1.0	Nos.
54	Providing and Fixing of 1 Mtr. Height Dedo Wall with both side cloth and Framing of Wooden / Steel using Weldmesh Jali, etc. complete.	1.0	Rmt.
55	Providing and fixing of Galvanised good quality Corrugated Sheets 0.8mm thick fixing required hight upto wall with framing in Wooden / Steel etc. complete.	1.0	Sq.mt

56	Providing and fixing of Barricat with 6 Perstance or any other P.V.C. pipe in horizontal 3 lines height pipe support fitting etc. complete as per requirement & instruction of EIC.	1.0	Rmt.
57	Providing and fixing of Barricat in steel / Alluminium Checkered grill fitted with 3 to 4.00 feet height with pipe support fitting / Wooden etc. complete as per requirement & instruction of EIC.	1.0	Rmt.
58	Providing and Arranging in Raw of Table (2' x 4') with laminated top sheet as per required & instruction of EIC.	1.0	Nos.
59	Providing and fixing of Steel moulding bed as per required & instruction of EIC.	1.0	Nos.
60	Providing Barrel for Water (Nala) 200 Ltr. Capacity as per required & instruction of EIC. (A) Galvanised./Alluminium / Brass / Iron / Steel / PVC	1.0	Nos.
61	Supplying Steel Barrel for Water (80 to 100 Ltr. Capacity) as per required & instruction of EIC.	1.0	Nos.
62	Supplying for Water tanker (5000 to 10000 Ltr. Capacity) as per required & instruction of EIC.	1.0	Nos.
63	Supplying and Fixing Wash Basin - Simple as per required & instruction of EIC.	1.0	Nos.
64	Supplying and Fixing Wash Basin - Brass-Copper- Fancy as per required & instruction of EIC.	1.0	Nos.
65	Supplying Platic Tub. (Large Size) (for used Dishes) as per required & instruction of EIC.	1.0	Nos.
66	Supplying Sintex tube as per required & instruction of EIC.	1.0	Nos.
67	Supplying Steel tube as per required & instruction of EIC.	1.0	Nos.
68	Supplying Seating Counter using Round Table with 10 person Capacity. The table cloth and Jool should be good quality.etc complete	1.0	Nos.
69	Providing and fixing Green Room plywood structure with required design and 18 mm thickness of plywood sheets or wooden planck frame for plywood with required design and thickness of plywood sheets with all material transportation scaffolding labour, required necessary gap etc complete.	1.0	Sq.mt
70	Providing and fixing Gree Room required M.S Frame Structure with required design and thickness with all material transportation scaffolding labour etc complete	1.0	Sq.mt
71	Making the surface level & dustproof, providing & fixing 6mm Thk. Model - SPLENDOUR - 100 Perstance BCF Polypropelene Carpet to be fixed on walls and floors. The rates shall include cost of all types of labour, material, transportation, etc. complete. (equivalent Brand DIVINE)	1.0	Sq.mt
72	Providing & Fixing Green Room of Armstrong Mineral Fibre Acoustical Suspended Ceiling System with Beauti Sky (Tegular) Edge Tiles With Armstrong 24mm Exposed GRID. tiles should have Humidity Resistance (RH) of 90 Perstance , NRC 0.5, Light Reflectance ≥80 Perstance , Thermal Conductivity k 0.052 - 0.057 w/m K, Colour White, Fire Performance UK Class 0 / Class 1 (BS 476) in module size of 600 x 600 x 14mm , suitable for Green Building application, with Recycled content of 34 Perstance . be laid on Armstrong Prelude 38 with 24 mm wide T section flanges color white having rotary stitching on all T sections i.e. the Main Runner, 1200 mm and 600 mm Cross Tees with a web height of 38mm and a load carrying capacity of 15.34Kgs/M2 and pull out strength of 100Kgs. The T Sections have a Galvanizing of 90 grams per M2 and need to be installed with Suspension system of Armstrong make.	1.0	Sq.mt
73	Providing and fixing curtain with all attachment in VVIP Green room good quality as per engineer in charge	1.0	Sq.mt
74	Providing and fixing standard attached door, Urinal, Washbasin, Europin Pan, dressing for VVIP Green room good quality required connect water tank, proper connection pipe, cock, sock pit, with all necessary attachment etc. complete as per engineer in charge.	1.0	Nos.
75	Providing Rostam having 10 ft. height using M.S. pre fabricated frame of M.S. pipe/ angle/ chanel with cross bressing and wooden top, 19 mm plywood flooring and cloth zool covering three sides of Rostam and back side covered with G.C.I. sheet with M.S. Framing Providing Zool railing and stair steps etc complete as directed.	1.0	Sq.mt
76	Providing Steel Benches - 5' x 2' size. as per required & instruction of EIC.	1.0	Nos.
77	Providing Steel Benches - 5' x 2' size with cloth and zool. as per required & instruction of EIC.	1.0	Nos.
78	Providing General urinal / Toilet. as per required & instruction of EIC.	1.0	Nos.
79	Providing Table cloth and zool up to 1 mt. height. as per required & instruction of EIC.	1.0	Nos.
80	Providing Ramp constructing and fixing ramp of any Size. as per required & instruction of EIC.	1.0	Sq.mt
81	Providing good quality White Umbrella for VVIP/VIP as per required & instruction of EIC.	1.0	Nos.
82	Providing good quality black Umbrella as per required & instruction of EIC.	1.0	Nos.
83	Supplying ISI Mark Himaliya Mineral Water in Glass Bottle for VVIP as per required & instruction of EIC.	1.0	Nos.
84	Supplying ISI Mark Himaliya 1 Lit. Mineral Water Bottle as per required & instruction of EIC.	1.0	Nos.
85	Supplying ISI Mark Himaliya 500 ml. Mineral Water Bottle as per required & instruction of EIC.	1.0	Nos.
86	Supplying ISI Mark Mineral Water 200 ml. Bottle (Cold) of Reputed Brand as per required & instruction of EIC.	1.0	Nos.
87	Supplying ISI Mark Mineral Water 250/300 ml. Bottle (Cold) of Reputed Brand as per required & instruction of EIC.	1.0	Nos.
88	Supplying ISI Mark Mineral Water 500 ml. Bottle (Cold) of Reputed Brand as per required & instruction of EIC.	1.0	Nos.
89	Supplying ISI Mark Mineral Water 1 Ltr. Bottle. (Cold) of Reputed Brand as per required & instruction of EIC.	1.0	Per Bottle
90	Supplying ISI Mark Mineral Water 20 Ltr. Jar (Cold) of Reputed Brand as per required & instruction of EIC.	1.0	Nos.
91	Providing good quality white Cloth Turkish Napkin 12x12 of Reputed Brand as per required & instruction of EIC.	1.0	Nos.
92	Providing good quality white Cloth Turkish Napkin 12x18 of Reputed Brand as per required & instruction of EIC.	1.0	Nos.
93	Providing good quality white Cloth Turkish full size Towel of Reputed Brand as per required & instruction of EIC.	1.0	Nos.
94	Providing ISI Standard Induction with Tea Making Kit of Reputed Brand as per required & instruction of EIC.	1.0	Nos.
95	Providing ISI Standard Electrick Kittle 1Lit. of Reputed Brand as per required & instruction of EIC.	1.0	Nos.
96	Providing Wet/ Dry Wipes big size packet of Reputed Brand as per required & instruction of EIC.	1.0	Nos.
97	Providing Silver Foil Roll of Reputed Brand as per required & instruction of EIC.	1.0	Nos.
98	Providing ISI standard N-95 Mask of Reputed Brand as per required & instruction of EIC.	1.0	Nos.
99	Providing ISI standard 3-ply Mask of Reputed Brand as per required & instruction of EIC.	1.0	Nos.
100	Providing ISI standard Steel Thermos Hot/Cold (Full size) of Reputed Brand as per required & instruction of EIC.	1.0	Nos.

101	Providing ISI standard Steel Thermos Hot/Cold (Medium size) of Reputed Brand as per required & instruction of EIC.	1.0	Nos.
102	Supplying Glass for Water/ Juice of Good Quality. (Borosil, Yera or equivalent) of Reputed Brand as per required & instruction of EIC.	1.0	Per 6 Nos.
103	Providing Service Tray (Steel, Brass, Wooden, PVC, etc.) of Reputed Brand as per required & instruction of EIC.	1.0	Nos.
104	Providing good quality Paper Napkin of Reputed Brand as per required & instruction of EIC.	1.0	Per 100 Nos.
105	Sanitizer Alcohol Base 100ML with Spray of Reputed Brand as per required & instruction of EIC.	1.0	Nos.
106	Supplying Green Tea/ Lamon Tea/ Black Tea/ Coffie etc. of Reputed Brand as per required & instruction of EIC.	1.0	Per 1 Packet
107	Supplying Standard Room Freshener of Reputed Brand as per required & instruction of EIC.	1.0	Nos.
108	Providing ISI Standard Good quality Dustbin Big of Reputed Brand as per required & instruction of EIC.	1.0	Nos.
109	Supplying Dispoisable Cup for Tee / Coffee (Bio Gradable) of Reputed Brand as per required & instruction of EIC.	1.0	Per 50 Nos.
110	Supplying Dispoisable Glass Water (Bio Gradable) of Reputed Brand as per required & instruction of EIC.	1.0	Per 50 Nos.
111	Supplying Dispoisable plate big size (Bio Gradable) of Reputed Brand as per required & instruction of EIC.	1.0	Per 12 Nos.
112	Providing Good Quality Paper Napkin Box of Reputed Brand as per required & instruction of EIC.	1.0	Nos.
113	Providing Good Quality Required Aircraft Toilet Kit. Etc. complete of Reputed Brand as per required & instruction of EIC.	1.0	Nos.
114	Providing Good Quality Tea Coster of Reputed Brand as per required & instruction of EIC.	1.0	Per 6 Nos.
115	Providing Freez for cold approx 50 Person as per required & instruction of EIC.	1.0	Nos.
116	Providing Good Quality of Glass Plate having Transparent Design (Imported) (1) Half size as per required & instruction of EIC.	1.0	Nos.
117	Providing Good Quality of Glass Plate having Transparent Design (Imported) (2) Full size as per required & instruction of EIC.	1.0	Nos.
118	Providing Good Quality of Glass Plate having Transparent Design (Imported) (3) Bowl as per required & instruction of EIC.	1.0	Nos.
119	Providing Good Quality of Glass Plate having Transparent Design (Imported) (4) Cup Saucer as per required & instruction of EIC.	1.0	Nos.
120	Providing Tepoy good quality (Glass, Formica, Sankheda, wooden, steel etc.) as per required & instruction of EIC.	1.0	Nos.
121	Providing Necessary pipe line fitting for disposing Rain water from Mandap. as per required & instruction of EIC.	1.0	Rmt.
122	Providing Manekchowk Gate 15 x 3 x 4 (fixing both side plywood and colour cotton cloth) wooden framinig covering all four Side selected shartin cloth including dismentalling the gate etc. complete as per site condition and as directed by Engineer-in-charge.	1.0	Rmt.
123	Providing high-end VIP portable fiberglass (FRP) chemical toilets for VIP/VVIPs. with Self-contained holding tanks,Hygiene and odor control,Premium fixtures,Durable shell etc. as per Instruction of EIC.	1.0	Nos.
124	Providing Chiffon cloth with chair cover (As per instucted symbol). as per required & instruction of EIC.	1.0	Nos.
125	Providing and fixing MOJO type barricade made from M.S. Angel Frame with G.I. Wire mesh jali of required height on hire charge including dismentaling the same after completion of the event including all transportation, carriage, lead and lift etc. complete as directed by engineer in charge.	1.0	Rmt.
126	Providing pole with Flag of various colour or Indian Flag with Required standard size and Required Material with all kind of Transporation,Fitting,Material and Labour etc.complete as per site condition and as directed by Engineer-in-charge.	1.0	Nos.
127	Providing Steel frame powder coated leather V.V.I.P chair set with back side cushion and cover .	1.0	Nos.
128	Providing and Fixing Takti of Approved size and Material with Wooden/MS laminated sheet takti stand and curtain for stone ceremony or inauguration with all kind of Material,Transportaion,Labor etc as per Engineer in Charge.	1.0	Sq.mt
129	Providing Paper silver coated dis As per required size.	1.0	Nos.
130	Providing Paper silver coated dariya (Cup) As per required size.	1.0	Nos.
131	Providing Designer Gate of necessary steel structure with cotton cloth cover all side with selected in any shape. of any height & site as per instruction of higher officers, Engineer-in-charge and site requirement.	1.0	Rmt.
132	Providing Decorative railing in both side stage & front of stage & both side of steps with coloured cloth covering as per instructions & requirement etc. comp. (A) Iron Railing.	1.0	Rmt.
133	Providing Decorative railing in both side stage & front of stage & both side of steps with coloured cloth covering as per instructions & requirement etc. comp. (B) Wooden Railing.	1.0	Rmt.
134	Providing Decorative railing in both side stage & front of stage & both side of steps with coloured cloth covering as per instructions & requirement etc. comp. (C) Steel or Brass Railing.	1.0	Rmt.
135	Providing & Fixing Faciya.	1.0	Sq.mt
136	Providing Multi Level Stage with steps/ramps of as required height for digniteries constructed with using pre-fabricated steel 'H' framed, supported Ghoda with square / round steel plate welded at bottom of H-Frame pipe for levelling and cross bressing each steel pipe member fixed properly with special Cup lock clamps on both side. The top has to be covered with 19mm thick Double layer Plywood in proper level and providing Fresh Red synthetic carpet flooring on stage steps and covering the cloth zool to four sides etc. complete as per site condition and instruction of Engineer-in-charge. (A) Stage upto 1.5 Mtr. Height.	1.0	Sq.mt
137	Providing Multi Level Stage with steps/ramps of as required height for digniteries constructed with using pre-fabricated steel 'H' framed, supported Ghoda with square / round steel plate welded at bottom of H-Frame pipe for levelling and cross bressing each steel pipe member fixed properly with special Cup Lock clamps on both side. The top has to be covered with 19mm thick Double layer Plywood in proper level and providing Fresh Red synthetic carpet flooring on stage steps and covering the cloth zool to four sides etc. complete as per site condition and instruction of Engineer-in-charge. (B) Stage upto 4.0Mtr. Height.	1.0	Sq.mt

138	Providing Multi Level Stage with steps/ramps of as required height for dignities constructed with using pre-fabricated steel 'H' framed, supported Ghoda with square / round steel plate welded at bottom of H-Frame pipe for levelling and cross bracing each steel pipe member fixed properly with special Cup Lock clamps on both side. The top has to be covered with 19mm thick Double layer Plywood in proper level and providing Fresh Red synthetic carpet flooring on stage steps and covering the cloth zool to four sides etc. complete as per site condition and instruction of Engineer-in-charge. (C) Stage upto 4.00 Mtr. Height.	1.0	Sq.mt
139	Providing Multi Level Stage with steps/ramps of as required height for dignities constructed with using pre-fabricated steel 'H' framed, supported Ghoda with square / round steel plate welded at bottom of H-Frame pipe for levelling and cross bracing each steel pipe member fixed properly with special Cup Lock clamps on both side. The top has to be covered with 19mm thick Double layer Plywood in proper level and providing Fresh Red synthetic carpet flooring on stage steps and covering the cloth zool to four sides etc. complete as per site condition and instruction of Engineer-in-charge. (C) Stage upto 6.00 to above Mtr. Height.	1.0	Sq.mt
140	Providing Designer Gate of necessary steel structure with Plywood, colour cotton cloth wooden framing cover all four side with selected satin cloth with dismantling and using other decorative material with flooring including necessary flowering arrangement, etc. of any height & site as per instruction of higher officers, Engineer-in-charge and site requirement.	1.0	Rmt.
141	Providing Wooden 2" to 3" Thick long Bamboo / Ballies using cross Bracing Mandap frame on Tadpatril/ Thick Plastic including fitting complete structure of water proof Mandap with Zool Patta. including necessary excavation fitting, up to 16' height etc. comp. as per instruction.	1.0	Rmt.
142	Providing Complete Steel Structure dome or triangular hanger type Mandap with RCC Foundation Base Plate, Nut-Bolt Fitting complete with zool in selected cloth in ceiling upto 14 ft. height.	1.0	Sq.mt
143	Providing Pillarless Mandap Iron Pipe Structure as directed in mandap upto 14 ft. height.	1.0	Sq.mt
144	Supplying and fixing of Wooden Ramp of 19mm thick plywood having upto 4 Ft. wide with good quality wooden frame including necessary bracing and support made on site with Red carpet including 3 ft. height wooden Railing on both side of Ramp with necessary clothing, etc. as per the instruction and site requirement. (A) upto 1.50 Mtr. height.	1.0	Rmt.
145	Supplying and fixing of Wooden Ramp of 19mm thick plywood having upto 4 Ft. wide with good quality wooden frame including necessary bracing and support made on site with Red carpet including 3 ft. height wooden Railing on both side of Ramp with necessary clothing, etc. as per the instruction and site requirement. (B) upto 4.00 Mtr. height.	1.0	Rmt.
146	Supplying and fixing of Wooden Ramp of 19mm thick plywood having upto 4 Ft. wide with good quality wooden frame including necessary bracing and support made on site with Red carpet including 3 ft. height wooden Railing on both side of Ramp with necessary clothing, etc. as per the instruction and site requirement. (C) upto 6.00 Mtr. and above height.	1.0	Rmt.
147	(A) Steel / SS Frame with Leather Seat Back Chair including cleaning and arranging on site as per the instruction of Engineer-in-charge.	1.0	Nos.
148	Providing Dias Table with Table Cloth and Zool. The Cloth and zool should be neat and clean and good quality.	1.0	Nos.
149	Providing Sound Stage as per required height.	1.0	Sq.mt
150	Providing Sound Tower made from steel structure 'H' frame stage as per required height.	1.0	Rmt.
151	Providing Video Shooting Tower as per requirement.	1.0	Rmt.
152	Providing and Fixing Wiremesh Jali.	1.0	Sq.mt
153	Providing Checking Room for Ladies.	1.0	Sq.mt
154	Providing 4 Mtr. High Steel Towers covered with Cloths for sound light system & security etc. complete.	1.0	Rmt.
155	Providing multi level display center as per requirement in size i.e. (Height width and length) with proper steel H frames.	1.0	Sq.mt
156	Providing Coloured Jute Urinals consisting Six Parts in each sufficient to maintain the privacy, etc. complete.	1.0	Nos.
157	Providing Waiters in standard dress as directed.	1.0	Nos.
158	Providing Waiters PRO Girls in standard dress as directed.	1.0	Nos.
159	Providing man power for unskilled persons / labour (Male / Female).	1.0	Nos.
160	Providing Water proof screen Side & Back Side in German Aluminium Dome as per requirement. The water proof Screen is good quality and neat and clean.	1.0	Sq.mt
161	Providing Name plate (Plastic/ Steel stripe/ Wooden with name writing) etc. complete as per requirement.	1.0	Nos.
162	Supplying Gulab with stick as per requirement & instruction.	1.0	Nos.
163	Supplying Flower mala (Lily and Gulab) as per requirement & instruction.	1.0	Nos.
164	Providing and Fixing Sofa Cover for Good Quality.	1.0	Nos.
165	Providing truss Mandap with necessary truss framing and selected cloth in roof & covering for truss.	1.0	Sq.mt
166	Providing Decorative Divi	1.0	Nos.
167	Providing Fresh Real Flower for Decoration of Front and Sides of Stages, Backdrop, Welcome Gate, Elevated Pathway, Stage Railing, Stair Railing, Podium, Khat Muhurat Place, Under LED Screen, On Tipoy or Any other Places with real flower, flower belt, flower toran & Flower bouquet for VIP/VVIP/CM/PM including all labour, materials, Transportation etc. Required as per Instruction of EIC.	1.0	Rmt.
168	Providing Artificial Flower for Decoration of Front and Sides of Stages, Backdrop, Welcome Gate, Elevated Pathway, Stage Railing, Stair Railing, Podium, Khat Muhurat Place, Under LED Screen, On Tipoy or Any other Places with real flower, flower belt, flower toran & Flower bouquet for VIP/VVIP/CM/PM including all labour, materials, Transportation etc. Required as per Instruction of EIC.	1.0	Rmt.
169	Providing Artificial flower pot for Tipoy	1.0	Nos.
170	Providing Real flower pot for Tipoy	1.0	Nos.
171	Providing Good Quality Real Flower Bouquet for welcome of VVIP's, small size	1.0	Nos.
172	Providing Good Quality Real Flower Bouquet for welcome of VVIP's, Big size	1.0	Nos.

173	Providing erecting metal detector wooden frame with all laour and materials etc. complete	1.0	Rmt.
174	Providing & Erecting Tin Shed, prefab Steel+A3 Structural framework consisting of 2" M.S. pipe vertical poles, 2" M.S. pipe rafters and 2" Purins, having roof 24 gauge galvanized sheet covered with Talpore/Agro net. Bottom of GI sheet covered with net & Clean cloth ceiling. all steel structure member painted with enamel paint. height of shed various from 12 to 20 feet as per instruction of Engineer in Charge.	1.0	Sq.mt
175	19mm Block Board platform properly laid on wooden Section Framework raised 4" to 9" above the ground in proper line and level VIP sitting area onn both side.	1.0	Sq.mt
176	Elevated pathway required with leading to the flag platform to be constructed using prefabricated H Frame Supports in 2"M.S. pipe having hight up to 3 to 5 feet with cross members fixed properly for stability. the top has to be covered with 18mm Block Board or plywood in proper level. including top & all four side of stage covered with neat & clean cloth as directed by Engineer in Charge.	1.0	Sq.mt
177	Providing and fixing wooden barricate having height 4 to 5 feet by using vertical poles and two horizontal wooden member or G.I. Pipe tied with vertical poles including making 0.45cm deep pit to fix the vertical pole including warping the cloth to vertical and horizontal pole etc. complete.	1.0	Rmt.
178	Decorating Flags in Satin Cloth fixed on 2" M.S. pipe properly painted. Having height 15 to 20 feet as per directed of Engineer in charge.	1.0	Nos.
179	Providing & Fixing wooden tables covered top & sides by decorative cloth.	1.0	Nos.
180	Providing & Fixing Solvent Printed Flax Design Banner or Signages or Hoardings of various Sizes including making, framing with M.S. Square pipe or any other Material and Labour Required as per instruction of EIC.	1.0	Sq.mt
181	Fixing all types of Flax / Banner of any size at place as directed by engineer in charge.	1.0	Sq.mt
182	M.S. Pipe Barricating with M.S. channel / Pipe vertical & horizontal supports properly bolted with painting in silver colour as directed by engineer in charge.	1.0	Rmt.
183	Providing and fixing German Aluminium Pegoda 6M.x6M. as directed by engineer in charge.	1.0	Nos.
184	Supply & installing of DCP Type - 5 Kg. Capacity Fire Extinguisher as per IS-2171 I.S.I mark with necessary fittings,transportation,Labour etc. Complete.	1.0	Nos.
185	Supply & installing of Water Co2 Type - 9 Ltr. Capacity Fire Extinguisher as per IS. A.I.S.I. Mark with necessary fittings,transportation,Labour etc. Complete.	1.0	Nos.
186	Fire Retardant Chemical Spraying and Application on Stage Area, Behind Stage Area, "D" Zone, Cultural Stage , Green Room Of PM/CM , Golden Pass Area, Press Area including submission of the necessary certificate as per Govt norms prior to function day with all kind of material,Labour etc as directed by engineer in charge.	1.0	Per Kg
187	Providing and Fixing Leminat Stall of any size as directed by engineer in charge.	1.0	Sq.mt
188	Preparing colourful cloth decoration (leria) Drapping in Dome & Cloth Partition as directed on cloth wall using satin colourful work including all labours and material, design as per directed.	1.0	Sq.mt
189	Providing and Fixing Q - Manager set as directed by engineer in charge.	1.0	Nos.
190	Providing Pet Tables or Tipoy as per Instruction of EIC.	1.0	Nos.
191	Providing Media Folder	1.0	Nos.
192	Provding Mud Flap	1.0	Nos.
193	Providing Gloves for Service Staff	1.0	Nos.
194	Designer For Graphic Designing for VVIP/VIP	1.0	1 Job.
195	Photo & Video Grapher	1.0	1 Job.
196	Drone Shoot By PHANTOM 4K PGI	1.0	1 Job.
197	Providing food VVIP for (Breakfast / High Tea) like 2-Juice, Hot Tea, Coffee, Green Tea, Black Tea, Milk, Dryfruits, 3-Dry Snacks, 3-Hot savoury, Dessert & Sweets, Fruits, required mineral water with all necessary serving plats, serving person in well dress, counter items accompniments as directed by committee or engineer incharge	1.0	Per Dish
198	Providing packed dish VVIP for (Lunch / Dinner) like 2-Starter, 1-Sweet, 2-Sabji, Paratha / Puri, Roti/Nan, 1-Namkeen, Dal-Rise/Curd-Biriyani, Salad, Butter milk, Mineral water with all necessary accompniments as directed by committee. or engineer incharge	1.0	Per Dish
199	Providing packed dish VVIP for snacks like cookies, Dryfruit kachories, sweet, packed Juice, Chocalates, Mineral water with all necessary accompniments as directed by committee.	1.0	Per Dish
200	Providing, fixing & arranging table on hire basis of minimum size 1.20 mtr x 0.60 mtr & counter covered with clothes and frills all around and top as directed,Tables with decorative Frills and Table covers.	1.0	Nos.
201	Providing & arranging wooden laminated office table on hire basis of size 0.90 mtr x 0.60 mtr/ 1.20 mtr x 0.60 mtr.	1.0	Nos.
202	GPS based total station survey of event venue/ ground & preparing necessary survey drawing covering all the details/objects of event venue and mandap arrangements including submission of auto cad drawing in DWG format & required number of color print outs in A1/A2 size	1.0	Sq.mt
203	Prov. & fixing of foger system (automatic water sprinkler system) on hire basis for cooling effect in Dome/Mandap For Public by providing flrxible pipe line and water sprinkler unit at specified internal in mandap with water tanker with pumping motor of required capcity to cover all mandap area and all labours and materials as directed by Engineer In Charge etc. comp. (System Shall be started 2hr before Hon'ble PM arrival Time). Required Certificate of water and system should be obtained from competent authorities.	1.0	Sq.mt
204	Providing, installing, arranging & dismantling after complition of program Q manager having brass pole & chains/inks covered with velvet type covering etc. complete.	1.0	Nos.
205	Providing,fixing, installing & dismantling after completion of program : metal detector frame on hire basis wooden frame as directed by engineer in charge.	1.0	Nos.
206	Providing ,erectiong and Dismantalling soundproof wall in PM/CM lounge AC Room as per Instructed of SPG /Other Officer Guideline including necessary material lie wooden /Ms framing, carpet cladding or any ,laboure and traspotration etc completed as per Requirement of SPG.	1.0	Sq.mt
207	Providing and Spraying Fire retardant Spray to All stage area,D Zone, Cultural stage, Green Room PM, VVIP area and all furnishing materials and Mandap as per NFPA with all labours as per Directed Engineer In-Charge.	1.0	Sq.mt
208	Creative wall branding digital Flex printing with designing star 350 GSM Black back material with Six Pass printing temporary structure MS Frame structure with installation	1.0	Sq.mt
209	Simple Wash basin as per requirement including necessary arrangement upto drainage connection.	1.0	Nos.

210	Providing and fixing wooden Ramp with required width and grade with proper framing with steel as per requirement.	1.0	Sq.mt
211	Stall 10' x 10' including necessary ballies fabricating all materials and labour as per requirement	1.0	Nos.
212	Prroviding,Supplying and Arranging walkie talkie with permission from concern quthorities as per required rang (Mini 5 km range) as directed by Engineer Incharge .	1.0	Nos.
213	Prroviding,Installing and Dismantalling after completion of programme Octanorm wall partition ancluding framing, material, tools and labour as required and directed by engineer in charge	1.0	Sq.mt
214	Providing and Installing Required Size of Entry and Exit gate for CM/PM with All necesaary Structures,fastenings,Fittings,Decoration,Security Sensors and other requirements and Materials as per VIP/VVIP/CM/PM Function Guidelines and As per Instruction of EIC.	1.0	Rmt.
215	Providing and Installing Required Size of Entry and Exit gate for VIP/VVIPs with All necesaary Structures,fastenings,Fittings,Decoration,Security Sensors and other requirements and Materials as per VIP/VVIP/CM/PM Function Guidelines and As per Instruction of EIC.	1.0	Nos.
216	Providing and Installing Required Size of Entry and Exit gate for General Public with All necesaary Structures,fastenings,Fittings,Decoration,Security Sensors and other requirements and Materials as per VIP/VVIP/CM/PM Function Guidelines and As per Instruction of EIC.	1.0	Nos.
217	Providing, Managing and Executing well-dressed Hostesses	1.0	Nos.
218	Providing and arranging for Anchor with speech scripted	1.0	Nos.
219	Providing and arranging Event Management Crew, Guest/artist Management, volunteers & ushers	1.0	Nos.
220	Event Managers	1.0	Nos.
221	Providing, printing and distribution of all area access cards lanyard	1.0	Nos.
222	Providing lanyard & Cover	1.0	Nos.
223	Photography & Videography of Event as per Instruction of EIC & Give all the Records of Photos and Videos in Color Hard Copy and Soft Copy as per Instruction of EIC.	1.0	1 Job.
224	Pre-event days Security services for entire day (5 security x 2 shift x 1 days)	1.0	Nos.
225	Making arrangements for security guards (10 Seucurity x 1 shift)	1.0	Nos.
226	Providing Pantry Kit for Green Room of VIP/VVIP/PM/CM as directed by EIC and as per Guidelines of Foods Departments.	1.0	per Kit

Executive Engineer
R & B Division
Morbi