

ગુજરાત રાજ્ય પોલીસ આવાસ નિગમ લિમિટેડ

::: ખાસ નોંધ :::

કામ શરૂ કરતા અગાઉ એજન્સીએ સ્થળ પર કામની વિગતો જેવી કે કામનું નામ, કામની અંદાજિત રકમ, કામની સમય મર્યાદા, કામ શરૂ કર્યાની તારીખ, કામ પૂર્ણ થવાની તારીખ, કોકીટ ગ્રેડ, વગેરે દર્શાવતું સાઇન બોર્ડ (સાઇન બોર્ડની લઘુત્તમ સાઇઝ ૬ X ૪ ફુટ) સાઇટના આગળના પ્રવેશ દ્વારા આગળ ઉભું કરવાનું રહેશે તથા જમીન લેવલથી સાઇન બોર્ડનું ટોપ ૭ ફુટ ઉંચું રાખવાનું રહેશે. જેના માટે અલાયદું કોઇ વધારાનું ચુકવણું કરવામાં આવશે નહીં.

	કામનું નામ :	:	
	ટેન્ડરની રકમ રૂ.	:	
	કામ શરૂ થવાની તારીખ	:	
	કામ પૂર્ણ થવાની નિર્ધારિત તારીખ	:	
	કામની સમય મર્યાદા	:	
	ઈજારદારશ્રીનું નામ અને સરનામું (ટેલિફોન નંબર સહિત)	:	
	<u>સ્ટ્રક્ચરનો પ્રકાર</u>		<u>દા.ત., (જી +૧) ફેમ સ્ટ્રક્ચર</u>
	<u>ટેન્ડરના સ્પેશીફિકેશન:</u>		
૧	ચણતર કામ	:	બ્રીક મેશનરી ૧:૬ ના પ્રમાણમાં
૨	કોંક્રીટ ગ્રેડ	:	પાયામાં M-25 જમીનની ઉપર M-25 રોડ M-30 જાડાઈ ૧૮ સેમી.
૩	પ્લાસ્ટર	:	૧૦ અને ૧૫ એમ.એમ.જાડાઈનું ૧:૪ ના માપમાં અંદરનું પ્લાસ્ટર ૨૦ એમ.એમ. જાડાઈનું ડબલ કોટ સેન્ડફેસ પ્લાસ્ટર બહારના ભાગે જેમાં ૧૨ એમ.એમ. ૧:૩ ના માપમાં પ્રથમ કોટ તથા ૮ એમ.એમ. ૧:૧ ના માપમાં બીજો કોટ
૪	ફ્લોરીંગ	:	વીટ્રીફાઈડ ટાઈલ્સ ડબલ ચાર્જ, બેડીંગ મોર્ટાર ૧:૬
૫	બારીઓ	:	એલ્યુમિનિયમ સેક્શન
૬	બારણાં	:	લાકડાની ફેમ તથા ફ્લશ ડોર
૭	કલર	:	અંદરનો કલર :પ્લાસ્ટીક પેઇન્ટ બહારનો કલર :એકેલીક પેઇન્ટ
૮	કુર્કીંગ પ્લેટફોર્મ	:	ટેલીફોન બ્લોક, ગ્રેનાઈટ પ્લેટ ફોર્મ
૯	કાર્યપાલક ઈજનેરશ્રીની કચેરીનું સરનામું (ટેલિફોન નંબર સહિત)	:	

SPECIAL Condition FOR RA & FINAL Bill

- 1) Agency has to give written inward application to corporation for running / final bill mentioning the work done by him, also give detail measurement sheet and relevant test certificates of materials. Corporation engineer verify specification of work done by contractor & also verify the measurement given by agency. For that agency has to remain present at site and give written confirmation about measurement and date of measurement and actual date of completion in measurement book and stamp and sign with date. Thereafter procedure of preparing of bill will be started.
- 2) Without written application and measurement sheet corporation engineer will not start the procedure for running / final bill.

ગુજરાત રાજ્ય પોલીસ આવાસ નિગમ લિમિટેડ

::: ખાસ નોંધ :::

બાંધકામમાં હાથ ધરવામાં આવતા વિવિધ પ્રકારની ટાઈલ્સના ફ્લોરીંગની કામગીરી હાથ ધરતી વખતે નક્શાઓમાં દર્શાવેલ વિગતે કે એન્જીનીયર ઈન્યાર્જ દ્વારા જણાવાયેલ વિગતોએ ફ્લોરીંગમાં લેવલ રાખવા અથવા સામાન્ય ઢાળ આપવાનો થાય તો આ અન્વયે ફ્લોરીંગ માટેની ગાદીની જાડાઈ વધઘટ થઈ શકે તેમ છે. સદર બાબત ટેન્ડરના ભાવ ભરતી વખતે ઈજારદારશ્રીએ ધ્યાને રાખી ટેન્ડર ભરવાનું રહેશે. આ પ્રકારની કામગીરી માટે ભાવ વધારાની માંગણી/એક્સ્ટ્રા આઈટમની માંગણી કોઈપણ સંજોગોમાં ધ્યાને લેવામાં આવશે નહીં જેની વિશેષ નોંધ લેવા વિનંતી.

ગુજરાત રાજ્ય પોલીસ આવાસ નિગમ લિમિટેડ

::: ખાસ નોંધ :::

ફ્લોરીંગનું કામ પુર્ણ થયા બાદ તેની ઉપર બીજી કામગીરી કરતી વખતે સ્કેચ તથા ખરાબ ન થાય તે સારૂ ફ્લોરીંગ પર પ્લાસ્ટર ઓફ પેરીસનું લેયર એજન્સીએ પોતાના ખર્ચે કરવાનું રહેશે. કબજો સોંપતા અગાઉ તેની સફાઈ પણ કરવાની રહેશે. તેના માટે કોઈ જાતનું અલગથી ચૂકવણું કરવામાં આવશે નહિ. જેની નોંધ લેવી.

ગુજરાત રાજ્ય પોલીસ આવાસ નિગમ લિમિટેડ

::: બાંધકામમાં વાપરવાના પાણી માટેની ખાસ શરતો :::

- ૧) બાંધકામ માટે પાણીના વપરાશ સારૂ પોલીસ ખાતા હસ્તકની જમીન ઉપર જો બોર બનાવેલ હોય તો તે બોરવેલ કામ પૂર્ણ થાય ત્યારે બોર માંથી પમ્પીંગ મશીનરી કાઢી લઇ કેસીંગ પાઇપ સહિત બોરની ઉપર કેપ લગાવી વિના મૂલ્યે સ્થાનિક લાઇન જમાદારને કબજો સોંપવાનો રહેશે તથા નિગમને ઇજારદારશ્રીએ જાણ કરવાની રહેશે. આ બોર માટે ઇજારદારશ્રીને કોઇ પણ પ્રકારનું ચુકવણું કરવામા આવશે નહીં.
- ૨) બોરવેલ બનાવવામાં આવે ત્યારે ઇજારદારશ્રી પાસેથી બનાવેલ બોરવેલના તમામ ડેટા લેખીતમાં મેળવવા તથા બોરની તમામ કામગીરીનું સુપરવીઝન નિગમના અધિકારીશ્રીઓ તરફથી કરવાની રહેશે.
- ૩) બાંધકામ અંતિમ તબક્કામાં હોય ત્યારે બોરવેલનો ડીસચાર્જ માપવો તથા પાણીનું સેમ્પલ મેળવી તેપાણી પીવાલાયક છે કે કેમ ? તે અંગેનું ટેસ્ટીંગ IS : 10500 મુજબ નિગમના સ્વખર્ચે કરાવવું.
- ૪) બોરવેલનું લોકેશન સમ્પ/પમ્પરૂમથી શક્ય તેટલું નજદીક રાખવું.
- ૫) ઇજારદારશ્રી તરફથી કામગીરી પૂર્ણ કરાયા બાદ ઇજારદારશ્રીએ પોતાનો પમ્પ સ્વખર્ચે કાઢીને લઇ જવાનો રહેશે. તથા બોર સારી હાલતમાં નિગમ હસ્તે સ્થાનિક પોલીસ અધિકારીશ્રીને સોંપવાનો રહેશે. બોરને સ્થાનિક લોકો કે વ્યક્તિઓ દ્વારા ચેડા કે નુકશાન ન થાય તે રીતે સોંપવાનો રહેશે.

ગુજરાત રાજ્ય પોલીસ આવાસ નિગમ લિમિટેડ

::: આર.સી.સી. કામમા કન્સ્ટ્રક્શન જોઇન્ટ તથા પ્લાસ્ટીસાઇઝર અંગેની શરત :::

- બાંધકામમાં આર.સી.સી. કામમા નવા અને જુના કોક્રીટ વચ્ચે પડતા કોલ્ડ જોઇન્ટ્સ માન્ય ઉત્પાદક કંપનીની ભલામણ અનુસાર ના પ્રમાણમા સીમેન્ટ સાથે એકેલીક પોલીમર મિશ્રણ કરેલ સ્લરી એપ્લાય કરવાની રહેશે. જેમનુ અલગથી પેમેન્ટ કરવાનુ થશે નહીં જે કોક્રીટ કામના ભાગરૂપે જ ગણવાનુ રહેશે.
- બાંધકામમાં કરવાની થતી કંટ્રોલ કોક્રીટની આઇટમોમા સમાવિષ્ટ પ્લાસ્ટીસાઇઝર માટે માન્ય ઉત્પાદક કંપનીનુ પ્લાસ્ટીસાઇઝર વાપરવાનુ રહેશે. તથા તે પ્લાસ્ટીસાઇઝરનો ઉપયોગ પ્રતિ સીમેન્ટ બેગે ૩૦૦ એમ.એલ. અથવા મિક્ષ ડીઝાઇનમા જણાવ્યા મુજબ બંને માથી જે વધારે હોય તેનો ઉપયોગ કરવાનો રહેશે. જેનુ અલગથી ચૂકવણું કરવામા આવશે નહીં.

ગુજરાત રાજ્ય પોલીસ આવાસ નિગમ લિમિટેડ

...ઇંટો માટેની શરતો...

- (૧) સદર કામના બાંધકામમા ફોગ વાળી જ ઇંટો વાપરવા દેવામાં આવશે .
- (૨) ફોગ વાળી ઇંટો ઁજીનીયર ઇન્ચાર્જ પાસે અગાઉ મંજૂર કરાવી લેવાની રહેશે .
- (૩) ફોગ વાળી ઇંટો જો સ્થાનિક કક્ષાઁથી ઉપલબ્ધ થાય તેમ ન હોય તો આગોતરી મંજૂરી સાથે અન્ય જીલ્લામાંથી લાવી વાપરવાની રહેશે .
- (૪) બ્રીક મેશનરીની કામગીરી ઉપર જણાવ્યા પ્રમાણેની ફોગ વાળી ઇંટો માટે કોઇ પણ પ્રકારનો ભાવ વધારો મંજૂર કરવામા આવશે નહીં .
- (૫) આ કામમાં યણતરમાં ઉપર જણાવ્યા મુજબની ઇંટો માટેની ખાસ શરતો મુજબ ઇંટોથી યણતર કામ કરવાનુ રહેશે તથા કોઇ પણ સંજોગોમા ઇંટોની અછત અન્વયે યણતર કામમાં ઇંટોના સ્થાને અન્ય વૈકલ્પિક જોગવાઇ આપવામાં આવશે નહીં. તેમજ તે અંગે સમયવધ પણ આપવામાં આવશે નહિ તેની ખાસ નોંધ લેવી.
- (૬) ઇંટો ફોગવાળી તેમજ ટેકનીકલ સ્પેશીફીકેશન બુકના પાના નં ૧૬ ક્રમ નં ૭ માં દર્શાવેલ બધા જ પેરામીટર (ટેસ્ટ) મુજબની ઇંટો લાવાવાની રહેશે.

ગુજરાત રાજ્ય પોલીસ આવાસ નિગમ લિમિટેડ

SPECIAL CONDITIONS FOR CONTROLLED CEMENT CONCRETE

- 1 Controlled cement concrete has to be used for all RCC work. The contractor has to use the materials i.e. sand, Kapchi, cement etc. from selected source. The contractor has to get mix design done, either from GERI or any government laboratory approved by G.S.P.H.C. Ltd. After submitting and getting approval of the same from concerned Executive Engineer shall immediately start the mix design and no extra time shall be permitted.
- 2 Once mix design is approved, the materials must be used from the mentioned selected source has to be changed, then contractor has to get approval of mix design again at his own expense. For this extra time shall be permitted.
- 3 During mix design. For different grades of concrete maximum water cement ratio and minimum cement content as per IS – 456:2000, given below must be taken care of. The cement content must not be less than that mentioned below.

Concrete Grade	Maximum water cement Ratio	Minimum cement content Kg/m ³
M-150	0.60	290
M-200	0.55	360
M-250	0.50	380
M-300	0.45	410

- 4 During execution contractor has to install a batching plant/ weight batch in good condition at site. The contractor has to do its necessary calibration by his own expense. The contractor has to ensure that the batching plant/ weight batch must work properly during the entire work.

ગુજરાત રાજ્ય પોલીસ આવાસ નિગમ લિમિટેડ

વિષય- કોંક્રીટ કામ માટે READY MIX CONCRETE RMC ની વાપરવા માટે ની સુચનાઓ

(૧) ઈજારદારશ્રી ને સાઈટ ઉપર જરૂરીયાત મુજબ નો કુલ્લી ઓટોમેટીક,અને પુરતી ક્ષમતા વાળાપ્લાન્ટનીસ્થાપના કરવાની રહેશે.

(૨) જો સાઈટ ઉપરપ્લાન્ટ સ્થાપીતકરવા માટેપુરતી જગ્યાઉપલબ્ધન હોય તો ટેન્ડર જોગવાઈ મુજબ કુલ્લી ઓટોમેટીક **RMC** પ્લાન્ટની પસંદગી કરવાની થશે . જે કંપનીના **RMC** પ્લાન્ટનું કોંક્રીટ વાપરવાનું થાય તે પ્લાન્ટની સંબંધિત કાર્યપાલક ઈજનેરશ્રી ધ્વારા સ્થળ વિઝિટ કરી **RMC** માટેના માલસામાન જેવા કે રેતી,કપચી,ગ્રીટ,સિમેન્ટ ,પાણી તથા એડમીક્ષરની ગુણવત્તા બાબતે જરૂરી ખરાઈ કરાવવાની રહેશે તથા તે માલસામાન ટેન્ડર જોગવાઈ મુજબનો છે તે પ્રમાણિત કરવાનું રહેશે .

(૩) **RMC** પ્લાન્ટમાંથી કોંક્રીટનો જથ્થો મેળવતા પહેલાં કાચા માલસામાનનું એટલે કેરેતી ,કપચી ,ગ્રીટ,સિમેન્ટ,પાણી તથા એડમીક્ષરનું જરૂરી પરીક્ષણ ટેન્ડર જોગવાઈ મુજબ કરાવવાનું રહેશે તથા **RMC** પ્લાન્ટમાંથી મેળવેલ વપરાયેલ કોંક્રીટના જથ્થા માટે ટેન્ડર જોગવાઈ મુજબના સી.સી. કયૂબ બાંધકામની સાઈટ પર કાસ્ટ કરાવી નિયમોનુસાર પરીક્ષણ કરાવવાના રહેશે .

(૪) **RMC** પ્લાન્ટ ધ્વારા વાપરવાનો થતો સિમેન્ટ ટેન્ડર જોગવાઈ અન્વયેની માન્ય ઉત્પાદક કંપનીનો **OPC53** ગ્રેડનો જ હોય તે અંગેની જરૂરી ચકાસણી સંબંધિત કાર્યપાલક ઈજનેરશ્રીનેકરાવવાની રહેશે .

(૫) **RMC** થી કોંક્રીટ કામગીરી થાય ત્યારે જે તે કોંક્રીટ કામગીરીમાં **RMC**પ્લાન્ટ પરથી વપરાયેલ કુલ સિમેન્ટનો જથ્થો (કિલોગ્રામ પ્રમાણિત કરી તે મુજબનો સિમેન્ટ વપરાશ બેગના જથ્થા મુજબ) દૈનિક સિમેન્ટ વપરાશ રજીસ્ટરમાં આકારવાનો રહેશે .

(૬) **RMC** પ્લાન્ટની પસંદગી કરતી વખતે પ્રતિસ્થિત કંપનીના પ્લાન્ટ જેવા કે અલ્ટ્રાટેક,બીપીસી ,એલ એન્ડ ટી ને જ પસંદગી આપવાની રહેશે . તે સિવાયના **RMC** પ્લાન્ટની પસંદગી કરતા પહેલાં વડી કચેરીની પૂર્વ મંજૂરી મેળવવાની રહેશે તથા **RMC**ની પ્રત્યેક ટ્રીપ સાથે વે — બેચર કોમ્પ્યુટરાઈઝ સ્લીપ મેળવી તેનો રેકૉર્ડ જાળવણી કરવાનો રહેશે .

(૭) **RMC** પ્લાન્ટમાંથી મેળવી જે કોંક્રીટ કામ કરવામાં આવે તે કોંક્રીટ જથ્થામાં વપરાયેલ સિમેન્ટના જથ્થા માટે સ્ટાર રેટનું ચુકવણું ટેન્ડર જોગવાઈ મુજબ જ કરવામાં આવશે .

ગુજરાત રાજ્ય પોલીસ આવાસ નિગમ લિમિટેડ

::: ખાસ નોંધ :::

સદર કામમા હાથ ધરવાની થતી કોટા ફ્લોરીંગ તેમજ કોટા સ્કર્ટિંગની આઇટમ માટે ઈજારદારશ્રીએ સૌ પ્રથમ એક સેમ્પલ તૈયાર કરવાનુ રહેશે જેમા તેઓ દ્વારા પ્રી-પોલિશ કોટા સ્ટોન લાવી, સ્થળ પર ટેન્ડરના સ્પેસીફિકેશન મુજબ પોલિશિંગની કામગીરી હાથ ધરી, ટેન્ડર આઇટમ મુજબ ફાઇનલ ફિનિશિંગ (Mirror Polished) આપવાની રહેશે.

વધુમા પ્રોજેક્ટ પૂર્ણ થાય / સોપણી સમયે Engineer in Charge દ્વારા અગાઉ મંજુર કરવામા આવેલ સેમ્પલ મુજબ Mirror Polish ની કામગીરી કરી આપવાની રહેશે.

ગુજરાત રાજ્ય પોલીસ આવાસ નિગમ લિમિટેડ

::: ઇજારદારશ્રી માટે વિશેષ નોંધ :::

ઉપરોક્ત ટેન્ડર આઇટમોના ભાવો ભરતી વખતે ઇજારદારશ્રી એ નીચેની બાબતોની ખાસ નોંધ લેવી.

- દરેક બિલ્ડીંગને બાંધકામને લગત માલ સામાન બાંધકામની પ્રવૃત્તિ દરમિયાન લીફ્ટની વ્યવસ્થાથી પહોંચાડવાનો રહેશે.
- બાંધકામના સમય દરમિયાન આજુબાજુ સંલગ્ન મકાનના રહીશો અને મકાનોને અડચણરૂપ, ખલેલઅને નુકશાન ન પહોંચે તે માટેના તમામ સાવચેતીના પગલા ઇજારદારશ્રીએ તેમના ખર્ચે અને જોખમે લેવાના રહેશે.
- ટેન્ડર ભરતી વખતે ઇજારદારશ્રી દ્વારા પોતઆનુ ઇ-મેઇલ આઇ.ડી. તેમજ મોબાઇલ નંબર ફરજિયાત ભરવાનો રહેશે.
- ઉક્ત બાંધકામમાં કોફિટનુ મિશ્રણ મિક્સર મશીન થકી જ કરવાનુ રહેશે. બાંધકામમાં તમામ કંટ્રોલ કોફીટની કામગીરી માટે વે-બેયર ફરજિયાત ઉપયોગ કરવાનો રહેશેતથા આ અત્રે કોઇ પણ જાતનુ ચુકવણુ કરવામાં આવશે નહીં. ડીઝીટલવે-બેયર ૧ બેગની ક્ષમતા તથા લઘુતમ ૨ બીન ધરાવતુ હોવુ જોઇએ. ડીઝીટલવે-બેયરમાં ઇલેક્ટ્રોનિક પેનલ્સ તથા મોટર પમ્પ જોડી શકાય અને છુટા કરી શકાય તેવા હોવા જોઇએ જેથી મિક્સ ડીઝાઇન મુજબનુ એગ્રીગેટનુ વજન થઇ શકે અને વોટર સિમેન્ટ રેશીયામુજબ નિયત કરેલ પાણીનો જથ્થો કંટ્રોલ કરી શકાય.

ગુજરાત રાજ્ય પોલીસ આવાસ નિગમ લિમિટેડ

::: કામની સાઇટ પર કાળજી તેમજ યુસ્ત તકેદારી રાખવા બાબતોની ખાસ નોંધ :::

- (૧) કોકીટીંગ કામ શરૂ કરતા પહેલા વેબેયરનુ કેલીબ્રેશન તેમજ પેનલ વિગેરે કાર્યરત છે કે નહી તેની ખાતરી કરવી, તેમજ મીક્ષ ડિઝાઇન મુજબ મટીરીયલ સ્થળ પર ઉતારવાનો રહેશે.
- (૨) ચાલુ કોન્ક્રીટીંગ કામગીરી દરમ્યાન પાણીની યોગ્ય માત્રા માટેના માપ રાખી વોટર સીમેન્ટ રેસીયો જાળવવાનો રહેશે.
- (૩) રેતી સ્કીનીંગ કરી તથા પાણીથી ઘોચા બાદ કોકીટીંગ કામમાં ઉપયોગમાં લેવી જરૂરી છે.
- (૪) સી.સી. ક્યુબ ના સેમ્પલનુ ક્યોરીંગ પ્લીસ્ટીક ડ્રમમાં કરવુ યોગ્ય નથી જેથી ક્યોરીંગ ટેન્કબનાવી સી.સી.ક્યુબના સેમ્પલનુ ક્યોરીંગ કરવા જણાવવામાં આવે છે.
- (૫) કોકીટીંગ કામ દરમ્યાન સ્લમ્પ ટેસ્ટ કરી રજીસ્ટર મેઇન્ટેન કરવા જણાવવામાં આવે છે.
- (૬) આર.સી.સી. મેમ્બર્સ / કોલમોમાં ડેટ ઓફ કાસ્ટીંગ ગ્રેડ ઓફ કોકીટ વિગેરે ઓઇલ પેઇન્ટથી માર્ક કરવા જણાવવામાં આવે છે.
- (૭) શટરીંગ કામ દરમ્યાન તીરાડો વાળા લાકડાના પાટીયા ઉબડખાબડ લોખંડના ફર્મા ના વપરાય તે અંગે તકેદારી રાખવા જણાવવામાં આવે છે.
- (૮) આર.સી.સી. મેમ્બર્સ જેવા કે કોલમ, બીમ, પદડી, વિગેરેમાં કાસ્ટીંગ બાદ કોકીટીંગ બાદ કોકીટમાં હની કોમ્પીંગ જોવા મળે છે, જ્યાં પણ આ પ્રકારે મુદ્દો ઉદભવે ત્યારે ટી.એ.ક્યુ.એ. કન્સલટન્ટ સાથે જે તે કોકીટ મેમ્બર્સનુ નિરિક્ષણ કરવુ તથા કોકીટ સ્પોટનુ યોગ્ય એન.ડી.ટી. પરીક્ષણ કરાવવુ જરૂરી બને છેકે કેમ? તે નક્કી કરવુ એન.ડે.ટી. પરીક્ષણ જણાતુ ન હોય તો તેવી બાબત આપના તથા ટી.એ.ક્યુ.એ. કન્સલટન્ટદ્વારા નક્કી કર્યા બાદજ આવા હની કોમ્પીંગના ભાગ ઉપર રીચ મોર્ટારમાં કેમીકલ ઉમેરી ફીનીશીંગ કરવા જણાવવામાં આવે છે.
- (૯) કોલમ તથા બીમ ની રીંગો બાંધતી વખતે હુકલેન્થ તથા હુક એંગલ સ્ટ્રકચરલ નક્શા મુજબ જાળવીકામ કરવા તકેદારી રાખવી.
- (૧૦) કોલમોમાં સળીયામાં ઓવરલેપીંગ સ્ટ્રકચરલ નક્શા મુજા સ્ટ્રગર રાખી કામગીરી કરાવવા જણાવવામાં આવે છે.

ગુજરાત રાજ્ય પોલીસ આવાસ નિગમ લિમીટેડ

ખાસ નોંધ

સદર બાંધકામમાં સ્થાનિક ઓથોરીટી (નગરપાલિકા વગેરે) માં બાંધકામ મંજૂરી અંગેની તમામ લાયઝનીંગ તેમજ સદર બાંધકામ માટે પાણીના તથા ગટરનાં કનેક્શન માટેનું તમામ લાયઝનીંગ ઇજારદારશ્રીએ કરવાનું રહેશે. તેમજ ફાયર ફાયટીંગની એન ઓ સી માટે પણ જરૂરી લાઇઝનીંગ ઇજારદારશ્રીએ કરવાનું રહેશે આ માટે જરૂરી દસ્તાવેજો નિગમ દ્વારા પૂરું પાડવામાં આવશે તથા નિયમ મુજબ કનેક્શન ચાર્જ / વિકાસ ચાર્જ નિગમ દ્વારા ભરપાઈ કરવામાં આવશે.

ગુજરાત રાજ્ય પોલીસ આવાસ નિગમ લિમિટેડ

::: ખાસ નોંધ :::

બહારના પ્લાસ્ટરની કામગીરી કરતી વખતે પ્લાસ્ટરની કામગીરી કરવા માટે H-ફ્રેમનો ઉપયોગ કરવાનો રહેશે. લાકડાની પાલકથી પ્લાસ્ટરની કામગીરી કરવી નહીં.

ગુજરાત રાજ્ય પોલીસ આવાસ નિગમ લિમીટેડ

ખાસ નોંધ

મકાન અને અન્ય બાંધકામ શ્રમયોગીઓ(રોજગારીનું નિયમન અને નોકરીની શરતો) અધિનિયમ, ૧૯૮૬ (The BOCW Act 1996) અને ધી કોન્ટ્રાક્ટ લેબર (રેગ્યુલેશન એન્ડ એબોલિશન)Act1970 બંને કાયદા અલગ છે અને તેનું અમલીકરણ અનુક્રમે શ્રમ અને રોજગાર વિભાગના તાબા હેઠળની નિયામકશ્રી, ઔદ્યોગિક સલામતી અને સ્વાસ્થ્યની કચેરી અને શ્રમ નિયામકશ્રીની કચેરી દ્વારા કરાવવામાં આવે છે. મકાન અને અન્ય બાંધકામ શ્રમયોગીઓ (રોજગારીનું નિયમન અને નોકરીની શરતો) અધિનિયમ, ૧૯૮૬ (The BOCW Act 1996) ની કલમ-૧(૪) મુજબ જે સંસ્થામાં (બાંધકામ સાઈટ પર) વર્ષમાં કોઈપણ એક દિવસે મકાન અને અન્ય બાંધકામમાં ૧૦ કે તેથી વધુ બાંધકામ શ્રમિકોને કામે રાખવામાં આવેલ હોય તેવી તમામ સંસ્થાને આ કાયદો લાગુ પડે છે. નાયબ નિયામકશ્રી, ઔદ્યોગિક સલામતી અને સ્વાસ્થ્યની કચેરી ખાતેથી લાગુ પડતા જીલ્લા માટે મેળવવાના રહેશે.

ઈજારદારને બ્લેકલિસ્ટ કરવા અંગેની જોગવાઈ

નિગમના SBD ની ક્લોઝ નં.- 58 મુજબ નિગમ જે-તે કામના ટેન્ડરને ટર્મિનેટ કરવા ઉપરાંત માર્ગ અને મકાન વિભાગના પરીપત્ર નં.- ક.પ-૪૦/ખપત/૫૦૭૩/સી-૬૨૦૭૪(૧૧૨)-સી, તા. ૦૪/૧૧/૧૯૮૬ મુજબ તથા નિગમના મેનેજીંગ ડીરેક્ટરશ્રીને મળેલ સત્તાની રૂએ ઈજારદારને કાળીયાદી(બ્લેકલિસ્ટ)માં મુકવા અંગેની તમામ સત્તા નિગમ અબાધીત રાખે છે. જે મુજબ ઈજારદારશ્રીને જે-તે કામમાંથી છુટા (ટર્મિનેટ) કરવા ઉપરાંત બ્લેકલિસ્ટ કરવા અંગેની તમામ સત્તા નિગમના મેનેજીંગ ડીરેક્ટરશ્રી પાસે રહેશે તથા જે-તે ઈજારદારશ્રીને તે બંધનકર્તા રહેશે.

Submission of P.F Registration Certificate & Monthly Challans towards proof of deposit of P.F. dues :

- Contractor has to submit copy of P.F Registration Certificate at the Time of Submission of 1st (R.A) Bill to the concerned Divisional Office of the Corporation.
- Along with every running bill and with final bill the contractor shall be required to submit copy of monthly challans as proof of payment of P.F. dues with the appropriate authority in respect of all the persons engaged by the contracting agency for the work of the corporation. In case of non-submission, no payment towards running / final bill will be released. Payment will be released only after submission of satisfactory proof towards payment in this regard by the contracting agency.

ગુજરાત રાજ્ય પોલીસ આવાસ નિગમ લિમિટેડ

ખાસ સુચના

- ૧ કરોડથી નીચેના કામો માટે સી.સી. ક્યુબના ૧૦% પરીક્ષણો ગેરી, ૪૦ % પરીક્ષણો સરકારી ઇજનેરી કોલેજો / સરકારી પોલિટેકનીક / અન્ય સરકારી સંસ્થાઓ અને બાકીના ૫૦ % પરીક્ષણો સરકાર માન્ય ખાનગી લેબોરેટરીમાં કરાવવાના રહેશે.
- ૧ કરોડથી ઉપરના કામો માટે સી.સી. ક્યુબના ૧૦% પરીક્ષણો ગેરી, ૪૦ % પરીક્ષણો સરકાર માન્ય ખાનગી લેબોરેટરી / સરકારી ઇજનેરી કોલેજો / સરકારી પોલિટેકનીક જેવી સંસ્થાઓ પાસે કરાવવાના રહેશે અને બાકીના ૫૦ % પરીક્ષણો સાઇટ ઉપર સ્થાપિત કરેલ લેબોરેટરીમાં કરાવવાના રહેશે. સાઇટ ઉપર જે પરીક્ષણો કરાવવામાં આવે તેવા પરિણામોની ટેસ્ટિંગ રજીસ્ટરમાં નિયમોનુસાર નોંધ કરાવવાની રહેશે. તેમજ તે પરીક્ષણો રનિંગ / ફાઇનલ બીલ સાથે રજૂ કરવાના રહેશે.
- સદર કામમા વાપરવાના થતા સી.સી. ક્યુબ સિવાયના બાકીના તમામ મટેરીયલ્સના ૧૦% પરીક્ષણો ગેરી, ૪૦ % પરીક્ષણો સરકારી ઇજનેરી કોલેજો / સરકારી પોલિટેકનીક / અન્ય સરકારી સંસ્થાઓ અને બાકીના ૫૦ % પરીક્ષણો સરકાર માન્ય ખાનગી લેબોરેટરીમાં કરાવવાના રહેશે.

ગુજરાત રાજ્ય પોલીસ આવાસ નિગમ લિમિટેડ

::: ખાસ નોંધ :::

ઉપરોક્ત કામમા વાપરવાના થતા માલ સામાન ટેન્ડરની જોગવાઈ મુજબ **Geri, Government Engineering College, Government Polytechnic College** અથવા નિગમ દ્વારા માન્ય કરવામા આવેલ ઇજનેર પ્રયોગશાળામા પરિક્ષણ કરવાના થાય છે. આ માટે નિગમના અધિકારી / ઇજનેર દ્વારા સાઇટ ઉપર લાવવામા આવેલ માલ સામાન ના નમૂના પરિક્ષણ અર્થે પસંદ કરવામા આવેથી આવા માલ સામાનના નમૂના પરિક્ષણ અર્થે નિગમના અધિકૃત ઇજનેર / અધિકારીઓ દ્વારા સૂચવવામા આવતા એન્જીનીયરીંગ પ્રયોગશાળામાં પહોંચાડવા અર્થે નિગમના સાઇટ ઇજનેર અને જરૂરી સહયોગ આપી નિગમના ઇજનેર સાથે આવો માલ સામાન પ્રયોગશાળામાં ઇજારદારશ્રીએ પહોંચાડવાનો રહેશે.

ગુજરાત રાજ્ય પોલીસ આવાસ નેગમ લિ.,ગાંધીનર

ક્રમ	કામનો પ્રકાર	ફરજીયાત કરાવવા જેવા ટાઈલ્સના ટેસ્ટીંગની વિગતો અને ટાઈલ્સના નંબર			
		500X500 mm (Double Charged Vitrified Floor Tiles) thickness (Min 8mm)	ટાઈલ્સ નંબર	500X300 mm (Ceramic Wall Tiles) thickness (Min 6mm)	ટાઈલ્સ નંબર
૧	૨૦૦ સ્કવેર મીટર કરતા ઓછો ફ્લોરીંગ વિસ્તાર હોય તેવા કામો	Water Absorption	૬	Water Absorption	૬
૨	૨૦૦ થી ૧૦૦૦ સ્કવેર મીટર જેટલો ફ્લોરીંગ વિસ્તાર હોય તેવા કામો	Water Absorption Modulas of Rupture Breaking Strength Bulk Density Surface Abrasion	૧૬	Water Absorption Modulas of Rupture Breaking Strength Bulk Density Surface Abrasion	૧૬
૩	૧૦૦૦ સ્કવેર મીટરથી ૨૫૦૦ સ્કવેર મીટર જેટલો ફ્લોરીંગ વિસ્તાર હોય તેવા કામો	Water Absorption Modulas of Rupture Breaking Strength Bulk Density Surface Abrasion Impact Resistance Thermal Expasion	૨૩	Water Absorption Modulas of Rupture Breaking Strength Bulk Density Surface Abrasion Impact Resistance Thermal Expasion	૨૩
૪	૨૫૦૦ સ્કવેર મીટરથી ૫૦૦૦ સ્કવેર મીટર જેટલો ફ્લોરીંગ વિસ્તાર હોય તેવા કામો	Water Absorption Modulas of Rupture Breaking Strength Bulk Density Impact Resistance Thermal Expasion Scratch Hardness of surface (Moh's Scale) Dimension Thickness of tile	૩૧	Water Absorption Modulas of Rupture Breaking Strength Bulk Density Surface Abrasion Impact Resistance Thermal Expasion Crazing Resistance Scratch Hardness of surface (Moh's Scale) Dimension Thickness of tile	૪૦
૫	૫૦૦૦ સ્કવેર મીટર કરતા વધારે ફ્લોરીંગ વિસ્તાર હોય તેવા કામો	Water Absorption Modulas of Rupture Breaking Strength Bulk Density Dimension Thickness of tile Straightness of sides Rectangularity Surface of Flatness Deep Abrasion Thermal Shock Resistance Resistance to chemical to glazed Tiles/ 7 reagents Scratch Hardness Impact Resistance Moisture Expasion Thermal Expasion	૪૭	Water Absorption Modulas of Rupture Breaking Strength Bulk Density Surface Abrasion Impact Resistance Thermal Expasion Thermal Shock Resistance Crazing Resistance Scratch Hardness Dimension Thickness of tile Surface Quality Resistance to chemical to glazed Tiles/ 7 reagents Resistance to staining Glazed Tiles/2 Strain	૫૨

ગુજરાત રાજ્ય પોલીસ આવાસ નિગમ લિમિટેડ

::: વિશેષ નોંધ :::

“આ કામના અંતિમ બીલમાં ઇજારદારશ્રીએ એક્સ્ટીરીઅર એકેલીક પેઇન્ટ માટે ટેન્ડરમાં ઉલ્લેખ કરેલ કંપનીનું ૦૫ વર્ષનું વોરંટી કાર્ડ મેળવી અવશ્ય બિડવાનું રહેશે તથા સાથોસાથ ૩૦૦/- રૂપિયાના સ્ટેમ્પ પેપર પર આ બાબતે બાંહેધરી પણ આપવાની રહેશે.” ૦૫ વર્ષનું વોરંટી કાર્ડ પુરૂ પાડવામાં નહીં આવે તો ટેન્ડરની સંબંધિત તે આઇટમનું કોઇ ચુકવણું કરવામાં આવશે નહીં.

નિગમના બાંધકામોમાં થયેલ બાહ્ય કલર કામ સારૂ માન્ય કલર કંપનીઓ પાસેથી સર્ટીફિકેટ મેળવવાનું રહે છે. સદર વોરંટી સર્ટીફિકેટ કંપની દ્વારા ઓથોરાઇઝડ પ્રતિનિધિની સહી/સિક્કા સાથેનું જ માન્ય ગણાશે તથા વોરંટી સર્ટીફિકેટમાં ૫ વર્ષ કે તેથી વધુના સમયગાળા સુધીની અવધિનું કુલ વોરંટી પિરિયડ મુજબનું સર્ટીફિકેટ જ માન્ય ગણાશે. અવમૂલ્યન (Depreciating) ટકાવારી સાથેનું પેઇન્ટ કંપનીનું વોરંટી સર્ટીફિકેટ માન્ય ગણાશે નહીં. આથી પેઇન્ટ કંપની નક્કી કરતા પૂર્વે વોરંટી સર્ટીફિકેટ અંગેની તકેદારી ખાસ રાખવાની રહેશે.

ગુજરાત રાજ્ય પોલીસ આવાસ નિગમ લિમીટેડ

::: કબુલાત / એકરાર પ્રમાણપત્ર :::

હુ/અમે આથી એકરાર કરૂ છુ/કરીએ છીએ કે, અમારા/મારી નજીકના સગા આ નિગમની વિભાગીય કચેરીમા તેમજ તે હેઠળની પેટા વિભાગીય કચેરીમાં કાર્યપાલક, નાયબ કાર્યપાલક, મદદનીશ ઇજનેર, અધિક મદદનીશ ઇજનેર, વિભાગીય હિસાબનીશ, સ્ટોરકિપર અથવા અન્ય કોઇ પણ હોદ્દા પર હાલ ટેન્ડર ભરવાની તારીખે કામ કરતા નથી.

ગુજરાત રાજ્ય પોલીસ આવાસ નિગમ લિમિટેડ

::: ખાસ સૂચના :::

કામ પુર્ણ કર્યા અંગેનું પ્રમાણપત્ર આપવા બાબત.

- એજન્સી દ્વારા કામ પુર્ણ થાય ત્યાર બાદ એજન્સી એ તે અંગે ની નોટીસ કાર્યપાલક ઈજનેરશ્રીને આપવાની રહેશે.
- આ નોટીસ મળતા કાર્યપાલક ઈજનેરશ્રીને ૫ (પાંચ) વર્કિંગ દિવસમાં સાઈટ વીઝીટ કરી ઈન્સ્પેક્શન કરવાનું અને જો કામ પુર્ણ થયેલ હોયતો તેનું પ્રમાણપત્ર તે જ વખતે ઈસ્યુ કરી તેની એક એક કોપી નીચે મુજબ ઈ-મેઈલ પર મોકલાવાની રહેશે.
- MD-gsphc@gujarat.gov.in
- se1.gsphc@gujarat.gov.in
- cfo.gsphc@gujarat.gov.in

ગુજરાત રાજ્ય પોલીસ આવાસ નિગમ લિમિટેડ

::: ખાસ સૂચના :::

કામ પુર્ણ થયા બાદ ઇજારદારશ્રી એ લાભાર્થી અધિકારીશ્રીનુ કામ સંતોષકારક રીતે પૂર્ણ કરી આપેલ છે તે બદલના પ્રમાણપત્ર/તાબાપાવતી મેળવ્યા બાદજ અંતિમ બીલની કાર્યવાહી હાથ ધરવામા આવશે.

:: વિશેષ નોંધ ::

સદર કામમાં સમાવિષ્ટ બિલ્ડીંગ માટે સરકારશ્રીના તા. ૧૩/૧૨/૨૦૨૩ ગેઝેટ અન્વયે ઈજારદારશ્રીએ એગ્રીમેન્ટ કરતા સમયે ફાયર ફાઈટીંગની લગત કામગીરી માટે ફાયર ફાઈટીંગની કામગીરી કરતી એજન્સી સાથે જરૂરી એમ.ઓ.યુ. રજુ કરવાનું રહેશે. ઈજારદારશ્રી દ્વારા ટેન્ડરની જોગવાઈ મુજબ વેળાસર સદર બિલ્ડીંગ માટે જરૂરી પ્રી-એન.ઓ.સી. મેળવવાની કામગીરી હાથ ધરી તે મુજબ બાંધકામમાં ફાયર હાઈડ્રન્ટ સીસ્ટમને લગત જરૂરી સુધારા-વધારા કરવાના થતા હોય તે માટે જરૂરી કાર્યવાહી હાથ ધરવાની રહેશે. લાભાર્થીને મકાનો ફાયર એન.ઓ.સી. સાથે હેન્ડીંગ ઓવર થઈ શકે તે હેતુથી ઈજારદારશ્રી દ્વારા બિલ્ડીંગ માટેની મેળવવાની થતી જરૂરી ફાઈનલ ફાયર એન.ઓ.સી. માટેની કામગીરી અંગેનું આગોતરૂં આયોજન કરવાનું રહેશે તેમજ સ્થાનિક સક્ષમ સંસ્થાઓમાં સરકારશ્રીના ગેઝેટ અન્વયે ભરવાપાત્ર રકમ ઈજારદારશ્રી દ્વારા ભરપાઈ કરવાની રહેશે. સ્થાનિક સંસ્થાઓ તરફથી જરૂરી ફાયર એન.ઓ.સી. મળ્યા બાદ ઈજારદારશ્રી દ્વારા ફાયર એન.ઓ.સી. ઓરીજનલ નકલ અને સ્થાનિક સંસ્થામાં એન.ઓ.સી. માટે ભરપાઈ કરવામાં આવેલ રકમના જરૂરી ચલણ/રસીદ વિભાગીય કચેરી ખાતે જરૂરી પત્રથી રજુ કરવાની રહેશે. સંલગ્ન વિભાગીય કચેરી દ્વારા સદર બાબતે વડી કચેરી ખાતે જરૂરી દરખાસ્ત કર્યા બાદ ફાયર એન.ઓ.સી. પેટે ભરપાઈ કરવામાં આવેલ રકમ ઈજારદારશ્રીને પરત કરવામાં આવશે.

વધુમાં જો ઈજારદારશ્રી દ્વારા ફાયર એન.ઓ.સી. માટે આગોતરૂં આયોજન નહીં કરવામાં આવે અને તેના કારણે ફાયર એન.ઓ.સી. મેળવવામાં થયેલ વિલંબ અંગે ઈજારદારશ્રી જવાબદાર રહેશે તેવા કિસ્સામાં સદર કામનું ફાઈનલ બીલ ફાયર એન.ઓ.સી. મળ્યા બાદ જ આપવામાં આવશે. જો કોઈ ખાસ કિસ્સામાં ઈજારદારશ્રી દ્વારા એન.ઓ.સી. મેળવવાની કામગીરી માટે જરૂરી કાર્યવાહી હાથ ધરવામાં આવેલ હોય પરંતુ ફાયરની એન.ઓ.સી. મળવામાં વિલંબ થાય તેમ હોય તો તેવા કિસ્સામાં ઈજારદારશ્રી દ્વારા રૂા. ૩૦૦ના સ્ટેમ્પ પેપર પર ફાયર એન.ઓ.સી. ૦૧ માસમાં મેળવી આપવાની તથા સદર સમયગાળા દરમ્યાન કોઈ ઘટના ઘટે તો તે અંગેની સંપૂર્ણ જવાબદારી ઈજારદારશ્રીની રહેશે તે અંગે તેમજ ફાયરની ફાઈનલ એન.ઓ.સી. પેટે ઉચ્ચક રકમ વિથહેલ્ડ રાખવા અંગેની લેખિત બાંહેધરી આપવાની રહેશે. વધુમાં ઉક્ત કિસ્સામાં ફાઈનલ ફાયર એન.ઓ.સી. વિના અંતિમ બિલના ચૂકવણાં અંગેનો મેનેજમેન્ટનો નિર્ણય અંતિમ રહેશે.

SPECIAL CONDITION OF CONTRACT

In order to exercise the required degree of constant control over the ingredients of concrete and their proportions the contractor shall set up and maintain at his own expense a testing laboratory at site manned by a qualified and experienced technician. The contractor shall provide all apparatus required for testing of concrete and its ingredients and in particular he must provide the following.

For Up to 1 Crore Tender Amount : -

- ❖ A complete set of Standard sieves
- ❖ Sieve vibrator.
- ❖ Slump cones. (1 nos.)
- ❖ Adequate number of standard C.C. Cubes. Moulds.
- ❖ Curing tanks for cubes.
- ❖ Electronic Weighing balance
- ❖ Liquid Measures

For Above 1 Crore Tender Amount : -

- ❖ A complete set of Standard sieves.
- ❖ Sieve vibrator.
- ❖ Slump cones. (2 nos.)
- ❖ Universal Testing Machine
- ❖ Adequate number of standard C.C. Cubes. Moulds. (12 Nos Min)
- ❖ Curing tanks for cubes.
- ❖ Cube Testing Machine
- ❖ Electronic Weighing balance (2 nos.of Required capacity)
- ❖ Liquid Measures
- ❖ Oven

Any other apparatus deemed necessary by GSPHCL or its consultants for proper control shall be provided by the contractor at his own cost.

ગુજરાત રાજ્ય પોલીસ આવાસ નિગમ લિમિટેડ

GENERAL CONDITIONS FOR TENDER

Incomplete tenders of the tenderers which are not full filling any of the conditions stated below shall become liable for rejection.

1. If the tenderers propose any alteration in the work specified in the tender or in the time allowed in carrying out the work or any other conditions.
2. If any of the pages of the tender are removed and / or replaced.
3. If the earnest money for the full amount is not attached to the tender.
4. If in the case of firm, each partner thereof does not sign or the witness on pages of the tender in the space provided for the purpose.
5. If the percentage additions in the item rate tender is given.

SPECIAL CONDITIONS OF CONTRACT

- [1]** The work to be carried out the contract shall except as otherwise provided in these conditions include all labour, materials, tools, plants, equipments and transport which may be required in preparation of and for and in the full and entire execution and completion of the works. The descriptions given in the schedule of quantities shall unless otherwise stated be held to included waste on materials, carriage and cartage, carrying in, return of empties, hoisting, setting, fitting and fixing in position and all other labours necessary in and for the full and entire execution and completion and all applicable taxes as aforesaid in accordance with good practice and recognized principles.
- [2]** The rates quoted by Contractor should also include for providing all scaffolding, hoists, tackle and other plant, shuttering profile and apparatus generally required for the proper execution of the work. The contractors shall provide without extra charges all labour and apparatus required by GSPHCL for testing and measuring the works and for weighting measuring, providing or testing the efficiency of any portion of the works and shall also at his own cost provide all planking gang ways, etc. necessary for affording access to every part of the works.
- [3]** The Contractor is expected to quote rate for each item after careful analysis of cost involved for the performance of the completed item considering all specifications and conditions of contract. This will avoid loss of profit or gain in case of curtailment or change of specification for any item. In case it is noticed that the rates quoted by the tenderer for any item are unusually low, analysis for such rates will have to be furnished by the tenderer on demand, to satisfy GSPHCL about the reasonableness of the rates.
- [4]** The Contractor shall provide at his cost all temporary lighting arrangement required for the works and to enable to contractors and sub-contractors to complete the works in the specified time including that for the workmen of any sub-contractors or special tradesmen.
- [5]** The Contractor shall provide and maintain at his own expense all lights, guards, fencing and watching when and wherever necessary or required by the Engineer in-charge / Project Architect / Engineer for the protection of the works or for the safety and convenience of those employed on the works or the public.

- [6] Varnier calipers gauge meter , metallic tapes and all other measuring instruments found necessary on the works shall be provided by the Contractor for the due performance of their contract as instructed by GSPHCL. The Engineer in-charge will use any or all measurement instruments or tools belonging to the Contractor as and when he chooses for checking the complete works as well as the work in progress. Any other apparatus deemed necessary by GSPHCL or its consultants for proper control shall be provided by the contractor at his own cost.
- [7] All scaffolding and ladders that may be necessary for taking measurement at site will be provided by the Contractor.
- [8] The whole of the works included in any contract shall be executed by the Contractor whom the work entrusted and the Contractor shall not directly or indirectly transfer assign or under let the contract or any part share thereof of any interest therein without the prior written consent of GSPHCL and no undertakings shall relieve the contractor from the full and entire responsibilities of the contractor or from active superintendence of the works during the progress.
- [9] The successful contractor will be required to submit PERT / CPM analysis of the entire work within 10 days of issuing the work order showing completion period as progress of the work shall be checked with the PERT / CPM analysis at various stages of completion.
- [10] The contractor shall confirm to the provisions of the Government Act relating to the work, and to the regulations and bye-laws of the local authorities. The contractor shall give all notices required by the said act, and obtain all required permission and license and pay all fees payable to such authorities in connection with constructing and maintaining temporary electric and water supply at site for the said project. All aspects of temporary works including their stability shall be the sole and ultimate responsibility of the contractor.
- [11] GSPHCL reserves the right to use the premises and any portion of site for execution of any work not included in this contract which GSPHCL may desire to get executed by other agencies. The contractor shall allow all reasonable facilities for the execution of such work but shall not be required to provide any plant or material for such work except by special arrangement with GSPHCL in such a manner as not to impede the progress of the works included in this contract and the contractor shall

not be responsible for any damage or delay which may happen or be occasioned by such work.

- [12]** The successful tenderer is bound to carry out any item of work up to any deviation in quantities for the completion of the job.
- [13]** The rate quoted shall include the cost of supplying colour photographs of 8" x 10" size with negative / soft copy to employer after completion of work from various angle one set each to employer and the architect separately in respect of each stage of work as directed.
- [14]** Contractor should submit three sets of as built drawings after completion of work.
- [15]** Police Housing Corporation has appointed a consultant for planning, supervision and co-ordination of this project work. Agency is required to carry out the work as per instruction of consultant Engineer / Architect / Engineer in-charge of corporation or their authorized representative in co-ordination to all other contracting agency engaged in this project work.
- [16]** Before tendering the tenderer shall visit the site on his own and also carefully examine all aspects in relation to work and tender. If any ambiguity or discrepancy is found, he shall refer to the engineer in-charge. The submission of the tender shall be regarded as signifying acceptance by the tenderer this instruction specifications and conditions.
- [17]** The tenderer shall make all the necessary arrangements for unloading the furniture and fixing the same at the suitable place on site. The contractor shall remain solely responsible for making the protection of the said furniture at his cost.
- [18]** The tenderer, if required by the corporation shall have to submit detailed computations and break ups of cost showing the figures on which the overall rates are based.
- [19]** The date of completion of job is essence to this contract. The contractor is therefore requested to complete the job in the stipulated time. Any deviation with respect to time or specification, the actions will be taken as per agreement booklet.
- [20]** Drawings are intended to give the tenderer an idea of work involved. These drawings are only indicative and for use prior to tendering only. Work shall proceed at the

tenderer's at site only on the basis of drawings marked "Final for Execution" which shall be issued to the successful tender. No claim shall be entertained from the tenderer if the "Final for Execution" drawings are with the tender.

- [21]** The quantities given are approximate and are meant primarily to a common basis for tender analysis.
- [22]** The contractor shall from time to time be entitled to receive payment on the basis of the actual work executed approved and certified by the consultant subject to deductions as hereafter mentioned. The period of honoring, consultant's certificates shall be 7 days.
- [23]** The contractor shall be responsible for making good in expeditions & workman like manner, any defects which may be found within one year of the handing over the premises, put to the beneficial use. In case contractor fails to do so, the same would be got done at his cost & risk. The cost incurred by the GSPHCL shall be deducted from.
- [24]** For any untendered or extra items, the contractor shall carry out of the work as per the instructions of the consultants / engineer in-charge. The rates for such items shall be worked out by the consultants / engineer in-charge considering all the aspects.
- [25]** The owner shall not be liable in any respect for any damages or compensation payable at law in consequences of any accident or injury to any work men of the contractor due to the action. The contractor in any user situation shall fully compensate, sit on his own all claims, proceedings, costs, charges or expenses incurred whatsoever of the owner his agent or servants.
- [26]** The contractor shall be deemed to have carefully examined the specification general conditions and drawings and to have fully informed and satisfied himself as to the nature and character of the work to be executed, site conditions and other relevant matters and details.
- [27]** The rates quoted in the tender shall be for the finished items of work. This shall include all charges required for labour, materials storage of materials, transportation of materials and equipment. Water and meter charges, temporary accommodation and plumbing works for labourers, tool and plant, marking out and cleaning of the

site, curing of various items of the work where cement has been used by keeping them constantly moist for such periods as stated in the relevant specifications and to do all things necessary to provide complete finished items of work in consistent with the inclusive of sales tax, octroi duty or other duties or feed levied by any government, public or local bodies. The exchange variations, labour conditions, or any other conditions whatsoever.

[28] The contractor shall make his own arrangements for the water required for the job. He shall also make arrangements for chlorinated drinking water for the workers during the execution of the work. The contractor shall also make arrangement for the security of materials, machineries, plants and all the items which are to be used during the work. Security shall not be the responsibility of the corporation.

[29] Drawings & Shop Drawings :

The drgs. enclosed in the tender are scope drgs. They indicate general layouts only. However, the actual location, distances shall be governed by field conditions. The contractor shall check at his own and all the drawings of connected utilities, so as to avoid possible conflict. Any discrepancies found in the drawg. And the field conditions shall be immediately brought to the notice of the consultants for decision.

[30] The contractor shall carry out the work strictly in accordance with drgs. work which shall be approved by the consultants.

[31] In case of questions regarding the meaning of any part tender document, the contractor shall approach either (1) Shree B B Patel (I/c Superintending Engineer) Gujarat State Police Housing Corporation Ltd., Contact No. : 079-23256800 to 805 or (2) Shree. K J Patel (I/c Executive Engineer), Contact No.: 0285-2622628 or Mobile No: 9978406775 till the last date of submission of tender.

[32] The rates quoted by the contractor shall be inclusive of Govt. Duties & Taxes, Octroies, Excise and Other levis also inclusive of charges like handling and transportation up to site.

[33] The contractor shall employ a full time qualified engineer at site during the execution period of work. He shall be assisted by adequate number of skilled and experienced persons / staff.

- [34]** The consultant shall at all times have access to the workshop and places where the work or part there of being fabricated or manufactured.
- [35]** The quantities set out in the bills of quantities are estimated quantities for the work out, they are not to be taken as actual and correct quantities of the work to be executed by the contractor. They are likely to increase up any extent an either side or may be purely deleted.
- [36]** Any Person found doing misconduct shall not be tolerated. The Engineer in-charge reserves the rights to require the contractor to remove the person who in his opinion misbehaves, is careless or is found unskilled.
- [37]** The time shall be considered as the essence of the contract and the contractor whereby agrees to commence and complete the work as provided in the said conditions.
- [38]** The quantity of the material supplied for any purpose shall be approved by the consultant / engineer in-charge. Prior to the use in the works whenever practicable samples are to be supplied & govt. approved by consultant / engineer in-charge before delivered to the site of works. Any material rejected will be removed from the site at contractor's expense.
- [39]** The main registered contractor is fully responsible for the whole work upto defect liabilities period. The payment shall be made to main registered principle contractor.
- [40]** If any minor or major changes/alteration/modifications at proposed site, the decision of engineer in-charge of Gujarat State Police Housing Corporation Ltd. will be final as per site condition.

Special Condition of Contract

1. In case of discrepancy between these "Special Conditions of Contract" and conditions mentioned elsewhere in the tender paper, these special conditions of contract will prevail.
2. On demand of contractor working/structural design drawings will be supplied by GSPHCL/GSPHCL's Design consultant/GSPHCL's proof consultant. The contractor shall pursue the delivery of working/structural design drawings before one month from starting of succeeding construction activity.
3. Read GSPHCL instead of Government of Gujarat in whole document.
4. Work will be supervised by GSPHCL and by Private consultant. (TPI.)
5. Contractor shall establish fully furnished site office (including AC, toilet and drinking water facility) of 300 sq.ft for client without any extra cost.
6. The various materials to be used in the works shall follow the specification as per relevant IS provision and records shall be maintained as per Performa.
7. The rate quoted is inclusive of all local State Government, Central Government and all other taxes.
8. The equipment shall be capable of determining accurately by direct weighing, prescribed amount of the various ingredients viz. Cement, sand, aggregates plasticizer and the combination of material in the mixer shall give a uniform mix within the prescribed time and discharging the mix without segregation. Equipment and its operations shall be all times subject to approval of the Engineer.
9. The contractor shall provide all the equipments and any other ancillary equipments, required for checking the performance of measuring and mixing device and shall make tests as and when ordered by the Engineer in charge to his satisfaction. The contractor shall make such adjustment, replace or replacement as may be necessary to meet the requirement of accuracy satisfaction of Engineer.
10. All the services and any utility lines (overhead, underground, surface utilities and any other) interfering in the work and those which require shifting shall have to be shifted by the contractor at expense of GSPHCL. The payment will be made as extra item, if not in tender. The services shall be shifted as per the guideline given by the concerned authority.
11. Only unconditional tender will be accepted.
12. In case of change of grade of concrete than specified in tender the same shall not be treated as a new item. Only the difference in the cost of cement will be paid.
13. Empty cement bags and wastage of steel are remain with the agency.
14. No fly ash will be allowed in concrete mix.
15. Testing of material expenses / charges shall be born by contractor. Testing are carried out at Govt. (R&B) approved laboratory or G.E.R.I. Testing at such laboratory can be done, if asked by GSPHCL, maximum up to 50% of frequency, mentioned in tender.
16. If Agency desires Fully automatic RMC plant confirming to IS 4926 of required capacity shall be established within site for which no extra payment will be done by GSPHCL.
17. All the building works shall start simultaneously at the time.