

Name of Work:- Demolition of VRC Building(Garage) at I.T.I. Kubernagar, Ahmedabad. (2nd attempt)

Section :-5

SPECIFICATION

Item No.1

Estimate of Demolition of Estimate of **Demolition of VRC Building(Garage) at I.T.I. Kubernagar, Ahmedabad..** Removing All Foundation Work, bricks, concrete, steel etc. Materials including cleaning, Ground levelling & Removing the all debris with all lead and lift. Completed as per instruction of Engineer in charge.

The specification for work man ship of dismantling work shall be follow as per Item No.20.23 Page No.148, Item No. 20.11(II) Page No.148, Item No.20.3 Page No.147, Item No.20.49(I) Page No.150, Item No.20.49(II) Page No.150, Item No.20.001 Page No.151 , Item No.20.43 Page No.150 Item No.20.56 Page No.151, Item No.20.39 Page No.150 of General Technical Specification booklet of building works. Except at all materials obtained from the demolition of said block shall be properly of the contractor.

All the serviceable and unserviceable materials shall be Immediately removed from the site and the ground shall be Cleaned and all the debris shall be removed and ground shall Be leveled as per the instruction of Engineer in charge.

Signature of
Contractor

Deputy Executive Engineer
Const(R & B) Sub Division-2
Ahmedabad

Executive Engineer
Medical (R & B) Division
Ahmedabad