

Issued to.....

On Dated.....

Senior Clerk(Account & Admin.)

Panchayat Irrigation Division,Valsad.

Name of work: **Repair to water harvesting structure Village :- Makadban Taluka : Dharampur , District : Valsad**

SCHEDULE - B

Memorandum Schowing the item of work to be carried out

Qty.	Unit	Description of Item	Tendered Rate		Amount
			In figures Rs.Paise	In Words	
1	2	3	4	5	6
5.4	CM	Item No. 1:- Dismantalling of the existing foundation concrete including disposing the dismantalled stuff including sorting out & stacking the useful materials & removing the debries & making good the damage etc.complete as directed. (b) In Cement Concrete.	1165.2	(Rupees One Thousand One Hundred Sixty Five and Twenty Paise Only)	6292.08
52.50	SM	Item No. 2:- Providing and laying dry rubble pitching of 300 mm thickness to required grade including trimming of earthwork hand packing the interstices with spauls, filling earth in interstices paneling complete for all leads and lifts.	455.50	(Rupees Four Hundred Fifty Five and Fifty Paise Only)	23913.75
167.50	SM	Item No. 3:- Providing Cement Plaster in various thickness and Proportion including smooth finishing, curing, scaffolding etc. complete for all leads & lifts as under. (a) Cement mortar 1:3 Proportion (i) 20 mm thick.	290.80	(Rupees Two Hundred Ninety and Eighty Paise Only)	48709.00
49.41	CM	Item No. 4:- Providing and laying Plain / Reinforced cement concrete of cement , sand and metal (12mm to 20mm size) in following proportion laid in situ including centering , shuttering , temping , smooth finishing, curing etc. complete As directed for all leads and lifts (Manually With Conventional Mixer) (III) 1:2:4	4891.30	(Rupees Four Thousand Eight Hundred Ninety One and Thirty Paise Only)	241679.13
14.40	SM	Item No. 5:- Providing and fixing M.S. Gate with all Hoisting and Finishing arrangements as per Design and Dimension with necessary two coats of oil paints etc complete (a) without frame with 3 mm plate for gate as per Drawing.	6400.00	(Rupees Six Thousand Four Hundred Only)	92160.00

Total Rs. 412753.96

(Rupees Four Lakh Twelve Thousand Seven Hundred Fifty Three and Ninety Six Paise Only)

I/We am/are Willing to carry out the work at.....% above/below Percent(should be written in figures and words) of the estimated rates mentioned above.Amount of my/our tender works out as under.

Estimated amount Put ter Rs. 412753.96

Deduct.....%below Rs.

Add.....% above

Rs.

Net Rs.
In words.....

Net Rs.
In words.....

*(Please strike out whichever is not applicable)

Note 1 All works shall be carried out as per Public Works Department Handbook and other specifications of Division or as directed.

નોંધ-૧ બધું જ કામ બાંધકામ વિભાગની પુસ્તિકા અને ડિવિઝનની બી ખાસ વિગત મુજબ અથવા સૂચના પ્રમાણે કરી આપવાનું રહેશે.

Note-2 All the columns in Schedule should be filled in ink and the total of the entries in the last column should be struck by the contractor under his signature.

નોંધ-૨ અનુસૂચિમાં બધા ખાનાની વિગતો સહીથી ભરવી અને છેલ્લા ખાનાની નોંધોનો સરવાળો કરી કંટ્રાક્ટરે પોતાની સહી કરવી.

Note-3 Rates quotes include clearance of site (prior commencement of work and at its close) in all respects and hold good for work under all conditions, site, moisture, weather etc.

નોંધ-૩ ટાંકેલા દરમાં, સ્થળની (કામના આરંભે અને પુરૂ થાય તે વખતે) દરેક રીતે સાફસુફી કરવાનો સમાવેશ થાય છે, અને તે દર તમામ પરિસ્થિતિ, સ્થળ, ભેજ, હવામાન વગેરે હેઠળ કામ માટે અમલમાં રહેશે.

Note-4 To be continued on additional sheets, if found necessary.

નોંધ-૪ જરૂર જણાય વધારાના કાગળો જોડી ચાલું રાખવું.

Note-5 All the Rates are included 1 % Labour Cess & shall be deducted from contractor all bills.

Deputy Executive Engineer,
Tribal Area Sub Division
Dharampur

Executive Engineer,
Panchayat Irrigation Division,
Valsad.

Signature of contractor