

Issued to.....

On Dated.....

Senior Clerk(Account & Admin.)

Panchayat Irrigation Division,Valsad.

Name of work: Repair to water harvesting structure Village :- Astol, Taluka : Kaprada , District : Valsad**SCHEDULE - B****Memorandum Schowing the item of work to be carried out**

Qty.	Unit	Description of Item	Tendered Rate		Amount
			In figures Rs.Paise	In Words	
1	2	3	4	5	6
11	CM	Item No. 1:- Dismantalling of the existing foundation concrete including disposing the dismantalled stuff including sorting out & stacking the useful materials & removing the debries & making good the damage etc.complete as directed. (b) In Cement Concrete.	1165.2	(Rupees One Thousand One Hundred Sixty Five and Twenty Paise Only)	12817.20
11.00	SM	Item No. 2:- Excavation for foundation in all sorts of soil inclunding sandy and gravelly soil , soft and hard murrum etc , dry condistion inclunding depositing the excavated stuff in unifrom layer in banks or as directed etc . Complete for lead up to 1.0 KM , and lift . (by machinary) (a) Above water table	81.50	(Rupees Eighty One and Fifty Paise Only)	896.50
10.00	SM	Item No. 3:- Excavation for foundation in soft rock inclunding depositing the excavated stuff in unifrom layer in banks or as directed etc . Complete for lead up to 1.0 KM , and lift . (by machinary) (a) Above water table	154.10	(Rupees One Hundred Fifty Four and Ten Paise Only)	1541.00
92.00	CM	Item No. 4:- Providing and laying plain / Reinforced cement concrete of cement , sand and metal (12 mm to 20 mm) size in following proportion Laid in situ inclunding centering and shuttering , temping , smooth finising , curing etc. Complete as directed for for all lead and Lifts (ii) 1:2:4	4891.30	(Rupees Four Thousand Eight Hundred Ninety One and Thirty Paise Only)	449999.60
4.95	SM	Item No. 5:- Providing and fixing M.S. Gate with all Hoisting and Finishing arrangements as per Design and Dimension with necessary two coats of oil paints etc complete (a) without frame with 3 mm plate for gate as per Drawing.	6400.00	(Rupees Six Thousand Four Hundred Only)	31680.00

Total Rs. 496934.30**(Rupees Four Lakh Ninety Six Thousand Nine Hundred Thirty Four and Thirty Paise Only)**

I/We am/are Willing to carry out the work at.....% above/below Percent(should be written in figures and words) of the estimated rates mentioned above.Amount of my/our tender works out as under.

Estimated amount Put ter Rs. 496934.30

Deduct.....%below Rs.

Add.....% above

Rs.

Net Rs.

Net

Rs.

In words.....

In words.....

*(Please strike out whichever is not applicable)

Note 1 All works shall be carried out as per Public Works Department Handbook and other specifications of Division or as directed.

નોંધ-૧ બધું જ કામ બાંધકામ વિભાગની પુસ્તિકા અને ડિવિઝનની બી ખાસ વિગત મુજબ અથવા સૂચના પ્રમાણે કરી આપવાનું રહેશે.

Note-2 All the columns is Schedule should be filled in ink and the total of the entries in the last column should be struck by the contractor under his signature.

નોંધ-૨ અનુસૂચિમાં બધા ખાનાની વિગતો સહીથી ભરવી અને છેલ્લા ખાનાની નોંધોનો સરવાળો કરી કંટ્રાક્ટરે પોતાની સહી કરવી.

Note-3 Rates quotes include clearance of site (prior commencement of work and at its close) in all respects and hold good for work under all conditions, site, moisture, weather etc.

નોંધ-૩ ટાંકેલા દરમાં, સ્થળની (કામના આરંભે અને પુરૂ થાય તે વખતે) દરેક રીતે સાફસૂફી કરવાનો સમાવેશ થાય છે, અને તે દર તમામ પરિસ્થિતિ, સ્થળ, ભેજ, હવામાન વગેરે હેઠળ કામ માટે અમલમાં રહેશે.

Note-4 To be continued on additional sheets, if found necessary.

નોંધ-૪ જરૂર જણાય વધારાના કાગળો જોડી ચાલું રાખવું.

Note-5 All the Rates are included 1 % Labour Cess & shall be deducted from contractor all bills.

Deputy Executive Engineer,
Tribal Area Sub Division
Dharampur

Executive Engineer,
Panchayat Irrigation Division,
Valsad.

Signature of contractor

Name of work : Repair to water harvesting structure Village :- Astol, Taluka : Kaprada , District : Valsad

CEMENT & STEEL CONSUMPTION

Sr. No.	Item	Qty. in CM	Rate of consumption	Cement Required
1	Item No. 4:- Providing and laying plain / Reinforced cement concrete of cement , sand and metal (12 mm to 20 mm) size in following proportion Laid in situ including centering and shuttering , temping , smooth finishing , curing etc. Complete as directed for for all lead and Lifts (ii) 1:2:4	92.00	6.40 Bags / CM	404.80
		Cement	Total	404.80
			Say	405.00

Deputy Executive Engineer
Tribal Area Sub Division
Dharampur