

Issued to.....

On Dated.....

Senior Clerk(Account &amp; Admin.)

Panchayat Irrigation Division,Valsad.

Name of work: **Constructing ovara at Village :Nargol Kubhar Talav, Ta.Umargam Dist. Valsad.****SCHEDULE - B****Memorandum Schowing the item of work to be carried out**

Qty.	Unit	Description of Item	Tendered Rate		Amount
			In figures Rs.Paise	In Words	
1	2	3	4	5	6
1	Job	<b>Item No. 1:--</b> Dewatering of foundation trenches from any depth.	5000	(Rupees Five Thousand Only)	5000.00
108	Cum	<b>Item No. 2:--</b> Excavation for foundation in all sorts of soil including yellow sandy and gravelly soil soft & hard murrum etc dry condition including depositing the excavated stuff in uniform layers table as directed etc complete for lead upto 1.00 K.M & all lift (By machinary) (b) Above water table	81.5	(Rupees Eighty One and Fifty Paise Only)	8802.00
156.06	Cum	<b>Item No. 3:--</b> Providing and laying Plain / Reinforced cement concrete of cement , sand and metal (20mm to 25mm size) in following proportion laid in situ including centering , shuttering , temping , smooth finishing, curing etc. complete As directed for all leads and lifts (Manually With Conventional Mixer) (III) 1:3:6	4110.5	(Rupees Four Thousand One Hundred Ten and Fifty Paise Only)	641484.63
13.5	100 Sq.cm .	<b>Item No. 04:--</b> Providing and fixing marble plate of 2cm thickness including engraving and filling paint for letter as directed.	250.6	(Rupees Two Hundred Fifty and Sixty Paise Only)	3383.10
<b>Total Rs.</b>					<b>658669.73</b>
<b>(Rupees Six Lakh Fifty Eight Thousand Six Hundred Sixty Nine and Seventy Three Paise Only)</b>					

I/We am/are Willing to carry out the work at.....% above/below Percent(should be written in figures and words) of the estimated rates mentioned above.Amount of my/our tender works out as under.

**Estimated amount Put ter Rs. 658669.73**Deduct.....%bel  
ow Rs.

Add.....% above Rs.

Net Rs.

Net Rs.

In words.....

In words.....

\*(Please strike out whichever is not applicable)

Note 1 All works shall be carried out as per Public Works Department Handbook and other specifications of Division or as directed.

નોંધ-૧ બધું જ કામ બાંધકામ વિભાગની પુસ્તિકા અને ડિવિઝનની બી ખાસ વિગત મુજબ અથવા સૂચના પ્રમાણે કરી આપવાનું રહેશે.

Note-2 All the columns in Schedule should be filled in ink and the total of the entries in the last column should be struck by the contractor under his signature.

નોંધ-૨ અનુસૂચિમાં બધા ખાનાની વિગતો સહીથી ભરવી અને છેલ્લા ખાનાની નોંધોનો સરવાળો કરી કંટ્રાક્ટરે પોતાની સહી કરવી.

Note-3 Rates quotes include clearance of site (prior commencement of work and at its close) in all respects and hold good for work under all conditions, site, moisture, weather etc.

નોંધ-૩ ટાંકેલા દરમાં, સ્થળની (કામના આરંભે અને પુરૂ થાય તે વખતે) દરેક રીતે સાફસૂફી કરવાનો સમાવેશ થાય છે, અને તે દર તમામ પરિસ્થિતિ, સ્થળ, ભેજ, હવામાન વગેરે હેઠળ કામ માટે અમલમાં રહેશે.

Note-4 To be continued on additional sheets, if found necessary.

નોંધ-૪ જરૂર જણાય વધારાના કાગળો જોડી ચાલું રાખવું.

Note-5 All the Rates are included 1 % Labour Cess & shall be deducted from contractor all bills.

Deputy Executive Engineer,  
Const. Irri. Khar. Panch. SDn  
Valsad

Executive Engineer,  
Panchayat Irrigation Division,  
Valsad.

Signature of contractor

Name of work : Constructing ovara at Village :Nargol Kubhar Talav, Ta.Umargam Dist. Valsad.

### **CEMENT & STEEL CONSUMPTION**

Sr. No.	Item	Qty. in CM	Rate of consumption	Cement Required
1	Item No. 3:-Providing and laying Plain / Reinforced cement concrete of cement , sand and metal (20mm to 25mm size) in following proportion laid in situ including centering , shuttering , temping , smooth finishing, curing etc. complete As directed for all leads and lifts (Manually With Conventional Mixer) (III) 1:3:6	156.06	4.40 Bags / CM	686.66
		<b>Cement</b>	<b>Total</b>	<b>686.66</b>
			<b>Say</b>	<b>687.00</b>
		<b>Steel</b>	<b>Qtl</b>	<b>0.00</b>
			<b>Say</b>	

Deputy Executive Engineer,  
Const. Irri. Khar. Panch. SDn  
Valsad