

NAME OF WORK :**C.R. To NH-51 bypass section (Providing Asphalt patch work on NH-51 bypass section)****SCHEDULE B**

It No	Qty	Unit	Item Description	Total	In Words	Total Amt
1	296.70	M.T	Providing, laying and rolling of open - graded premix surfacing of Patch work composed of 11.2mm to 0.09mm (Type A) aggregates using tack coat of Emulsion RS-1 @ 2.50 Kg / 10.00 Sqmt with using viscosity grade VG- 30 bitumen for mixing @ 51.00 Kg/M.T. of total weight of mix to required line, grade and level to serve as wearing course on a previously prepared / existing damaged base, including mixing in a suitable hot mix plant of appropriate capacity not less than 50 tonnes/hour, laying manually and rolling with a smooth wheeled roller, finished to required level and grades as directed by the Engineer in Charge.	3767.30	Rupees Three Thousand Seven Hundred SixtySeven and Paise Thirty Only.	1117757.91

Total = 11,17,757.91

I/We am/are willing to carry out the work at.....% above/below percent(Should be written in figures and words) of the estimated rate mentioned above. Amount of my /our tender works out as under.

Estimated amount put to tender
Deduct% below
Net :
In words :

The Contractor shall exhibit a board with detailed specification and details of work as directed by the Engineer-In-Charge for which no extra payment shall be made.

The labour cess will be deducted as per prevailing rules i.e. 1% of the work done.

GST and Income tax TDS will be deducted at a source while making payments of bills

In all R.C.C. Items in Rate Analysis Standard Cement Consumption has been taken as per Govt. G.R.: PRC-10/2017 Cement Consumption/16/C Date:11/05/2017 as stated in S.O.R. therefore in R.C.C. items where there is a change as per actual mix design the cost of difference of cement consumption have been deducted from the rate of original item at the rate of input rate mentioned in all the tender.

Deputy Executive Engineer
City R&B Sub division
Bhavnagar

Executive Engineer
R&B division
Bhavnagar