

CSR Fund Under Union Home Minister - Construction of Community Hall / Yoga Center at (1) Pindarda (2) Piplaj & (3) Unava Ta: Gandhinagar Dist: Gandhinagar. CSR Fund/ Community Hall/ Gandhinagar/ PKG No - 01 (2026-27)

SCHEDULE FOR TESTING OF MATERIALS

For ensuring quality control and workmanship, various tests prescribed below for materials shall be taken at periodical intervals as stipulated below.

The materials shall be a got tested at Government Laboratory (R & B) or field Laboratory of GERI (R & B) for which 1% of the estimated amount put to Tender shall be recovered from the contractor from the R.A. bills and final bills at the testing charges shall be paid to the GERI by the Government. However if the crages increase over 1% no excess recovery shall be made form the contractor as per resolution of B & C Department dated 10th, May 1985 vide TNC/1085 (4) s.

Item No. as per Schedul e 'B'	Brief Description of materials to be tested.	Qty. of Materials	Prescription of test which shall be carried out	Frequency @ which test shall be carried out	Total Nos of test to be taken
1	2	3	4	5	6
	Kapchi 40 mm 20 mm	80.45 412.40	*Gradation test *Impact Value *Flakiness Index of	1 to 100 - cum. 1 test 100 to 500 - cum. 3 test 500 to 1500 - cum. 5 test 1500 to 5000 - cum. 7 test	1 3
	Grit	126.06	*Stripping Value	As above	3
			*P.I.Value	As above	
			*Silt Content	As above	
	Sand	668.66	*Gradation, FM, SC	One Test per every 200 Cmt.	4
	Water		Chemical test	One test per source	1
	Bricks	233646	*Water absorption *Efflorence Size *Strength Comprehensive	1 test @ 50,000 Bricks	5
	Cement	297.727 M.T.	*Consistency *Setting time *Compressive Strength.	1 test @ 50.0 M.T. 100 T 2 tests, 200T 3 tests, 300T 4 tests, 500T 5 tests, 800 T 6 tests, 1300 T 7 tests & 8 testd for large consingment.	4
	Steel	36.618 TMT	*Tensile, (TMT) Yield *Elongation Size	As per Manual of Quality Control 1 test/40 tonnes / per category	1 Test Per Category

Item No. as per Schedule 'B'	Brief Description of materials to be tested.	Qty. of Materials	Prescription of test which shall be carried out	Frequency @ which test shall be carried out	Total Nos of test to be taken
	C.C.Cube Test	Cmt	*Compressive Strength.	1 to 5 cmt - 1 No	
				6 to 15 cmt - 2 No	
				16 to 20 cmt - 3 No	
	1:1.5:3	338.85		20 to 50 cmt - 4 No	10
			*Compressive Strength.	51 to above - 4 +1 additional sample for each 50 cu.mt. Or part there of.	

The contractor shall have to pay 1% of the estimate cost put to tender towards all testing of materials & the same shall be deducted from their bills for the work. The testing of various materials shall be carried out in GERI and result received shall be binding to all i.e. the contractor and Government.

Testing charges of GERI shall be born by Govt. No refund be made not extra charges over 1% shall be recoverable from the contractor.

Signature of Contractor.

Deputy Executive Engineer
Road Project Sub Division
Jilla Panchayat, Gandhinagar

Executive Engineer
R & B Panchayat Division
Gandhinagar