

**Name of Work :- Addition to New building for Family Court at Godhra Dist.  
Panchmahal**

**BILL OF QUANTITIES**

**Memorandum showing item of works to be carried out.**

It. No.	Description of Item	Qty.	Unit	Rate in figures	Amount
1	2	3	4	5	6
1	Supplying, Installation, Testing and Commissioning of Kirloskar make Diesel Engine driven fire Hydrant pump set suitable for Automatic Operation and Consisting of Following : Horizontal type, Centrifugal end suction back pull out, top discharge pump of cast iron body & Bronze impeller with M.S. fabricated common base plate, coupling, coupling guard, foundation bolts etc. as required. Model- KFE, Flow - 97 m <sup>3</sup> /hr, Head - 70 meter, Engine - 39 BHP/3 ph, Suc X Del - 100 x 80	1.00	Set	371680.00	371680.00
2	Providing and Installing of Fully Automatic Sanitary Napkin Incinerator Machine and Vending Machine with all fittings charge and labour charges etc. complete as directed by engineer in charge.	5.00	Set	39026.40	195132.00
3	Providing and fixing Sliding Pleated Mosquito net having standard extruded colour anodized aluminum section of premium quality of section size top and bottom of 50.8 mm x 25.4 mm x 2.0 mm and both side section of 63.50 mm x 25.4 mm x 2.00 mm with collapsible mosquito net with Magnet Locking System etc. complete as directed by EIC.	6.00	Sq.m.	2869.41	17216.46
4	<b>THREE SEATER WAITING SOFA</b> Providing and Arranging three seater gang seater having seat and back made from CRCA capular Tubular frame welded with perforated Die moulded CRCA sheet base frame made from round Tubular welded with horizontal beam Two side armrest welded with frame including finishing metal parts with epoxy polyester powder coating of 50 micron thickness Including all materials and labour etc. complete as per drawing and instruction of engineer-in charge. 3 Seater S.S. Gang Seater	12.00	No.	14255.14	171061.68
5	<b>MEDIUM BACK REVOLVING CHAIR</b> Providing and fixing Medium back Revolving chair seat and back are made from 12mm thick hot pressed plywood covered with moulded cushion and with premium fabric. The back foam should be designed with contoured lumber support for extra comfort. Foam should be with 45 density. Chair with chrome based five prong stand with nylon castors. Chairs with Synchrow tilt mechanism of standard make. Chair size 45 cm x 53 cm of back side and 52 cm x 48 cm seat side. Chair with scratch and weather resistant arm rest. Chair with permanent mechanism is designed with 360 revolving type with pneumatic height adjustment. Complete as directed by Architect and engineer in charge.	15.00	No.	6911.43	103671.45
6	<b>ROLLER BLINDS</b> Providing and fixing the Premium quality roller blinds with sunscreen & blackout layer of approved colour, design, size etc. The Duplex blind shall not filters the light into the room. The blind shall operated via a chain system, alternate strip of dim out & sheer fabrics shall be aligned to create a full sheer blind. The roller blind shall be installed on brackets & clamps fixed over the wall or ceiling. The brackets & clamps shall be made up of high strength alloy or zinc plated mild steel Including all material, fixtures, screw, nails, labour etc. complete as directed by Engineer incharge.	90.00	Sq.m.	4699.53	422957.70

It. No.	Description of Item	Qty.	Unit	Rate in figures	Amount
1	2	3	4	5	6
7	Providing MASS RACK 27U 600 mm x 1000 mm with height of 1310 mm Floor Standing Server Rack with Server Tray, Keyboard Tray, Power Strip 10 Socket, Cable Organizer 1U Closed, 4 Fans & Hardware Kit - Combo Pack for computer room etc. complete as directed by EIC.	1.00	No.	43963.28	43963.28
8	Providing and fixing <b>Fully Glazed Door</b> having aluminum Colour anodized section frame 85 mm x 38.10 mm with 5 mm thick frosted glass with powder coated aluminum fittings fixed on floor spring and fixtures with silicon sealant etc. complete	11.00	Sq.m.	4636.91	51006.01
9	Providing and fixing <b>safety grill</b> of required pattern for windows/ Ventilator / Door using M.S. Polished bars / Pipes / M.S. Angles / Flats of required spacing as per drawings as design and hold fastening with coach bolts including one coat of primer and two coats of matt finished oil painting etc. complete.	967.00	Kg.	109.08	105480.36
			<b>TOTAL Rs.</b>	<b>1482168.94</b>	

**i.e. Rs. Fourteen lacs Eighty Two thousand One hundred Sixty Eight and Ninety Four paisa only.**

I/We am/are willing to carry out the work @ \_\_\_\_\_ % above/below percent (Should be written in figures and words) of the estimated rate mentioned above. Amount of my /our tender works out as under.

Estimated amount put to tender	Estimated amount put to tender
Deduct.....% below	Add.....% Above
Net Rs. _____	Total Rs. _____
In words _____	In words _____

**Note :-**

- The Contractor shall exhibit a board with detailed specification and details of work as directed by the Engineer-In-Charge for which no extra payment shall be made.
- The labour cess will be deducted as per prevailing rules i.e. 1% of the work done.
- GST and Income tax TDS will be deducted at a source while making payments of bills.
- In all R.C.C. Items in Rate Analysis Standard Cement Consumption has been taken as per Govt. G.R.: PRC-10/2017 Cement Consumption/16/C, Date:11/05/2017 as stated in S.O.R. therefore in R.C.C. items where there is a change as per actual mix design the cost of difference of cement consumption have been deducted from the rate of original item at the rate of input rate mentioned in all the tender.
- The Contractor will have to submit the all required mix design at his own cost before execution as directed and to be approved from the Engineer in charge.**

**Above all items of "Schedule-B" with Item Description, Unit, Rate & Amount have verified by me and found order.**

Executive Engineer  
R & B Division,  
Godhra