

1.

BILL OF QUANTITIES**(A) Percentage Rate Tender (Up to INR 50 Cr.)**

As per attached sheet.

Name of work :- Repairing of existing HDPE pipeline of dia.280 mm & supplying and fixing new valve (survey no-235 new) at village: Aanand Bhakhari, Taluka-Satlasana Dist- Mehsana at chainage 3280 mt. Kuda to Bhimpur Pipeline project by using HDPE 280 mm dia. pipe.

Qty	Item	Estimated Rates With Labour Cess		Unit	Amount
		In Figures RS.	InWords		
	ITEM NO-1 Excavation of pipeline trenches/foundation trenches in the strata shown below including depositing the excavated stuff as and where directed upto lead of 50 Mts. and 6.0 Mt lift of excavation below average G.L. including refilling, cleaning the site with thin jungle cutting but excluding dewatering if any.(A) Excavation in all sorts of soil. (As Per GWRDC SOR 2023-24(Ch.4 item no- 1 A p.no-33)		Two Hundred Twenty One Rupees And Nineteen Paise Only	Cmt	
30	(a) Up to 1.5mtr	221.19			6635.70
30	(b) 1.5mtr to 3.00 mtr	232.30			6969.00
1200	ITEM NO-2 Refilling the pipeline trenches incl. ramming, watering, consolidating desposal of surplus stuff as directed within a radius of 3 km with selected soil brought from outside including all lead (As Per GWSSB SOR 2022-23 Section-A Item No.14(2) Pg.No.40)	175	One Hundred Seventy Five Rupees Only	Cmt	210000.00
36	ITEM NO-3 Providing Laying & Joinig in standard length ISI mark regid unplasticised H.D.P.E. Pipes suitable for irrigation water with self fit joint incl, joining necessary fitting like Tee, Bend, Coupler, reducer, End cap joining (cement solvent) of following class and dia as per IS specification No. 4985/1988 etc.comp (a) 6.00 kg/cm2 (14) 280 mm dia (As Per GWSSB SOR 2022-23 Section-A Item No.4.1.A.(14) Pg.no.8)	1777.60	One Thousand Seven Hundred Seventy Seven Rupees And Sixty Paise Only	Rmt	63993.60
2	ITEM NO :- 4 Providing and Fixing I S I mark following class & dia of different type of valves with necessary fittings of standered design and specification incl. testing with all leads and lifts etc.complete. (3)(g) Sluice valve 300 mm dia. (As Per GWRDC SOR 2023-24 (Ch 9 sr no-1 p.no-50)	22307.87	Twenty Two Thousand Three Hundred Seven Rupees And Eighty Seven Paise Only	No	44615.74
2	ITEM NO-5 Constructing sluice valve chamber As Per Sub Estimate No- 1	32187	Thirty Two Thousand One Hundred Eighty Seven Rupees Only	No	64374.00

1	ITEM NO-6 Constructing Tail Kundi As Per Sub Estimate No- 2	224273	Two Lakh Twenty Four Thousand Two Hundred Seventy Three Rupees Only	No	224273.00
1	ITEM NO-7 Providing videography on occasion of function or for on going construction work including dubbing, titeling etc. complete including cost of casette/CD. For Whole day As Per GWRDC SOR 2023- 24 (Ch 11 sr no45 p.no-61)	2222	Two Thousand Two Hundred Twenty Two Rupees Only	Per Day	2222.00
0.54	ITEM NO-8 Supplying & Fixing Road SignBoard of MSPlate&Angel Iron Incl Painting Lettering Etc ComplIncl Fixingin CC(1:4:8) With necessary Excavation Etc Comp Asper IRCType Design (NonReflective Type) As Per GWRDC SOR 2023-24 (Ch 11 sr no-6 p.no-53)	2410.87	Two Thousand Four Hundred Ten Rupees And Eighty Seven Paise Only	Smt	1301.87
300	ITEM NO-9- Crop Compensation	15	Fifteen Rupees Only	Smt	4500.00
Total (Without GST)					628884.91

I/We am/are willing to carry out the work at.....% above/below percent(Should be written in figures and words) of the estimated rate mentioned above. Amount of my /our tender works out as under.

Estimated amount put to tender

Estimated amount put to tender

Deduct.....% below

Add.....% Above

Net

Net

In words

In words

(A) Total Tendered Amount

(B) Rebate on above tendered amount (if any) % (in figure)
(in words).....

(C) Net Tendered Amount (A-B) (in figure)
(in words).....

#

1	The Contractor shall exhibit a board with brief details of work as directed by the Engineer-In-Charge for which no extra payment shall be made.
2	The labour cess will be deducted as per prevailing rules i.e. 1% of the work done.
3	GST and Income tax TDS will be deducted at a source while making payments of bills
4	In all R.C.C. Items in Rate Analysis Standard Cement Consumption has been taken as per Govt. G.R. NO.: MIS102010/17/K1 Dated:30/07/2018 as stated in S.O.R. there fore in R.C.C. items where there is a change as per actual mix design the cost of difference of cement consumption have been deducted from the rate of original item at the rate of input rate mentioned in all the tender.