

Name of Work :- Providing Paver Patta & Asphalt Patchwork on Various Road in Thangadh Taluka of Panchayat Planning R&B Sub Division, Surendranagar, Dist. Surendranagar

BILL OF QUANTITIES

Item No.	Quantities Estimated but may be more or less	Description of Item (with brief specification and reference to book of specifications)	Estimated Rate		Unit	Total Amount According to Estimated Quantities
			In Figure	Rs. in Words		
			Rs. Ps.			
(1)	(2)	(3)	(4)	(5)	(6)	(7)
1	154.00	Providing and laying Compacted W.B.M. 150mm thick of Grading-II, using B.T.M.C. metal of size 45mm to 63mm including using 13% Stone Screening 13.2mm size and 7% stone dust as filler including spreading, watering and consolidation by vibratory roller etc. complete	1479.65	Rs. One Thousands Four Hundred Seventy Nine and Sixty Five Paisa Only	Cum.	227866.10
2	58.00	Providing and Laying of 37.50mm thick Compacted Built up Spray Grount with B.T. Aggregates as per required gradation & using bitumen Grade VG-30 of Mixing with aggregates @ 1.99% i.e. 19.90 Kg./M.T. of total mix including & Bitumen for Tack Coat Emulsion (RS1) @ 2.50 Kg./10-Sq.mt. for B.T. Surface including heating & mixing in Drum Mix Plant, transporting spreading the same with paver finisher & consolidation with vibratory roller including necessary fire wood oil, lubricant, labour charges etc. using contractor own drum mix plant & equipment tools etc. complete in accordance with the requirement of specification	2376.53	Rs. Two Thousands Three Hundred Seventy Six and Fifty Three Paisa Only	M.T.	137838.74
3	443.25	Providing and laying sealcoat using asphalt viscosity grade of VG-30 with BT aggregate as specified using aggregate at the rate of 0.18 Cum/10 Sqm and bitumen for mixing with aggregate at the rate of 4.50% i.e. 45.00 Kg/MT of total mix including heating and mixing in drum mix plant and spreading the same by paver finisher and consolidation with vibratory roller including necessary using contractor's own drum mix plant, machineries and equipment, tools etc. complete in accordance with the requirement of specification.	3532.98	Rs. Three Thousands Five Hundred Thirty Two and Ninety Eight Paisa Only	M.T.	1565993.39
				Total Rs.		1931698.23

I / We am/are willing to carry out the work at % above / below (Should be written in figures and words) of the estimated rates mentioned above. Amount of my/our tender works out as under.

Estimated amount

Put to tender

Rs.

Add..... % above

Rs.

Total

Rs.

In words.....

(Please strike out whichever is not applicable)

Estimated amount

Put to tender

Rs.....

Deduct..... % below

Rs.....

Net

Rs.....

In words.....

(1)	(2)	(3)	(4)	(5)	(6)	(7)
-----	-----	-----	-----	-----	-----	-----

NOTES :-

- [1] The Contractor shall exhibit a board with detailed specification and details of work as directed by the Engineer-In-Charge for which no extra payment shall be made.
- [2] The labour cess will be deducted as per prevailing rules i.e. 1% of the work done.
- [3] GST and Income tax TDS will be deducted at a source while making payments of bills
- [4] In all R.C.C. Items in Rate Analysis Standard Cement Consumption has been taken as per Govt. G.R.: PRC-10/2017 Cement Consumption/16/C Date:11/05/2017 as stated in S.O.R. therefore in R.C.C. items where there is a change as per actual mix design the cost of difference of cement consumption have been deducted from the rate of original item at the rate of input rate mentioned in all the tender.
- [5] Concrete & bitumenous Mix Design carried out by Contractor at his own cost.

Signature of Contractor

***Deputy Executive Engineer
Panchayat Plan.(R&B) Sub-Dn.
Surendranagar***

***Executive Engineer
Panchayat (R&B) Div.
Surendranagar***