

Name of Work: Work of Widening, Strengthening and Resurfacing of various road as and when required or in emergency under Panchayat R&B Division, Junagadh (Annual Rate Basis)

SPECIFICATIONS OF MATERLAIS

M 1 Water

- 1.1** Water shall not be salty or brackish and shall be clean, **reasonably clear and free from objectionable quantities** of silt and traces of oil and injurious alkalies, salts, organic matter and other deleterious material which will either weaken the mortar or concrete or cause efflorescence or attack the steel in R.C.C. Container for transport, storage and handling of water shall be clean. Water shall conform to the standards specified in I.S. 456 1978.
- 1.2** If required by Engineer in charge it shall be tested by comparison with distilled water. Comparison shall be made by means of standard cement tests for soundness, time of setting and mortar strength as specified in I.S. 269 1976. Any indication of unsoundness, change in time of setting by 30 minutes or more or decrease of more than 10 per cent in strength of mortar prepared with water sample when compared with the results obtained with mortar prepared with distilled water shall be sufficient cause for rejection of water under test.
- 1.3** Water for curing mortar, concrete or masonry should not be too acidic or too alkaline. It shall be free of elements which significantly affect the hydration reaction or otherwise interfere with the hardening of concrete during curing or those which produce objectionable stains or other unsightly deposits on concrete or mortar surfaces.
- 1.4** Hard and bitter water shall not be used for curing.
- 1.5** Potable water will be generally found suitable for curing mortar or concrete. **M 2. Lime**

- 2.1** Lime shall be hydraulic lime as per I.S. 712 1973. Necessary test shall be carried out as per I.S. 6932 (Parts I to X), 1973.
- 2.2** The following field tests for times are to be carried out:
 - (1)** A very rough idea can be formed about the type of lime by its visual examination i.e. fat lime bears pure white colour, lime in form of porous lumps of dirty white colour indicates quick lime, and solid lumps are unburnt lime stone.
 - (2)** Acid tests for determining the carbonate content in lime. Excessive amount of impurities
- 2.3** Storage shall comply with I.S. 712 1973. The slaked lime, if stored, shall be kept in a weather proof and damp proof shed with impervious floor and sides to protect it against rain, moisture, weather and extraneous materials mixing with it. All lime that has been damaged in any way shall be rejected and all rejected materials shall be removed from site of work.
- 2.4** Field testing shall be done according to I.S. 1624 1974 to show the acceptability of materials.

M 3. Cement

- 3.1** Cement shall be ordinary portland slag cement as per I.S. 269 1976 or Portland slag cement as per I.S. 455 1976.

M 4. White Cement

4.1 The white cement shall conform to I.S. 804112 E 1978.

M 5. Coloured Cement

5.1 Coloured cement shall be with white or gray portland cement as specified in the item of

5.2 The pigments used for coloured cement shall be of approved quality and shall not exceed 10% of cement used in the Mix. The mixture of pigment shall be properly grounded to have a uniform colour and shade. The pigments shall have such properties to provide for durability under exposure to sunlight and weather.

5.3 The pigment shall have the property such that it is neither affected by the cement nor detrimental to it. **M 6. Sand**

6.1 Sand shall be natural sand, clean, well graded, hard strong durable and gritty particle free from injurious amounts of dust clay, kankar nodules, soft or flaky particles shale, alkali, salts organic matter, loam, mica or other deleterious substance and shall be got approved from the Engineer in charge. The sand shall not contain more than 8 percent of silt as determined by field test. If necessary the sand shall be washed to make it clean.

6.2 Coarse Sand:

The fineness modulus of coarse sand shall not be less than 2.5 and shall not exceed 3.0. The sieve analysis of coarse shall be as under.

L S. Sieve Designation	Percentage by Weight Passing sieve	I S. Sieve Designation	Percentage by Weight Passing through sieve
4.75 mm.	100	600 Micron	30-100
2.36 mm.	90 to 100	300 Micron	5-70
1.18 mm.	70-100	150 Micron	0-50

6.3 Fine Sand:

The fineness modulus shall not exceed 1.0. The sieve analysis of fine sand shall be as under:

L S. Sieve Designation	Percentage by Weight Passing sieve	I S. Sieve Designation	Percentage by Weight Passing through sieve
4.75 mm.	100	600 Micron	40-85
2.36 mm.	90 to 100	300 Micron	5-50
1.18 mm.	70-100	150 Micron	0-10

M 7. Stone Dust:

7.1 This shall be obtained from crushing hard black trap or equivalent. it shall not contain 'more than 8%" silt as determined by field test with measuring cylinder. The method of determining silt contents by field test is given as under:

7.2 A sample of stone dust to be tested shall be placed without drying in 200 mm. measuring cylinder. The quantity of the sample shall be such, that it fills the cylinder upto 100 mm. mark. The clean water shall be added upto 150 mm. Mark, The mixture shall be stirred vigorously and the content allowed to settle for 3 hours.

7.3 The height of silt visible as settled layer above the stone dust shall be expressed as percentage of the height of the stone dust below. The stone dust containing more than 8% silt shall be washed so as to, bring the silt content within the allowable limit.

7.4 The fineness modulus of stone dust shall not be less than 1.80.

M 8. Stone Grit

8.1 Grit shall consist of crushed or broken stone and be hard strong, dense, durable, clean, of proper gradation and free from skin or coating likely to prevent adhesion of mortar Grit shall generally be cubical in shape and as far as possible flaky elongated pieces shall be avoided. It shall generally comply with the provisions of I.S. 383 1970. Unless special stone of particular quarries is mentioned, grit shall be obtained from the best black trap or equivalent hard stone as approved by the Engineer in charge. The grit shall have no deleterious reaction with cement.

8.2 The grit shall conform to the following gradation as per sieve analysis

L S. Sieve Designation	Percentage by Weight Passing sieve	I S. Sieve Designation	Percentage by Weight Passing through sieve
12.5 mm.	100%	4.75 mm.	0-20%
10.00 mm.	80- 100 %	2.36 mm.	0-25%

8.3 The crushing strength of grit will be such as to allow the concrete in which it is used to built up the specified strength of concrete.

8.4 The necessary tests for 'grit shall carried out as per the requirements of I.S. 2386 (Parts I to VII) 1963, as per instructions of the Engineer in charge. The necessity of test will be decided by the Engineer-in charge.

M 9. Cinder:

9.1 Cinder is well burnt furnace residue which has been fused or sintered into lumps of varying sizes.

9.2 Cinder aggregates shall be well burnt furnace residue obtained from furnace using coal fuel only. It shall be sound clean free from clay, dirt, ash or other deleterious matter.

9.3 The average grading for cinder aggregates shall be as mentioned below:

L S. Sieve Designation	Percentage by Weight Passing sieve	I S. Sieve Designation	Percentage by Weight Passing through sieve
20 mm.	10000%	4.75 mm.	70
10 mm.	86	2.36 mm.	52

M 10. Lime Mortar

- 10.1** Lime shall conform to specification M 2. Water shall conform to specification M 1.
Sand shall conform to specification M 6.

10.2 Proportion of Mix:

- 10.2.1** Mortar shall consist of such proportions of slaked lime and sand as may be specified in the item. The slaked lime and sand be measured by volume. 10. 3. Preparation of mortar:
10.3. 1. Lime mortar shall be prepared by wet process as per I.S. 1625 1971. Power driven mill shall be used for preparation of lime mortar. The slaked lime shall be placed in the mill in an even layer and ground for the 180 revolutions with a sufficient water. Water shall be added as required during grinding (care being taken not to add more water) that will bring the mixed material to a consistency of stiff paste. Thoroughly wetted sand shall then be added evenly and the mixture ground for another 180 revolutions.

10.4 Storage

- 10.4.1** Mortar shall always be kept damp, protected from sun and rain till used up, covering, it by tarpaulin or open sheds.

10.5 Use

- 10.5.1** All mortar shall be used as soon as possible after grinding. It should be used on the day on which it is prepared. But in no case mortar made earlier than 36 hours shall be permitted for use.

M 11. Cement Mortar

- 11.1** Water shall conform to specification M71. Cement shall conform to specification M 3.
Sand shall conform to

M 6. 11. 2. Proportion of Mix

- 11.2.1** Cement and sand shall be mixed to specified proportion, sand being measured by measuring box.
The proportion of cement will be by volume on the basis of 50 Kg./Bag of cement being equal to 0.0342
Cu.m. The mortar may be hand mixed or machine mixed as directed.

11.3 Preparation of mortar

- 11.3.1** In hand mixed mortar cement and sand in the specified proportions shall be thoroughly mixed dry on a clean impervious platform by turning over at least 3 times or more till a homogenous mixture of uniform colour is obtained. Mixing platform shall be so arranged that no deleterious extraneous material shall get mixed with mortar or mortar shall flow out. While mixing, the water shall be gradually added and thoroughly mixed to form a stiff plastic mass of uniform colour so that each particle of sand shall be completely covered with a film of wet cement. The water cement ratio shall be adopted as directed.
- 11.3.2** The mortar so prepared shall be used, within 30 minutes of adding water. Only such quantity of mortar shall be prepared as can be used within 30 minutes.

M 12. Stone Coarses Aggregate for Nominal Mix Concrete

- 12.1** Coarse aggregate shall be machine crushed stone of black trap or equivalent and be

strong, dense, durable, clean and free from skin and coating likely to prevent proper adhesion of mortar.

- 12.2** The aggregate shall generally be cubical in shape. Unless special stones of particular quarries are mentioned aggregates shall be machine crushed from the best black trap or equivalent hard stone as approved. Aggregate shall have no deleterious reaction with cement. The size of the coarse aggregate for plain cement concrete and ordinary reinforced cement concrete shall generally be as per the table given below.

However in case (if reinforced cement concrete the maximum limit may be restricted to 6 mm. less than the minimum lateral clear distance between bars or 6 mm. less than the cover, whichever is smaller.

I.S. Sieve Designation	Percentage passing for single sized aggregates of Nominal size			I.S. Sieve Designation	Percentage passing for single sized aggregates of Nominal size		
	40 mm	20 mm	16 mm		40mm	20mm	16mm
80 mm	-	-	-	12.5 mm	-	-	-
63 mm	100	-	-	10 mm	0.5	0.02	0.3
40 mm	85-100	100	-	4.75 mm	-	0.5	0.5
20 mm	0-20	85-100	100	2.35 mm	-	-	-
16 mm		-	85-100		-	-	-

Note: This percentage may be varied some what by Engineer in charge when considered necessary for obtaining better density and strength of concrete.

- 12.3** The grading test shall be taken in the beginning and at the change of source of materials. The necessary test indicated in I.S. 383 19710 and I.S. 456 1978 shall have to be carried out to ensure the acceptability. The aggregates shall be stored separately and handled in such a manner as to prevent the intermixing of different aggregates. If the aggregates are covered with dust, they shall be washed with water to make them clean.

M 13. Blak Trap or Equivalent Hard Stone Coares.

- 13.1 Aggregate For Design Mix Concrete :** Coarse aggregate shall be of machine crushed stone of black trap or equivalent hard stone and be hard strong dense, durable clean and free from skin and coating likely to prevent proper adhesion of mortar.

- 13.2** The aggregates shall generally be cubical in shape, Unless special stones of particular quarries are mentioned, aggregates shall be machine crushed from the best, black trap or equivalent hard stones as approved. Aggregate shall have no deleterious reaction with cement.

- 13.3** The necessary tests indicated in I.S. 383 1970 and I.S. 456 1978 shall have to be carried out to ensure the acceptability of the material.

- 13.4** If aggregate is covered with dust it shall be washed with water, to make it clean.

M 14. Brick Bats Aggregate

- 14.1** Brick bat aggregate shall be broken from well burnt or slightly over burnt and dense brick. It shall be homogeneous in texture roughly cubical in shape, clean and free from dirt of any other foreign material. The brick bats shall be of 40 mm. to 50 mm. size

otherwise specified in the item. The underburnt over burnt brick bats shall not be

14.2 The brick bats shall be measured by volume by suitable boxes or as directed.

M 15. Brick

15.1 The bricks shall be hand or machine moulded and made from suitable soils and klin burnt. They shall be free from crack and nodules of free lime. They shall have smooth rectangular faces with sharp corners and shall be of uniform colour.

The bricks shall be moulded with a frog of 100 mm. x 40 mm. and 10 mm. to 20 mm. deep on one of its flat sides. The bricks shall not break when thrown on the ground from a height of 600 mm.

15.2 The size of modular bricks shall be 190 mm. x 90 mm. x 90 mm.,

15.3 The size of the conventional bricks shall be as under
(9" X 4.3/8" X 2.3/4") 225 X 110 X 75 mm.

15.4 Only bricks of one standard size shall be used on one work. The following tolerances shall be permitted in the conventional size adopted in a particular work.

Length + 1/81" (3.0 mm.) Width: + 1/1611 (1.50 mm.) Height: + 1/611 (1.50 mm.)

15.5 The crushing strength of the bricks shall not be less than 35 Kg./Sq.Cm. The average water absorption shall not be more than 20 percent by weight. Necessary tests for crushing strength and water absorption etc. shall be carried out as per I.S. 3495 (Part I to IV) 1976.

M 16 Stone

16.1 The stone shall be of the specified variety such as Granite / Trap Stone / Quarzite or any other type of good hard stones. The stones shall be obtained only from the approved quarry and shall be hard, sound, durable and free from defects like cavities, cracks, sand holes, flaws, injurious veins, patches of loose or soft materials etc. and weathered portions and other structural defects or imperfections tending to affect their soundness and strength. The stone with round surface shall not be used. The percentage of water absorption shall not be more than 5% of dry weight, when tested in accordance with I.S. 1134 1974. The minimum crushing, strength of the stone shall be 200 Kg./Sq.Cm. unless otherwise specified.

16.2 The samples of the stone to be used, shall be got approved before the work is started.

16.3 The Khanki facing stone shall be dressed by chisel as specified in the item "or khanki facing in required shape and size. The face of stone shall be so dressed that the bushing, on the exposed face shall not project by more than 40 mm. from the general wall surface and on face to be plastered it shall not project by more than 19 mm. nor shall it have depressions more than 10 mm. from the average wall surface.

M 17. Laterite Stone

17.1 Laterite stone shall be obtained from the approved quarry. It shall be compacted in texture, sound, durable and free from soft patches. It shall have a minimum crushing strength of 100 Kg./Sq.Cm. in its dry condition. It shall not absorb water more than 20% of its own weight when immersed for 24 hours in water. After quarrying the stone shall be allowed to weather for some time before using in work.

17.2 The stone shall be dressed into regular rectangular blocks so that all faces are free from

waviness and unevenness, edges true and square.

17.3 Those types of stone in which white clay occurs, should not be used.

M 18. Mild Steel Bars

18.1 Mild steel bars reinforcement for R.C.C. work shall conform to I.S. 432 (Part 11) 1966 and shall be of tested quality. It shall also comply with relevant part of I.S. 456 1978.

18.2 All the reinforcement shall be clean and free from dirt, paint, grease, mill scale or loose or thick rust at the time of placing.

18.3 For the purpose of payment, the bar shall be measured correct up to 100 mm. length and weight payable worked out at the rate specified below

1	6 mm	0.22 Kg/Rmt	8	20 mm	2.47 Kg/Rmt
2	8 mm	0.39 Kg/Rmt	9	22 mm	2.98 Kg/Rmt
3	10 mm	0.62 Kg/Rmt	10	25 mm	3.85 Kg/Rmt
4	12 mm	0.89 Kg/Rmt	11	28 mm	4.83 Kg/Rmt
5	14 mm	1.21 Kg/Rmt	12	32 mm	6.31 Kg/Rmt
6	16 mm	1.58 Kg/Rmt	13	36 mm	7.99 Kg/Rmt
7	18 mm	2.00 Kg/Rmt	14	40 mm	9.86 Kg/Rmt

M 19. High Yield Strength Steel Deformed Bars

19.1 High yield strength steel deformed bars be either cold twisted or hot rolled, shall conform to I.S. 11739 1966 and I.S. 11,39 1966 respectively.

19.2 Other provision and requirements shall conform to No. M 18 for Mild steel bars.

M 20 High Tensile Steel Wires

20.1 The high tensile wires for the use in prestressed concrete work shall conform to I.S. 2090 1962.

20.2 The tensile strength of the high tensile steel bars shall be as specified in the Item. In absence of the given strength, the minimum Strength shall be taken as per para 6.1 of I.S. 1785 1962. Testing, shall be done per I.S. requirements.

20.3 The high tensile steel shall be free from loose mill scale, rust oil, grease, or any other harmful matter. Cleaning of steel bars may be carried out by immersion in solvent solution, wire brushing or passing through a pressure box containing carborundum.

20.4 The high tensile wire shall be obtained from manufactures in coil having diameter not less than 350 times the diameter of wire its (If so that wire springs back straight on being uncoiled.

Name of Work: Work of Widening, Strengthening and Resurfacing of various road as and when required or in emergency under Panchayat R&B Division, Junagadh (Annual Rate Basis)

SPECIFICATIONS OF MATERLAIS (AS PER MORTH PROVISION)

GENERAL SPECIFICATION OF MATERIALS FOR INSTRUCTURES

as per Guidelines of the MORTH for road works

1001. GENERAL

Materials to be used in the work shall conform to the specifications mentioned on the drawings the requirements laid down in this section and specifications for relevant items of work covered under these specifications.

If any material, not covered in these specifications, is required to be used in the work, it shall conform to relevant Indian Standards, if there are any, or to the requirements specified by, the Engineer.

1002. SOURCES OF MATERIAL

The Contractor shall notify, the Engineer of his proposed sources of materials prior to delivery. If it is found after trial that sources of supply previously approved do not produce uniform and satisfactory products, or if the product from any other source proves unacceptable at any time, the Contractor shall furnish acceptable material from other sources at his own expense.

1003. BRICKS

Burnt clay bricks shall conform to the requirements of IS:1077, except that the minimum compressive strength when tested flat shall not be less than 8.4 MPa for individual bricks and 10.5 MPa for average of 5 specimens. They shall be free from cracks and flaws and nodules of free lime. The brick shall have smooth rectangular faces with sharp corners and emit a clear ringing sound when struck. The size may be according to local practice with a tolerance of ± 5 per cent.

1004. STONES

Stones shall be of the type specified. It shall be hard, sound, and free from cracks, decay and weathering and shall be freshly quarried from an approved quarry. Stone with round surface shall not be used.

The stones, when immersed in water for 24 hours, shall not absorb water by more than 5 per cent of their dry weight when tested in accordance with IS:1124.

The length of stones shall not exceed 3 times its height nor shall they be less than twice its height plus one joint. No stone shall be less in width than the height and width on the base shall not be greater than three fourth of the thickness of the wall nor less than 150 mm.

1005. CAST IRON

Cast iron shall conform to IS:210. The grade number of the material shall not be less than 14.

1006. CEMENT

Cement to be used in the works shall be any of the following types with the prior

approval of the Engineer :

- a) Ordinary Portland Cement, 33 Grade, conforming to IS:269.
- b) Rapid Hardening Portland Cement, conforming to IS:8041.
- c) Ordinary Portland Cement. 43 Grade, conforming to IS:8112.
- d) Ordinary Portland Cement. 53 Grade, conforming to IS:12269.
- e) Sulphate Resistant Portland Cement, conforming to IS:12330.

Cement conforming to IS:269 shall be used only after ensuring that the minimum required design strength can be achieved without exceeding the maximum permissible cement content of 540 kg/cu.m. of concrete.

Cement conforming to IS:8112 and IS:12269 may be used provided the minimum cement content mentioned elsewhere from durability considerations is not reduced. From strength considerations, these cements shall be used with a certain caution as high early strengths of cement in the 1 to 28 day range can be achieved by finer grinding and higher constituent ratio of C3S/C2S, where C3S is Tri-calcium Silicate and C2S is Di-calcium Silicate. In such cements, the further growth of strength beyond say 4 weeks may be much lower than that traditionally expected. Therefore, further strength tests shall be carried out for 56 and 90 days to fine tune the mix design from strength

Cement conforming to IS:12330 shall be used when sodium sulphate and magnesium sulphate are present in large enough concentration to be aggressive to concrete. The recommended threshold values as per IS:456 are sulphate concentration in excess of 0.2 per cent in soil substrata or 300 ppm (0.03 per cent) in ground water. Tests to confirm actual values of sulphate concentration are essential when the structure is located near the sea coast, chemical factories, agricultural land using chemical fertilizers and sites where there are effluent discharges or where soluble sulphate bearing ground water level is high. Cement conforming to IS:12330 shall be carefully selected from strength considerations to ensure that the minimum required design strength can be achieved without exceeding the maximum permissible cement content of 540 kg/ cu.m. of concrete.

Cement conforming to IS:8041 shall be used only for precast concrete products after specific approval of the Engineer.

Total chloride content in cement shall in no case exceed 0.05 per cent by mass of cement. Also, total sulphur content calculated as sulphuric anhydride (SO₃) shall in no case exceed 2.5 per cent and 3.0 per cent when tri calcium aluminate per cent by mass is upto 5 or greater than 5 respectively.

1007. COARSE AGGREGATES

For plain and reinforced cement concrete (PCC and RCC) or prestressed concrete (PSC) works, coarse aggregate shall consist of clean, hard, strong, dense, non porous and durable pieces of crushed stone, crushed gravel, natural gravel or a suitable combination thereof or other approved inert material. They shall not consist of pieces of disintegrated stones, soft, flaky, elongated particles, salt, alkali, vegetable matter or other deleterious materials in such quantities as to reduce the strength and durability of the concrete, or to attack the steel reinforcement. Coarse aggregate having positive alkali-silica reaction shall not be used. All coarse aggregates shall conform to IS:383 and tests for conformity shall be carried out as per IS:2386, Parts I to VIII.

The contractor shall submit for the approval of the Engineer, the entire information indicated in Appendix A of IS:383.

Maximum nominal size of coarse aggregate for various structural components in PCC, RCC or PSC, shall conform to Section 1700.

The maximum value for flakiness index for coarse aggregate shall not exceed 35 per

The coarse aggregate shall satisfy the following requirements of grading :

TABLE 1000 1 : REQUIREMENTS OF COARSE AGGREGATE

IS Sieve Size	Per cent by Weight passing the Sieve		
	40mm	20mm	12.5mm
63mm	100	-	-
40mm	95-100	100	-
20mm	30-70	95-100	100
12.5mm	-	-	90-100
10mm	10-35	25-35	40-85
4.75mm	0-5	0-10	0-10

1008. SAND/FINE AGGREGATES

For masonry work, sand shall conform to the requirements of IS: 2 116.

For plain and reinforced cement concrete (PCC and RCC') or prestressed concrete (PSQ works, Fine aggregate shall consist of clean, hard, strong and durable pieces of crushed stone, crushed gravel, or a suitable combination of natural sand, crushed stone or gravel. They shall not contain dust, lumps, soft or flaky, materials, mica or other deleterious material's in such quantities as to reduce the strength and durability of the concrete, or to attack the embedded steel. Motorised sand washing machines should be used to remove impurities from sand. Fine aggregate having positive alkali silica reaction shall not be used. All fine aggregates shall conform to IS:383 and tests for conformity shall be carried out as per IS:2386, (Parts 1 to VIII). The Contractor shall submit to the Engineer the entire information indicated in Appendix A of IS:383. The Fineness modulus of fine aggregate shall neither be less than 2.0 nor greater than 3.5.

Sand/fine aggregate for structural concrete shall conform to the following grading requirements :

TABLE 1000 2

IS Sieve Size	Per cent by Weight Passing the Sieve		
	Zone I	Zone II	Zone III
10mm	100	100	100
4.75mm	90-100	90-100	90-100
2.36mm	60-95	75-100	85-100
1.18mm	30-70	55-90	75-100
600 micron	15-34	35-59	60-79
300 micron	5-20	8-30	12-40
150 micron	0-10	0-10	0-10

1010. WATER

Water used for mixing and curing shall be clean and free from injurious amounts of oils, acids, alkalis, salts, sugar, organic materials or other substances that may be deleterious to concrete or steel. Potable water is generally considered satisfactory for mixing concrete. Mixing and curing with sea water shall not be permitted. As a guide, the following concentrations represent the maximum permissible values

- (a) To neutralise 200 ml sample of water, using phenolphthalein as an indicator, it should not require more than 2 ml of 0.1 normal NaOH.
- (b) To neutralise 200 ml sample of water, using methyl orange as an indicator, it should not require more than 10 ml of 0.1 normal HCl.
- (c) The permissible limits for solids shall be as follows when tested in accordance with IS:3025 :

	Permissible (max)	Limits
Organic	200 mg/lit	
Inorganic	3000 mg/lit	
Sulphates (SO)	500 mg/lit	
Chlorides (Cl)	500 mg/lit*	
Suspended matter	2000 mg/lit	

- * In case of structures of lengths 30m and below, the permissible limit of chlorides may be increased upto 1000 mg/lit

All samples of water (Including potable water) shall be tested and suitable measures taken where necessary to ensure conformity of the water to the requirements stated herein

- (d) The pH value shall not be less than 6.

1012. CONCRETE ADMIXTURES

1012.1 General

Admixtures are materials added to the concrete before or during mixing with a view to modify one or more of the properties of concrete in the plastic or hardened state.

Concrete admixtures are proprietary items of manufacture and shall be obtained only from established manufacturers with proven track record, quality assurance and full fledged laboratory facilities for the manufacture and testing of concrete.

The contractor shall provide the following information concerning each admixture after obtaining the same from the manufacturer :

- (a) Normal dosage and detrimental effects, if any, of under dosage and over dosage.
- (b) The chemical names of the main ingredients in the admixtures.
- (c) The chloride content, if any, expressed as a percentage by the weight of the admixture
- (d) Values of dry material content, ash content and relative density of the admixture which can be used for Uniformity Tests.

- (e) Whether or not the admixture leads to the entertainment of air when used as per the manufacturers recommended dosage, and if so to what extent
- (f) Where two or more admixtures are proposed to be used in any one mix, confirmation as to their compatibility.
- (g) There would be no increase in risk of corrosion of the reinforcement or other embedment as a result of using the admixture.

1012.2. Physical and Chemical Requirements

Admixtures shall conform to the requirements of IS:9103. In addition, the following conditions shall be satisfied :

- (a) "Plasticizers" and "Super Plasticizers" shall meet the requirements indicated for "Water reducing Admixture".
- (b) Except where resistance to freezing and thawing and to disruptive action of deicing salts is necessary, the air content of freshly mixed concrete in accordance with the pressure method given in IS:1199 shall not be more than 2 per cent higher than that of the corresponding control mix and in any case not more than 3 per cent of the test mix.
- (c) The chloride content of the admixture shall not exceed 0.2 per cent when tested in accordance with IS:6925. In addition, the maximum permissible limit of chloride content of all the constituents as indicated in Section 1700 shall also be observed.
- (d) Uniformity tests on the admixtures are essential to compare qualitatively the composition of different samples taken from batch to batch or from the same batch at different times.

The tests that shall be performed along with permissible variations in the same are indicated below:

- Dry Material Content : to be within 3 per cent and 5 per cent of liquid and solid admixtures respectively of the value stated by the manufacturer.
- Ash content : to be within 1 per cent of the value stated by the manufacturer.

Relative Density (for liquid admixtures) : to be within 2 per cent of the value stated by the manufacturer.

- (e) All tests relating to the concrete admixtures shall be conducted periodically at an independent laboratory and compared with the data given by the manufacturer.

1014. STORAGE OF MATERIALS

1014.1 General

All materials may be stored at proper places so as to prevent their deterioration or intrusion by foreign matter and to ensure their satisfactory quality and fitness for the work. The storage space must also permit easy inspection, removal and restorage of the materials. All such materials even though stored in approved godowns/places, must be subjected to acceptance test prior to their immediate use.

1014.3 Aggregates

Aggregate stockpiles may be made on ground that is denuded or vegetation is hard and

well drained. If necessary the ground shall be covered with 50 mm plank.

Coarse aggregates, unless otherwise agreed by the Engineer in writing, shall be delivered to the site in separate sizes (2 sizes when nominal size is 25 mm or less and 3 sizes when the nominal size is 32 mm or more). Aggregates placed directly on the ground shall not be removed from the stockpile within 30 cm of the ground until the final cleaning up of the work, and then only the clean aggregate will be permitted to be used.

In the case of fine aggregates, these shall be deposited at the mixing site not less than 8 hours before use and shall have been tested and approved by the Engineer.

1014.4 Cement

Cement shall be transported, handled and stored on the site in such a manner as to avoid deterioration or contamination. Cement shall be stored above ground level in perfectly dry and watertight sheds and shall be stacked not more than eight bags high. Wherever bulk storage containers are used their capacity should be sufficient to cater to the requirement at site and should be cleaned at least once every 3 to 4 months.

Each consignment shall be stored separately so that it may be readily identified and inspected and cement shall be used in the sequence in which it is delivered at site. Any consignment or part of a consignment of cement which has deteriorated in any way, during storage, shall not be used in the works and shall be removed from the site by the Contractor without charge to the Employer.

The Contractor shall prepare and maintain proper records on site in respect of delivery, handling, storage and use of Cement and these records shall be available for inspection by the Engineer at all times.

The Contractor shall make a monthly return to the Engineer on the date corresponding to the interim certificate date, showing the quantities of cement received and issued during the month and in stock at the end of the month.

1014.5 Reinforcement /Untensioned Steel

The reinforcement bars, when delivered on the job, shall be stored above the surface of the ground upon platforms, skids, or other supports, and shall be protected from mechanical injury and from deterioration by exposure.

1014.6 Prestressing Materials

All prestressing steel, sheathing, anchorages and sleeves or coupling must be protected during transportation, handling and storage. The prestressing steel, sheathing and other accessories must be stored under cover from rain or damp ground and protected from the ambient atmosphere if it is likely to be aggressive. Storage at site must be kept to the absolute minimum.

- (A) Tendon : Wire, strand and bar from which tendons are to be fabricated shall be stored about 300mm above the ground in a suitably covered and closed space so as to avoid direct climatic influences and to protect them from splashes from any other materials and from the cutting operation of an oxy acetylene torch or arc welding process in the vicinity. Under no circumstances, tendon material shall be subjected to any welding operation or on site heat treatment or metallic coating such as galvanising. Storage facilities and the procedures for transporting material into or out of store, shall be such that the material does not become kinked or notched. Wire or strand shall be stored in

large diameter coils which enable the tendons to be laid out straight. As a guide, for wires above 5 mm dia, coils of about 2m dia without breaks or joints shall be obtained from manufacturer and stored. Protective wrapping for tendons shall be chemically neutral. All prestressing steel must be provided with temporary protection during storage.

- (B) Anchorage Components :** The handling and storing procedures shall maintain the anchorage components in a condition in which they can subsequently perform their function to an adequate degree. Components shall be handled and stored so that mechanical damage and detrimental corrosion are prevented. The corrosion of the gripping and securing system shall be prevented. The use of correctly formulated oils and greases or of other corrosion preventing material is recommended where prolonged storage is required. Such protective material shall be guaranteed by the producer to be non aggressive and non degrading.

Prestressing steel shall be stored in a closed store having single door with double locking arrangements and no windows. Also the air inside the store shall be kept dry as far as possible by using various means to the satisfaction of the Engineer. Also instrument measuring the air humidity shall be installed inside the store. This is with a view to eliminating the possibility of initial rusting of prestressing steel during storage. The, prestressing, steel shall be coated with water solvable grease. The prestressing steel should be absolutely clean and without any signs of rust.

All prestressing steel shall be stored at least 30 cm above ground level and it shall be invariably wrapped by protective cover of tar paper or polythene or any other approved material.

The Contractor should see that prestressing steel shall be used within 3 months of its manufacture. He should chalk out his programme in this respect precisely, so as to avoid initial corrosion before placing In position.

1014.7 Water

Water shall be stored in containers/tanks covered at top and cleaned at regular intervals in order to prevent intrusion by foreign matter or growth of organic matter. Water from shallow, muddy or marshy surface, shall not be permitted. The intake pipe shall be enclosed to exclude silt, mud grass and other solid materials and there shall be a minimum depth of 0.60 m of water below the intake at all times.

1015 TESTS AND STANDARD OF ACCEPTANCE

All materials, even though stored in an approved manner shall be subjected to an acceptance test prior to their immediate use.

Independent testing of cement for every consignment shall be done by, the Contractor at site in the laboratory approved by the Engineer before use. Any cement with lower quality than those shown in manufacturer's certificate shall be debarred from use. In case of imported cement, the same series of tests shall be carried out before acceptance.

1015.1. Testing and Approval of Material

The Contractor shall furnish test certificates from the manufacturer/ supplier of materials along with each batch of material(s) delivered to site.

The Contractor shall set up a field laboratory with necessary equipment for testing of all materials, finished products used in the construction as per requirements of conditions of contract and the relevant specifications. The testing of all the materials shall be carried out by the Engineer or his representative for, which the Contractor shall make all the necessary arrangements and bear the entire cost.

Tests which cannot be carried out in the field laboratory have to be got done at the Contractor's cost at any recognised laboratory / testing establishments approved by the Engineer.

1015.2. Sampling of Materials

Samples provided to the Engineer or his representatives for their retention are to be in labelled boxes suitable for storage.

Samples required for approval and testing must be supplied well in advance by at least 48 hours or minimum period required for carrying out relevant tests to allow for testing and approval. Delay to works arising from the late submission of samples will not be acceptable as a reason for delay in the completion of the works.

If materials are brought from abroad, the cost of sampling/testing whether in India or abroad shall be borne by the Contractor.

1015.3. Rejection of Materials not conforming to the Specifications

Any stock or hatch of material(s) of which sample(s) does not conform to the prescribed tests and quality shall be rejected by the Engineer or his representative and such materials shall be removed from site by the Contractor at his own cost. Such rejected materials shall not be made acceptable by any modification.

1015.4. Testing and Approval of Plant and Equipment

All plants and equipment used for preparing, testing and production of materials for incorporation into the permanent works shall be in accordance with manufacturer's specifications and shall be got approved by the Engineer before use.

Name of Work: Work of Widening, Strengthening and Resurfacing of various road as and when required or in emergency under Panchayat R&B Division, Junagadh (Annual Rate Basis)

902. CONTROL OF ALIGNMENT, LEVEL AND SURFACE REGULARITY

902.1 General

All works performed shall conform to the lines, grades, cross sections and dimensions shown on the drawings or as directed by the Engineer, subject to the permitted tolerances described herein-after:

902.2 Horizontal Alignment

Horizontal alignments shall be reckoned with respect to the centre line of the carriageway as shown on the drawings. The edges of the carriageway as constructed shall be correct within a tolerance of ± 10 mm there from. The corresponding tolerance for edges of the roadway and lower layers of pavement shall be ± 25 mm.

902.3 Surface Levels

The levels of the subgrade and different pavement courses as constructed, shall not vary from those calculated with reference to the longitudinal and cross-profile of the road shown on the drawings or as directed by the Engineer beyond the tolerances mentioned in Table 900-1.

TABLE 900-T. TOLERANCES IN SURFACE LEVELS

1.	Subgrade	+20MM -25MM
2.	Sub-base + 10 mm	-20MM
	(a) Flexible pavement	+6MM
	(b) Concrete pavement [Dry clean concrete or Rolled concrete]	-10MM
3.	Base-course for flexible pavement	+6MM
	(a) Bituminous course	-6MM
	(b) Other than bituminous	+10MM
	(i) Machine laid	-10MM +15M
	(ii) Manually laid	-15MM
4.	Wearing course for flexible pavement	+6MM
	(a) Machine laid	-6MM
	(b) Manually kid	+10MM -10MM
5.	Cement concrete pavement	+5MM -6MM*

* This may not exceed - 8 mm at 0 - 30 cm from the edges.

Provided, however, that the negative tolerance for wearing course shall not be permitted in conjunction with the positive tolerance for base course, if the thickness of the former is thereby reduced by more than 6mm for flexible pavements and 5 mm for concrete pavements.

For checking compliance with the above requirement for subgrade, sub-base and base courses, measurements of the surface levels shall be taken on , a grid of points placed at 6.25 m longitudinally and 3.5 m transversely. For any 10 consecutive measurements taken longitudinally or transversely, not more than one measurement shall be permitted to exceed the tolerance as above, this one measurement being not in excess of 5 mm above the permitted tolerance.

For checking the. compliance with the above requirement for bituminous wearing courses and concrete pavements, measurements of the surface levels shall be taken on a grid of points spaced at 6.25 m along the length and at 0.5 m from the edges and at the centre of the pavement. In any length of pavement, compliance shall be deemed to be met for the final road surface, only if the tolerance given above is satisfied for any point on the surface.

902.4 Surface Regularity of Pavement Courses

The longitudinal profile shall be checked with a 3 metre long straight edge/moving straight-edge as desired by the Engineer at the middle of each traffic lane along a line parallel to the centre line of the road.

The maximum permitted number of surface irregularities shall be as per Table 900-2.

TABLE 900-2. MAXIMUM PERMITTED NUMBER OF SURFACE IRREGULARITIES

Irregularity Length(m)	Surfaces of carriageways paved shoulders				Surfaces of laybys, service areas and all bituminous base and courses			
	4 MM		7 MM		4 MM		7 MM	
National Highways/ Expressways	300	75	300	75	300	75	30	75
Roads of lower category*	20	9	2	1	40	18	4	2
	40	18	4	2	60	27	6	3

* Category of each section of road as described in the Contract

The maximum allowable difference between the road surface and underside of a 3 m straight-edge when placed parallel with, or at right angles to the centre line of the road at points decided by the Engineer shall be:

for pavement surface (bituminous and cement concrete)	3 mm
for bituminous base courses	6 mm
for granular sub-base/ base courses	8 mm
for sub-bases under concrete pavements	10 mm
Quality Control for Road Works	

902.5 Rectification

Where the surface regularity of subgrade and the various pavement courses fall outside the specified tolerances, the Contractor shall be liable to rectify these in the manner described below and to the satisfaction of the Engineer.

- (i) **Subgrade:** Where the surface is high, it shall be trimmed and suitably compacted. Where the same is low, the deficiency shall be corrected by scarifying the lower layer

fresh material and recompacting to the required density. The degree of compaction and the type of material to be used shall conform to the requirements of Clause 305.

(ii) Granular Sub-base: Same as at (i) above, except that the degree of compaction and the type of material to be used shall conform to the requirements of Clause 401.

(iii) Lime/Cement Stabilized Soil Sub-base: For lime/cement treated materials where the surface is high, the same shall be suitably trimmed while taking care that the material below is not disturbed due to this operation. However, where the surface is low, the same shall be corrected as described herein below.

For cement treated material, when the time elapsed between detection of irregularity and the time of mixing of the material is less than 2 hours, the surface shall be scarified to a depth of 50 mm supplemented with freshly mixed materials as necessary and recompacted to the relevant specification. When this time is more than 2 hours, the full depth of the layer shall be removed from the pavement and replaced with fresh material to Specification. This shall also apply to lime treated material except that the time criterion shall be 3 hours instead of 2 hours.

(iv) Water Bound Macadam/Wet Mix Macadam Sub-base/Base: Where the surface is high or low, the top 75 mm shall be scarified, reshaped with added material as necessary and recompacted to Clause 404. This shall also apply to wet mix macadam to Clause 406.

(v) Bituminous Constructions: For bituminous construction oilier than wearing course, where the surface is low, the deficiency shall be corrected by adding fresh material over a suitable tack coat if needed and recompacting to specifications. Where the surface is high, the full depth of the layer shall be removed and replaced with fresh material and compacted to specifications.

For wearing course, where the surface is high or low, the full depth of the layer shall be removed and replaced with fresh material and compacted to specifications. In all cases where the removal and replacement of a bituminous layer is involved, the area treated shall not be less than 5 m in length and not less than 3-5 m in width.

(vi) Dry Lean Concrete Sub-base/Rolled Cement Concrete: The defective length of the course shall be removed to full depth and replaced with material conforming to Clauses 601 or 603, as applicable. The area treated shall be at least 3 m long, not less than 1 lane wide and extend to the full depth. Before relaying the course, the disturbed subgrade or layer below shall be corrected by levelling, watering and compacting.

(vii) Cement concrete pavement: The defective areas having surface irregularity exceeding 3 mm but not greater than 6 mm may be rectified by bump cutting or scrubbling or grinding using approved equipment. When required by the Engineer, areas which have been reduced in level by the above operation(s) shall be retextured in an approved manner either by cutting grooves (5 mm deep) or roughening the surface by hacking the surface. If high areas in excess 6 mm or low areas in excess of 3 mm occur, exceeding the permitted numbers and if the Contractor cannot rectify, the slab shall be demolished and reconstructed at the Contractor's expense and in no case the area removed shall be less than the full width of the lane in which the irregularity occurs and full length of the slab. If deemed necessary by the Engineer, any section of the slab which deviates from the specified levels and tolerances shall

112. ARRANGEMENT FOR TRAFFIC DURING CONSTRUCTION

112.1. General

The Contractor shall at all times carry out work on the highway in a manner creating least interference to the flow of traffic while consistent with the satisfactory execution of the same. For all works involving improvements to the existing highway, the Contractor shall, in accordance with the directives of the Engineer, provide and maintain, during execution of the work, a passage for traffic either along a part of the existing carriageway under improvement, or along a temporary diversion constructed close to the highway. The Contractor shall take prior approval of the Engineer regarding traffic arrangements during construction.

112.2. Passage of Traffic along a part of the Existing Carriageway under Improvement

For widening/strengthening existing carriageway where part width of the existing carriageway is proposed to be used for passage of traffic, treated shoulders shall be provided on the side on which work is not in progress. The treatment to the shoulder shall consist of providing at least 150 mm thick granular base course covered with bituminous surface dressing in a width of at least 1.5 m and the surface shall be maintained throughout the period during which traffic uses the same to the satisfaction of the Engineer. The continuous length, in which such work shall be carried out, would be limited normally to 500 m at a place. However, where work is allowed by the Engineer in longer stretches passing places at least 20 m long with additional paved width of 2.5 m shall be provided at every 0.5 km interval.

In case of widening existing two-lane to four-lane, the additional two lanes would be constructed first and the traffic diverted to it and only thereafter the required treatment to the existing carriageway would be carried out. However, in case where on the request of the Contractor, work on existing two-lane carriageway is allowed by the Engineer with traffic using part of the existing carriageway, stipulations as in Para above shall apply.

After obtaining permission of the Engineer, the treated shoulder shall be dismantled, the debris disposed of and the area cleared as per the direction of the

112.3. Passage of Traffic along a Temporary Diversion

In stretches where it is not possible to pass the traffic on part width of the carriageway, a temporary diversion shall be constructed with 7 m carriageway and 2.5 m earthen shoulders on each side (total width of roadway 12 m) with the following provision for road crust in the 7 m width:

- (i) 200 mm (compacted) granular sub base;
- (ii) 225 mm (compacted) granular base course; and
- (iii) Premix carpet with Seal Coat/Mix Seal Surfacing.

The alignment and longitudinal section of diversion including junctions and temporary cross drainage provision shall be as approved by the Engineer.

112.4. Traffic Safety and Control

The Contractor shall take all necessary measures for the safety of traffic during construction and provide, erect and maintain such barricades, including signs,

markings, flags, lights and flagmen as may be required by the Engineer for the information and protection of. Traffic approaching or passing through the section of the highway under improvement. Before taking up any construction, an agreed phased programme for the diversion of traffic on the highway shall be drawn up in consultation with the Engineer.

The barricades erected on either side of the carriageway/portion of the carriageway closed to traffic, shall be of strong design to resist violation, and painted with alternate black and white stripes. Red lanterns or warning lights of similar type shall be mounted on the barricades at night and kept lit throughout from sunset to sunrise.

At the points where traffic is to deviate from its normal path (whether on temporary diversion or part width of the carriageway) the channel for traffic shall be clearly marked with the aid of pavement markings, painted drums or a similar device to the directions of the Engineer. At night, the passage shall be delineated with lanterns or other suitable light source.

One-way traffic operation shall be established whenever the traffic is to be passed over part of the carriageway inadequate for two-lane traffic. This shall be done with the help of temporary traffic signals or flagmen kept positioned on opposite sides during all hours. For regulation of traffic, the flagmen shall be equipped with red and green flags and lanterns/lights.

On both sides, suitable regulatory/warning signs as approved by the Engineer shall be installed for the guidance of road users. On each approach, at least two signs shall be put up, one close to the point where transition of carriageway begins and the other 120m away. The signs shall be of approved design and of reflectory type, if so directed by the Engineer.

112.5. Maintenance of Diversions and Traffic Control Devices

Signs, lights, barriers and other traffic control devices, as well as the riding surface of diversions shall be maintained in a satisfactory condition till such time they are required as directed by the Engineer. The temporary travelled way shall be kept free of dust by frequent applications of water, if necessary.

901. GENERAL

- 901.1** All materials to be used, all methods adopted and all works performed shall be strictly in accordance with the requirements of these specifications. The Contractor shall set up a field laboratory at locations approved by the Engineer and equip the same with adequate equipment and personnel in order to carry out all required tests and Quality Control work per Specifications and/or as directed by the Engineer. The internal layout of the laboratory shall be as per Clause 121 and/or as directed by the Engineer. The list of equipment and the facilities to be provided shall be got approved from the
- 901.2** The Contractor's laboratory should be manned by a qualified Materials Engineer/Civil Engineer assisted by experienced technicians, and the set-up should be got approved by the Engineer.
- 901.3** The Contractor shall carry out quality control tests on the materials and work to the frequency stipulated in subsequent paragraphs. In the absence of clear indications about method and or frequency of tests for any item, the instructions of the Engineer shall be followed.
- 901.4** For satisfying himself about the quality of the materials and work, quality

control tests will also be conducted by the Engineer (by himself, by his Quality Control Units or by any other agencies deemed fit by him), generally to the frequency set forth here in under. Additional tests may also, be conducted where, in the opinion of the Engineer, need for such tests exists.

- 901.5** The Contractor shall provide necessary co-operation and assistance in obtaining the samples for tests and carrying out the field tests required by the Engineer from time to time. This may include provision of labour, attendants, assistance in packing and despatching and any other assistance considered necessary in connection with the tests.
- 901.6** For the work of embankment, subgrade and pavement, construction of subsequent layer of same or other material over the finished layer shall be done after obtaining permission from the Engineer. Similar permission from the Engineer shall be obtained in respect of all other items of works prior to proceeding with the next stage of construction.
- 901.7** The Contractor shall carry out modifications in the procedure of work, if found necessary, as directed by the Engineer during inspection. Works falling short of quality shall be rectified/redone by the Contractor at his own cost, and defective work shall also be removed from the site of works by the Contractor at his own cost.
- 901.8** The cost of laboratory building including services, essential supplies like water, electricity, sanitary services and their maintenance and cost of all equipment, tools, materials, labour and incidentals to perform tests and other operations of quality control according to the Specification requirements shall be deemed to be incidental to the work and no extra payment shall be made for the same. If, however, there is a separate item in the Bill of Quantities for setting up of a laboratory and installing testing equipment, such work shall be paid for separately.
- 901.9** For testing of samples of soils/soil mixes, granular materials, and mixes, bituminous materials and mixes, aggregates, cores etc., samples in the required quantity and form shall be supplied to the Engineer by the Contractor at his own cost.
- 901.10** For cement, bitumen, mild steel, and similar other materials where essential tests are to be carried out at the manufacturer's plants or at laboratories other than the site laboratory, the cost of samples, sampling, testing and furnishing of test certificates shall be borne by the Contractor. He shall also furnish the test certificates to the Engineer.
- 901.11** For testing of cement concrete at site during construction, arrangements for supply of samples, sampling, testing and supply of test results shall be made by the Contractor as per the frequency and number of tests specified in the Handbook of Quality Control for Construction of Roads and Runways (IRC :SP 11) and relevant IS Codes or relevant clauses of these Specifications, the cost of which shall be borne by the Contractor.
- 901.12** The method of sampling and testing of materials shall be as required by the "Handbook of Quality Control for Construction of Roads and Runways" (IRC : SP: 11), and these MOST Specifications. Where they are contradicting, the provision in these Specifications shall be followed, Where they are silent, sound engineering practices shall be adopted. The sampling and testing procedure to be used shall be as approved by the Engineer and his decision shall be final and binding on the Contractor.

901.13 The materials for embankment construction shall be got approved from the Engineer. The responsibility for arranging and obtaining the land for borrowing or exploitation in any other way shall rest with the Contractor who shall ensure smooth and uninterrupted supply of materials in the required quantity during the construction period.

901.14 Defective Materials

All materials which the Engineer/his representative has determined as not conforming to the requirements of the Contract shall be rejected whether in place or not; they shall be removed immediately from the site as directed. Materials, which have been subsequently corrected, shall not be used in the work unless approval is accorded in writing by the Engineer. Upon failure of the Contractor to comply with any order of the Engineer/his representative, given under this Clause, the Engineer/his representative shall have authority to cause the removal of rejected material and to deduct the removal cost thereof from any payments due to the Contractor.

901.15 Imported Materials

At the time of submission of tenders, the Contractor shall furnish a list of materials/finished products manufactured, produced or fabricated outside India which he proposes to use in the work. The Contractor shall not be entitled to extension of time for acts or events occurring outside India and it shall be the Contractor's responsibility to make timely delivery to the job site of all such materials obtained from outside India.

The materials imported from outside India shall conform to the relevant Specifications of the Contract. In case where materials/ finished products are not covered by the Specifications in the Contract, the details of Specifications proposed to be followed and the testing procedure as well as laboratories/ establishments where tests are to be carried out shall be specifically brought out and agreed to in the Contract.

The Contractor shall furnish to the Engineer a certificate of compliance of the tests carried out. In addition, certified mill test reports clearly identified to the lot of materials shall be furnished at the Contractor's cost.

Item No 1.

Providing and laying 37.5 mm thick Bituminous Macadam with B.T. aggregate as per M.O.R.T. & H. specification and using emulsion RS-1 as per IS 8887: for tack coat @ 2.50 KG. / 10 Sq.m. with mechanical sprayer and Bulk asphalt VG-30 for mixing @ 34.00 KG. / M.T. i.e. 3.40 % of total weight of mix including heating and mixing the aggregate and asphalt in continuous of drum mix plant and hot laid process spreading the same by paver finisher and consolidation with roller as per M.O.R.T. & H specification to achieve desired density, including providing all materials equipments, tools and plants, fire wood, oil, kerosene, labour charges etc. complete using contractor's own machinery drum mix plant and paver finisher etc. complete.

The work shall be carried out using DRUM mix Plant and spreading the same with Paver Finisher and consolidation with vibratory road roller

The Bitumen Macadam 37.5mm thick shall be laid in ONE layers using VG-30 Grade Bulk bitumen for mixing at a rate of 34.00 Kg./M.T. and for Tack coat using Emulsion RS-1- grade bitumen at 2.5 Kg./10-Sqm. and spreading the same with paver finisher and consolidation with Vibratory road roller with all lead and lift as directed

504.1. Scope

This work shall consist of construction in a single course having 50 mm to 100 mm thickness or in multiple courses of compacted crushed aggregates premixed with a bituminous binder on a previously prepared base to the requirements of these Specifications. Since the bituminous macadam is an open-graded mix, there is a potential that it may trap water or moisture vapour within the pavement system. Therefore, adjacent layer (shoulders) should have proper drainage quality to prevent moisture-induced damage to the BM.

504.2. Materials**504.2.1. Bitumen:**

The bitumen shall be viscosity graded paving bitumen complying with Indian Standard Specification for paving bitumen, IS:73 or as specified in the Contract. The type and grade of bitumen to be used would depend upon the climatic conditions and the traffic. Guidelines for selection of bitumen are given in Table 500-1.

504.2.2. Coarse Aggregates

The coarse aggregates shall consist of crushed rock, crushed gravel or other hard material retained on 2.36 mm sieve. It shall be clean, hard, durable and cubical shape, free from dust and soft organic and other deleterious substances. The aggregate shall satisfy the physical requirements specified in Table 500-6. Where crushed gravel is proposed for use as aggregate, not less than 90 percent by weight of the crushed material retained on 4.75 mm sieve shall have at least two fractured faces resulting from crushing operation. Before approval of the source, the aggregates shall be tested for stripping. Where the Contractor's selected source of aggregates have poor affinity for bitumen, as a condition for the approval of that source, the bitumen shall be treated with approved anti-stripping agents, as per the manufacturer's recommendations, without additional

504.2.3. Fine Aggregates

Fine aggregates shall consist of crushed or naturally occurring mineral material, or a combination of two, passing 2.36 mm sieve and retained on 75 micron sieve. It shall be clean, hard, durable, free from dust and soft organic and other deleterious substances.

Natural sand shall not be used in the binder course.

TABLE 500-6. Physical Properties of Coarse Aggregate

Property	Test	Specification	Method of Test
Cleanliness	Grain size analysis	Max 5% passing	IS:2386 Part I
Particle shape	Combined Flakiness and Elongation Indices*	Max 35%	IS:2386 Part I
Strength	Los Angeles Abrasion Value or Aggregate Impact Value	Max 35% Max 27%	IS:2386 Part IV
Durability	Soundness either: Sodium Sulphate or Magnesium Sulphate	Max 12% Max 18%	IS:2386 Part V
Water	Water Absorption	Max 2%	IS:2386 Part III
Stripping	Coating and Stripping of Bitumen Aggregate Mix	Minimum retained coating 95 %	IS:6241
Water Sensitivity	Retained Tensile Strength**	Min. 80%	AASHTO 283

* If the minimum retained tensile strength falls below 80 percent, use of anti stripping agent is recommended to meet the minimum requirements.

504.2.4. Aggregate Grading and Binder Content

The combined grading of the coarse aggregates and fine aggregates, when tested in accordance with IS:2386 Part 1, wet sieving method, shall conform to limits given in Table 500-8. The type and quantity of bitumen and appropriate thickness is also given in Table 500-7.

504.2.5. Proportioning of Material

The combined aggregate grading shall not vary from the lower limit on one sieve to the higher limit on the adjacent sieve to avoid gap grading. The aggregate may be proportioned and blended to produce a uniform mix complying with the requirements in Table 500-7. The binder content shall be within a tolerance of ± 0.3 percent by weight of total mix when individual specimens are taken for quality control tests in accordance with the provisions of Section 900.

504.3. Construction Operation

504.3.1. Weather and Seasonal Limitations

The provisions of Clause 501.5.1 shall apply

Table 500-7 : Aggregate Grading and Bitumen Content

Grading	1	2
Nominal maximum aggregate size*	40 mm	19 mm
Layer thickness	80 -10 mm	50 - 75 mm
IS Sieve size (mm)	Cumulative % by weight of total aggregate passing	
45	100	
37.5	90 - 100	
26.5	75 - 100	100
19	-	90 - 100
13.2	35 - 61	56 - 88

4.75	13 - 22	16 - 36
2.36	4 - 19	4 - 19
0.3	2 - 10	2 - 10
0.075	0 - 8	0 - 8
Bitumen content ** percent by mass of total mix	3.3**	3.4**

* Nominal maximum aggregate size is the largest specified sieve size upon which any of the aggregate material is retained.

** Corresponds to specific gravity of the Aggregate being 2.7. In case aggregates have specific gravity more than 2.7, bitumen content can be reduced proportionately. Further, for regions where highest daily mean air temperature is 30°C or lower and lowest daily mean air temperature is -10°C or lower, the bitumen content may be increased by 0.5 percent.

504.3.2. Preparation of the Base

The base on which bituminous macadam is to be laid shall be prepared, shaped and compacted to the required profile in accordance with Clauses 501.8 and 902.3 as appropriate, and a prime coat, shall be applied in accordance with Clause 502 where specified, or as directed by the Engineer. The surface shall be thoroughly swept clean by a mechanical broom, and the dust removed by compressed air. In locations where mechanical broom cannot get access, other approved methods shall be used as directed by the Engineer.

504.3.3. Tack Coat

A tack coat in accordance with Clause 503 shall be applied as required under the Contract or as directed by the Engineer.

504.3.4. Preparation and Transportation of the Mix

The provisions of Clauses 501.3 and 501.4 shall apply.

504.3.5. Spreading

The provisions of Clause 501.5.3 shall apply.

504.3.6. Rolling

Compaction shall be carried out in accordance with the provisions of Clauses 501.6 and

Rolling shall be continued until the specified density is achieved, or where no density is specified, until there is no further movement under the roller. The required frequency of testing is defined in Clause 903.

504.4. Surface Finish and Quality Control of Work

The surface finish of the completed construction shall conform to the requirements of Clause 902. For control of the quality of materials and the works carried out, the relevant provisions of Section 900 shall apply.

504.5. Protection of the Layer

The bituminous macadam shall be covered with either the next pavement course or wearing course, as the case may be, within a maximum of forty-eight hours. If there is to be any delay, by the Contractor the course shall be covered by a seal coat to the requirement of Clause 512 before opening to any traffic. The seal coat in such cases shall

shall be considered incidental to the work and shall not be paid for separately.

504.6. Arrangements for Traffic

During the period of construction, arrangements for traffic shall be made in accordance with the provisions of Clause 112.

504.7. Measurement for Payment

Bituminous macadam shall be measured as finished work in cubic metres, or by weight in metric tonnes, where used as regulating course, or square metres at the specified thickness as indicated in the Contract or shown on the drawings, or as otherwise directed by the Engineer.

504.8. Rate

The contract unit rate for bituminous macadam shall be payment in full for carrying out the required operations as specified. The rate shall include cost for all components listed in Clause 501.8.8.2.

Item No 2.

Providing, laying and rolling of 25mm thick using Bitumean grade of VG-30 open graded premix bituminous carpet with B.T. aggregate as specified and using RS1 Emulsion for tack coat at the rate of 2.50 Kg/10 Sqm on B.T.Surface. (As per IRC-16) and using bitumen for mixing with aggregate at the rate of 3.36% i.e. 33.60 Kg/M.T. of total mix including heating and mixing in drum mix plant, spreading the same with paver finisher and consolidation with vibratory roller including necessary firewood, oil lubricants, labour charges etc. using equipment, tool etc completed in accordance with the requirement of specification (as per R.A)

507 BITUMINOUS CONCRETE**507.1 Scope**

This work shall consist of construction of Bituminous Concrete, for use in wearing and profile corrective courses. This work shall consist of construction in a single layer of bituminous concrete on a previously prepared bituminous bound surface. A single layer shall be 30 mm/40 mm/50 mm thick.

507.2 Materials**507.2.1 Bitumen**

The bitumen shall conform to Clause 507.2.1.

507.2.2 Coarse Aggregates

The coarse aggregates shall be generally as specified in Clause 507.2.2, except that the aggregates shall satisfy the physical requirements of Table 500-16 and where crushed gravel is proposed for use as aggregate, not less than 95 percent by weight of the crushed material retained on the 4.75 mm sieve shall have at least two fractured faces.

Table 500-16 : Physical Requirements for Coarse Aggregate for Bituminous Concrete

Property	Test	Specification	Method of Test
Cleanliness (dust)	Grain size analysis	Max 5% passing 0.075 mm sieve	IS:2386 Part I
Particle shape	Combined Flakiness and Elongation Indices	Max 35%	IS:2386 Part I
Strength	Los Angeles Abrasion Value or Aggregate Impact Value	Max 30% Max 24%	IS:2386 Part IV
Durability	Soundness either:Sodium Sulphate or Magnesium Sulphate	Max 12% Max 18%	IS:2386 Part V
Polishing	Polished Stone Value	Min 55	BS:812-114
Water Absorption	Water Absorption	Max 2%	IS:2386 Part III
Stripping	Coating and Stripping of Bitumen Aggregate Mix	Minimum retained coating 95%	IS:6241
Water Sensitivity	Retained Tensile Strength*	Min 80%	AASHTO 283

* If the minimum retained tensile test strength falls below 80 percent, use of anti stripping agent is recommended to meet the requirement.

507.2.3 Fine Aggregates

The fine aggregates shall be all as specified in Clause 505.2.3.

507.2.4 Filler

Filler shall be as specified in Clause 505.2.4.

507.2.5 Aggregate Grading and Binder Content

When tested in accordance with IS:2386 Part 1 (Wet grading method), the combined grading of the coarse and fine aggregates and filler shall fall within the limits shown in Table 500-17. The grading shall be as specified in the Contract.

Table 500-17 : Composition of Bituminous Concrete Pavement Layers

Grading	1	2
Nominal aggregate size*	19 mm	13.2 mm
Layer thickness	50 mm	30 - 40 mm
IS Sieve (mm)	Cumulative % by weight of total aggregate passing	
45		
37.5		
26.5	100	
19	90-100	100
13.2	59-79	90-100
9.5	52-72	70-88
4.75	35-55	53-71
2.36	28-44	42-58
1.18	20-34	34-48
0.6	15-27	26-38
0.3	10-20	18-28
0.15	5-13	12-20
0.075	2-8	4-10
Bitumen content % by mass of total mix	Min 5.2*	Min 5.4**

Notes:

* The nominal maximum particle size is the largest specified sieve size up on which any of the aggregate is retained.

** Corresponds to specific gravity of aggregate being 2.7. In case aggregate have specific gravity more than 2.7, the minimum bitumen content can be reduced proportionately. Further the region where highest daily mean air temperature is 30°C or lower and lowest daily air temperature is – 10°C or lower, the bitumen content may be increased by 0.5 percent

507.3 Mix Design

507.3.1 Requirements for the Mix

Clause 505.3.1 shall apply.

507.3.2 Binder Content

Clause 505.3.2 shall apply.

507.3.3 Job Mix Formula

Clause 505.3.3 shall apply.

507.3.4 Plant Trials – Permissible Variation in Job Mix Formula

The requirements for plant trials shall be as specified in Clause 505.3.4, and permissible limits for variation as given in Table 500-18.

Table 500-18 : Permissible Variations in Plant Mix from the Job Mix Formula

Description	Permissible Variation
Aggregate passing 19 mm sieve or larger	± 7%
Aggregate passing 13.2 mm, 9.5 mm	± 6%
Aggregate passing 4.75 mm	± 5%
Aggregate passing 2.36 mm, 1.18 mm, 0.6 mm	± 4%
Aggregate passing 0.3 mm, 0.15 mm	± 3%
Aggregate passing 0.075 mm	± 1.5%
Binder content	± 0.3%
Mixing temperature	± 10°C

507.3.5 Laying Trials

The requirements for laying trials shall be as specified in Clause 505.3.5. The compacted layers of bituminous concrete (BC) shall have a minimum field density equal to or more than 92 percent of the average theoretical maximum specific gravity (G_{mm}) obtained on the day of compaction in accordance with ASTM D2041.

507.4 Construction Operations

507.4.1 Weather and Seasonal Limitations

The provisions of Clause 501.5.1 shall apply.

507.4.2 Preparation of Base

The surface on which the bituminous concrete is to be laid shall be prepared in accordance with Clauses 501 and 902 as appropriate, or as directed by the Engineer. The surface shall be thoroughly swept clean by mechanical broom and dust removed by compressed air. In locations where a mechanical broom cannot get access, other approved methods shall be used as directed by the Engineer.

507.4.3 Geosynthetics

Where Geosynthetics are specified in the Contract, this shall be in accordance with the requirements stated in Clause 703.

507.4.4 Stress Absorbing Layer

Where a stress absorbing layer is specified in the Contract, this shall be applied in accordance with the requirements of Clause 517.

507.4.5 Tack Coat

The provisions as specified in Clause 507.4.6 shall apply.

507.4.6 Mixing and Transportation of the Mix

The provisions as specified in Clauses 501.3, 501.4 and 507.4.7 shall apply

507.4.7 Spreading

The general provisions of Clauses 501.6 and 501.7 shall apply, as modified by the approved laying trials.

507.4.8 Rolling

The general provisions of Clauses 501.6 and 501.7 shall apply, as modified by the approved laying trials.

507.5 Opening to Traffic

Provisions in Clause 504.5 shall apply.

507.6 Surface Finish and Quality Control

The surface finish of the completed construction shall conform to the requirements of Clause 902. All materials and workmanship shall comply with the provisions set out in Section 900 of these Specifications.

507.7 Arrangements for Traffic

During the period of construction, arrangements for traffic shall be made in accordance with the provisions of Clause 112.

507.8 Measurement for Payment

The measurement shall be as specified in Clause 505.8.

507.9 Rate

The contract unit rate shall be all as specified in Clause 504.9, except that the rate shall include the provision of bitumen at 5.2 percent & 5.4 percent for grading 1 and grading 2 by weight of total mix respectively. The variation in actual percentage of bitumen used will be assessed and the payment adjusted plus and minus accordingly.

Item No 3.

Providing and laying Compacted 100 mm thick of Specified quarry Spall in side shoulder including carriage of material and spreading on prepared base including compacting as per MOST Specification etc... complete.

1. The quarry spauls shall be approved quarry as approved by the Ex. Engineer prior to collection. Filling of boxes, shall not be allowed till the metal is broken to the specified
2. The quarry spaul shall be as uniform in size as possible. The quarry spaul shall be hard, tough, solid durable of black trap quarry of close texture, free from decay and weathering. The stone shall be angular and roughly cubical in shape and round elongated or flaky materials shall be rejected. No sound or long rubble or angular chips smaller than specified size shall be allowed.

Grading for quarry spauls

IS : Sieve	Grading - I	Grading - II	Grading - III
75mm	100	--	--
53mm	--	100	--
26.5mm	55 - 75	50 - 80	100
9.50mm	--	--	--
4.75mm	10 - 30	15 - 35	25 - 45
2.36mm	--	--	--
0.425mm	--	--	--
0.075mm	< 10	< 10	< 10

Material passing through 425 micro sieve for all the three gradings when tested according to I.S. 2720 (Part-5) shall have liquid limit and plastic index not more than 25 and 6 respectively.

3. All unsound, weathered or disintegrated stone obtained from the under surface layer of the quarry or other layers of boulders shall be rejected.
4. Wherever any doubt as to whether above requirement are satisfied in whole or part of the collection it shall be got screened by the Contractor if so ordered by the Executive Engineer, and for which no extra payment shall be claimed by the contractor
5. Any collection which does not fully satisfy the above requirements is liable to be rejected all together.
6. Regular stacks shall be made by the contractor on a fairly level ground. All the stack shall be marked by white wash immediately on being measured and recorded by the Engineer-in-charge.
7. The rate includes blasting the rock, if any, breaking the quarry spauls, stacking measuring in pharas etc. complete.
8. Stacks shall as per actual requirements and any materials in excess shall have to be transported by the contractor at the places directed by the Executive Engineer at the risk and cost of the contractor.
9. While stacking materials the depositing should commence at one end of the K.M. and carried continuously towards the other end unless the Executive Engineer shall direct otherwise and as a rule measurements shall be taken after metal for halt kilometer or Km. has been fully collected. Any fraction of these distance shall not be measured up.

10. The measurements shall be recorded in on Cum. basis on level computing method after rolling and consolidation and shall be paid accordingly.
- **Spreading quarry spauls in grade & camber complete.**
1. The quarry spauls shall be only be allowed to be spread after the written permission of the Executive Engineer is obtained.
2. The permission for spreading the metal shall be given by the Executive Engineer if
 - (i) The full quantity of a particular mile(kilometer)is completely collected.
 - (ii) The collection of metal-is also completed in the adjoining two miles (Kilometers)
 - (iii) The measurements are recorded in the Measurement book.
3. Q. S. shall if required, be screened, if containing rubbish dust, grass etc. it shall than be filled in basket & conveyed where required and spread evenly on the prepared surface be given twisting motion to the basket at the time of spreading. The surface shall then (15 m) by means of templates and strings as well as with camber boards and spirit level.
4. Between the straight length and curves and at the meeting points of the convex and concave portions of the reverse curves, the change in camber of the road, due to super elevations shall be made as well as with camber boards and spirit level.
5. At the time of spreading Q. S. a small quantity (about 4 to 5 percent) of metal as directed, shall be retained at the first instance. It shall be spread later 0:1 after partial consolidated as required to rectify the camber and to fill up the hollows if any. No extra amount shall be paid for this.
6. Measurements shall be paid as per the measurements of collection less the quantity remained to be spread and on cubic metre basis.
7. The rate includes the cost of screening the Q.S. if any spreading, sectioning, with template and adding reserved quota of metal, while/oiling is in progress for making good hollows and camber.
8. The surface shall be brought to the required camber which shall be checked at every 50 ft.(15 M) by means off templates of while the necessary of the in between shall tested by strings and corrected as required.
9. The centre line shall first be marked in the subgrade which is properly consolidated and has uniform carnber and grade as required
10. The Q. S. shall be laid for a small length on 25 ft. (8 M.) and then the edge stones shall be laid.
11. Pegs shall be driven on either side of the road and joined with strings true and parallel with a distance between they equal to the width be laid with over metal Similarly.
12. The Q. S. shall be laid as close as possible so as too leave minimum possible interstices and voids.
13. Before roiling is allowed on soling the side berms shall be filled upto the top of the soling and at least 3'-0" (1 m.) on either side so as to prevent metal layer getting disturbed at times during rolling. The rate is inclusive of all the operations as stated above.

14. Immediately following the spreading of the coarse aggregates rolling shall be started with three wheeled power roller of 8 - to - 10 tone capacity or tondum roller or equivalent vibratory roller. The weight of the roller shall depend upon the type of the aggregate and be indicated by Engineer-in-charge.
15. Except on super elevated portions where the roiling shall proceed from inner edge to outer, rolling shall from the edges gradually progressing towards the centre. First the edge / edges shall be compacted with roller running forward and backward. The roller shall then move inward parallel to centre line of the road, in successive passes uniformly lapping preceding tracks by at least one half the width.
16. Rolling shall continue until the aggregate is thoroughly keyed and the creeping of the aggregate a head of the roller is no longer visible. During rolling, slight sprinkling of water may be done, if necessary. Rolling shall no be done when the sub grade is soft or yielding or when it causes a wave like motion in the sub grade or sub base course.
17. The rolled surface shall be checked transversely and longitudinally with templates and any irregularities corrected by loosening the surface, adding or removing necessary amounts of aggregate and re - rolling until the entire surface conform to desired camber and grade. In no case shall the base of screening be permitted to make up depression.
18. The blindage material where it is required to be used shall be applied successively in two or more thin layer at a slow and uniform rate. After each application, the surface shall be copiously sprinkled with water, the resulting, slurry swept in with hand brooms or mechanical brooms to fill the voids properly and rolled during which water shall be applied the wheels of the rollers, if necessary to wash down the binding material sticking to them. These operations shall continue until the resulting slurry after filling of voids forms a wave ahead of the wheels of the moving roller.
19. After the final compaction of water bound macadam course, the road shall be allowed to any over night Next morning hungry spots shall be filled with screenings of binding materials as directed lightly sprinkled with water, if necessary and rolled. No traffic shall be allowed on the road until the macadam has set. The Engineer - in - charge shall have the discretion to stop hauling traffic from using the completed water bound macadam course, if in his opinion, it would cause excessive damage to the surface.

Mode of Measurement & Payment

1. Measurements shall be paid as per the measurements of collection less the quantity remained to be spread and on cubic meter basis.
2. The rate includes the cost of screening the Q.S. if any spreading, sectioning, with template and adding reserved quota of metal, while/oiling is in progress for making good hollows and camber.

408. SHOULDERS, ISLANDS AND MEDIAN

408.1 Scope

The work shall consist of constructing shoulder (hard/paved/earthen with brick or stone block edging) on either side of the pavement, median in the road dividing the carriageway into separate lanes and islands for channelising the traffic at junctions in accordance with the requirements of these Specifications and in conformity with the lines, grades and cross-sections shown on the drawings or as directed by the Engineer.

408.2 Materials

Shoulder on either side of the road may be of selected earth/ granular material/ paved conforming to the requirements of Clause 305/401 and the median may be of selected earth conforming to the requirements of Clause 305.

Median/Traffic islands shall be raised and kerbed at the perimeter and the enclosed area filled with earth and suitably covered with grass turf/shrubs as per Clause 307 and/or paved as per Clause 410.3.4 or 410.3.5.

Paved shoulders shall consist of sub-base, base and surfacing courses, as shown in the drawings and materials for the same shall conform to relevant Specifications of the corresponding items. Where paved or hard shoulders are not provided, the pavement shall be provided with brick/stone block edgings as shown in the drawings. The bricks shall conform to Clause 1003 of these Specifications. Stone blocks shall conform to Clause 1004 of these Specifications and shall be of size 225 mm x 110 mm x

408.3 Size of Shoulders/Median/Islands

Shoulder (earthen/hard/paved) / median / traffic island dimensions shall be as shown on the drawings or as directed by the Engineer.

408.4 Construction Operations

408.4.1. Shoulder : The sequence of operations shall be such that the construction of paved shoulder is done in layers each matching the thickness of adjoining pavement layer. Only after a layer of pavement and corresponding layers in paved and earth shoulder portion have been laid and compacted, the construction of next layer of pavement and shoulder shall be taken up.

Where the materials in adjacent layers are different, these shall be laid together and the pavement layer shall be compacted first. The corresponding layer in paved shoulder portion shall be compacted thereafter, which shall be followed by compaction of earth shoulder layer. The adjacent layers having same material shall be laid and compacted together.

In all cases where paved shoulders have to be provided along Side of existing carriageway, the existing shoulders shall be excavated in full width and to the required depth as per Clause 301.3.7. Under no circumstances, box cutting shall be done for construction of shoulders.

Compaction requirement of earthen shoulder shall be as per Table 300-2. In the case of bituminous courses, work on shoulder (earthen/ hard/paved) shall start only after the pavement course has been laid and compacted.

During all stages of shoulder construction, the required crossfall shall be maintained to drain off surface water.

Regardless of the method of laying, all shoulder construction material shall be placed directly on the shoulder. Any spilled material dragged on to the pavement surface shall be immediately removed, without damage to the pavement, and the area so affected thoroughly cleaned.

408.4.2. Median and Islands

Median and Islands shall be constructed in a manner similar to shoulder up to the road level. Thereafter the median and islands, if raised, shall be raised at least 300 mm by

using kerb stones of approved material and dimensions and suitably finished and painted as directed by the Engineer. If not raised, the median and islands shall be differentiated from the shoulder/ pavement as the case may be, as directed by the Engineer. The confined area of the median and islands shall be filled with local earth or granular material or any other approved material and compacted by plate compactor/power rammer. The confined area after filling with earth shall be turfed with grass or planted with shrubs, or finished with tiles/slabs as provided in the

408.4.3. Brick/stone block edging: The bricks/stone blocks shall be laid on edge, with the length parallel to the transverse direction of the road. They shall be laid on a bed of 25 mm sand, set carefully rolled into position by a light roller and made flush with the finished level of the pavement.

408.4.5. Surface Finish and Quality Control of Works

The surface finish of construction shall conform to the requirements of Clause 902. Control on the quality of materials and works shall be exercised by the Engineer in accordance with Section 900.

408.6. Measurements for Payment

Shoulder (earthen/hard/paved), island and median construction shall be measured as finished work in position as below :

- (i) For excavation in cu. m.
- (ii) For earthwork/granular fill in cu. m.
- (iii) For sub-base, base, surfacing courses in units as for respective items.
- (iv) For kerb in running metres, length of kerb for median shall be measured for each side separately.
- (v) For turfing, shrubs and tile/slab finish in sq.m.
- (vi) For brick/stone block edging in running meter, the length for brick / stone block edging for median edging shall be measured for each side separately.

408.7. Rate

The Contract unit rate for shoulder (hard/paved/earthen with brick or stone block edging), island and median construction shall be payment in full for carrying out the required operations including full compensation for all components listed in Clause 401.7 (i) to (v) as applicable. The rate for brick/stone block edging shall include the cost of sand cushion.

Item No 4.

Construction of granular sub-base 200mm thick layer by providing machine crushed B.T. material satisfying MORT&H specification (Fifth revision) of grading III including spreading in uniform layer with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC and compacting with vibratory roller to achieve the desired density etc. complete.

401.0 GRANULAR SUB-BASE**401.1 Scope**

This work shall consist of laying and compacting well-graded material on prepared subgrade in accordance with the requirements of these Specifications. The material shall be laid in one or more layers as sub-base or lower sub-base and upper sub-base (termed as sub-base hereinafter) as necessary according to lines, grades and cross-sections shown on the drawings or as directed by the Engineer.

401.2 Materials

401.2.1 The material to be used for the work shall be natural sand, crushed gravel, crushed stone, crushed slag, or combination thereof depending upon the grading required. Use of materials like brick metal, Kankar and crushed concrete shall be permitted in the lower sub-base. The material shall be free from organic or other deleterious constituents and shall conform to the gradings given in Table 400-1 and physical requirements given in Table 400-2. Gradings III and IV shall preferably be used in lower sub-base. Gradings V and VI shall be used as a sub-base-cum-drainage layer. The grading to be adopted for a project shall be as specified in the Contract. Where the sub-base is laid in two layers as upper sub-base and lower sub-base, the thickness of each layer shall not be less than 150 mm.

401.2.2 If the water absorption of the aggregates determined as per IS:2386 (Part 3) is greater than 2 percent, the aggregates shall be tested for Wet Aggregate Impact Value (AIV) (IS:5640). Soft aggregates like Kankar, brick ballast and laterite shall also be tested for Wet AIV (IS:5640).

Table-400-1- Grading for Granular Sub-base materials ::

Sieve Designation	Percent by Weight Passing the IS Sieve					
	Grading I	Grading II	Grading III	Grading IV	Grading V	Grading VI
75.00mm	100	--	--	--	100	--
53.00mm	80-100	100	100	100	80-100	100
26.5mm	55-90	70-100	55-75	50-80	55-90	75-100
9.50mm	35-65	50-80	--	--	35-65	55-75
4.75mm	25-55	40-65	10-30	15-35	25-50	30-55
2.36mm	20-40	30-50	--	--	10-20	10-25
0.85mm	--	--	--	--	2-10	--
0.425mm	10-15	10-15	--	--	0-5	0-8
0.075mm	<5	<5	<5	<5	--	0-3

Table 400-2-Physical Requirements for Materials for Granular sub-base

Aggregate Impact Value (AIV)	IS-2396 (Part-4-) or I.S. 5640	40% Maximum
Liquid Limits	IS-2720 (Part-5-)	Maximum 25
Plasticity Index	IS-2720 (Part-5-)	Maximum 06
CBR at 98% dry density (at IS2720-Part-8-)	IS-2720 (Part-5-)	Minimum 30 unless otherwise specified in the contract

401.3 Construction Operations ::

401.3.1. Preparation of subgrade : Immediately prior to the laying of sub-base, the subgrade already finished to Clause 301 or 305 as applicable shall be prepared by removing all vegetation and other extraneous material, lightly sprinkled with water if necessary and rolled with two passes of 80 -100 kN smooth wheeled roller.

401.4.2. Spreading and compacting :

The sub-base material of grading specified in the. Contract and water shall be mixed mechanically by suitable equipment with provisions for controlled addition of water and mechanical mixing. So as to ensure homogenous and uniform mix. The required water content shall be determined in accordance with IS 2720 (Part 8) The mix shall be spread on the prepared subgrade with the help of a motor grader of adequate capacity, its blade having hydraulic control suitable for initial adjustment and for maintaining the required slope and grade during the operation or other means as approved by the Engineer.

Moisture content of the mix shall be checked in accordance with IS-2720 (part 2) and suitably adjusted so that at the time of compaction it is from 1 to 2 percent below the optimum moisture content.

Immediately after spreading the mix, rolling shall be done by an approved roller. If the thickness of the compacted layer does not exceed 100 mm, a smooth wheeled roller of 80 to 100 kN weight may be used. For a compacted single layer, up to 200 mm the compaction shall be done with the help of a vibratory roller of minimum 80 to 100 kN static weight capable of achieving the required compaction. Rolling shall commence at the lower edge and proceed towards the upper edge longitudinally for portions having unidirectional cross fall or on super-elevation. For carriageway having cross fall on both sides, rolling shall commence at the edges and progress towards the crown.

Each pass of the roller shall uniformly overlap not less than one-third of the track made in the preceding pass. During rolling, the grade and cross fall (camber) shall be checked and any high spots or depressions which become apparent, corrected by removing or adding fresh material. The speed of the roller shall not exceed 5 km per hour.

Rolling shall be continued till the density achieved is at least 98% of the maximum dry density for the material determined as per IS 2720 (Part-8-). The surface of any layer of materials on completion of compaction shall be well closed, free from movement under compaction equipment and from compaction planes, ridges, cracks or loose materials. All loose segregated or otherwise defective area shall be made good to the full thickness of layer and re-compacted.

401.4 Surface Finish and Quality Control of Work

The surface finish of construction shall conform to the requirements of Clause 902. Control on the quality of materials and works shall be exercised by the Engineer in accordance with Section 900.

401.5 Arrangements for Traffic

During the period of construction, arrangement of traffic shall be maintained in accordance with Clause 112.

401.6 Measurements for Payment

Granular sub-base shall be measured as finished work in position in cubic metres.

The protection of edges of granular sub-base extended over the full formation as shown in the drawing shall be considered incidental to the work of providing granular sub-base and as such no extra payment shall be made for the same.

401.7 Rate

The Contract unit rate for granular sub-base shall be payment in full for carrying out the required operations including full compensation for :

- (i)** Malting arrangements for traffic to Clause 112 except for initial treatment to verges, shoulders and construction of diversions;
- (ii)** Supplying all materials to be incorporated in the work including all royalties, fees, rents where necessary and all leads and lifts;
- (iii)** All labour, tools, equipment and incidentals to complete the work to the Specifications;
- (iv)** Carrying out the work in part widths of road where directed; and
- (v)** Carrying out the required test for quality control.

401.8 Measurements for payment ::

Granular sub-base shall be measured as finished work in provision in Cubic meter. The protection of edges of granular sub-base extended over the full formation as shown in the drawing shall be considered incidental to the work of providing granular sub-base and as such no Extra Payment shall be made for the same.

- (vi) The payment shall be made on Cubic meter basis with a average area method.**

Item No 5.

Providing, Laying, spreading and compacting 250 mm thick graded stone aggregates to wet mix macadam in Two layers each of 125 mm as per MORT & H specification including premixing the material with water at OMC in mechanical mix plant, carriage of mixed material by tippers to site, laying in uniform layers with paver in sub base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density.

406. WET MIX MACADAM SUB-BASE/BASE**406.1 Scope**

This work shall consist of laying and compacting clean, machine crushed chips and granular material, premixed with water, to a dense mass on a prepared sub grade/sub-base/base or existing pavement as the case may be in accordance with the requirements of these specifications. The material shall be laid in single layer as necessary to lines, grades and cross-sections shown on the approved drawings or as directed by the Engineer.

The thickness of a single compacted Wet Mix Macadam layer shall not be less than 125mm. When vibrating or other approved types of compacting equipment are used, the compacted depth of a single layer of the sub-base course may be up to 125 mm with the approval of the Engineer.

406.2. Materials**406.2.1. Aggregates****406.2.1.1. Physical requirements :**

Coarse aggregates shall be crushed stone. If crushed gravel / single is used, not less than 90 percent by weight of the gravel / single pieces retained on 4.75 mm sieve shall have at least two fractured faces. The aggregates shall conform to the physical requirements set forth in Table 400-12 below.

If the water absorption value of the coarse aggregate is greater than 2 per cent, the soundness test shall be carried out on the material delivered to site as per IS: 2386 (Part-5).

TABLE - 400-12. Physical Requirements of Coarse Aggregates for Wet Mix Macadam for Sub-base/Base Courses

	Test	Test Method	Requirements
1	* Los Angeles Abrasion value	IS:2386 (Part-4)	40 per cent (Max)
	Or		
	* Aggregate Impact value:2386 (Part-4) or IS:5640		30 per cent (Max)
2	Combined Flakiness and Elongation Indices	IS:2386 (Part-1)	35 per cent (Max)

** To determine this combined proportion, the flaky stone from a representative sample should first be separated out. Flakiness index is weight of flaky stone metal divided by weight of stone sample. Only the elongated particles be separated out from the remaining (non-flaky) stone metal. Elongation index is weight of elongated particles divided by total non-flaky particles. The values of flakiness index and elongation index so found are added up.

406.2.1.2 Grading requirements:

The aggregates shall conform to the grading given in Table 400.13.

TABLE 400.13 GRADING REQUIREMENTS OF AGGREGATES FOR WET MIX MACADAM

Sieve Designation	Percent by weight passing the I.S. sieve
53.00mm	100
45.00mm	95-100
26.5mm	--
22.4mm	60-80
11.2mm	40-60
4.75mm	25-40
2.36mm	15-30
600 micron	8-22
75 micron	0-8

Materials finer than 425 micron shall have Plasticity Index (PI) not exceeding 6.

The final gradation approved within these limits shall be well graded from coarse to fine and shall not vary from the low limit on one sieve to the high limit on the adjacent sieve or vice versa.

406.3. Construction Operations

406.3.1 Preparation of base: The surface of the subgrade/sub-base/base to receive the wet mix macadam course shall be prepared to the specified lines and crossfall (camber) and made free of dust and other extraneous material. Any ruts or soft yielding places shall be corrected in an approved manner and rolled until firm surface is obtained if necessary by sprinkling water. Any sub-base/base/surface irregularities, where predominant, shall be made good by providing appropriate type of profile corrective course (levelling course) to Clause 501 of these Specifications.

As far as possible, laying wet mix macadam course over an existing thick bituminous layer may be avoided since it will cause problems of internal drainage to the pavement at the interface of two courses. It is desirable to completely pick out the existing bituminous course where wet mix macadam is proposed to be laid over it.

406.3.2. Provision of lateral confinement of aggregates:

While constructing wet mix macadam, arrangement shall be made for the lateral confinement of wet mix. This shall be done by laying materials in adjoining shoulders along with that of wet mix macadam layer and following the sequence of operations described in Clause 404.3.3.

406.3.3 Preparation of mix:

Wet Mix Macadam shall be prepared in an approved mixing plant of suitable capacity having provision for controlled addition of water and forced/positive mixing arrangement like pug mill or pan type mixer of concrete batching plant. The plant shall have following features:

- i For feeding aggregates- three/ four bin feeders with variable speed motor
- ii Vibrating screen for removal of oversize aggregates
- iii Conveyor Belt
- iv Controlled system for addition of water

- v Forced/positive mixing arrangement like pug-mill or pan type mixer
- vi Centralized control panel for sequential operation of various devices and precise process control
- vii Safety devices

Optimum moisture for mixing shall be determined in accordance with IS: 2720 (Part-8) after replacing the aggregate fraction retained on 22.4 mm sieve with material of 4.75 mm to 22.4 mm size. While adding water, dew allowance should be made for evaporation losses. However, at the time of compaction, water in the wet mix should not vary from the optimum value by more than agreed limits. The mixed material should be uniformly wet and no segregation should be permitted.

406.3.4 406.3.4 Spreading of Mix

Immediately after mixing, the aggregates shall be spread uniformly and evenly upon the prepared sub-grade/sub-base/base in required quantities. In no case shall these be dumped in heaps directly on the area where these are to be laid nor shall their hauling over a partly completed stretch be permitted.

The mix may be spread by a paver finisher. The paver finisher shall be self-propelled of adequate capacity with following features:

- i Loading hoppers and suitable distribution system, so as to provide a smooth uninterrupted material flow for different layer thicknesses from the tipper to the
- Hydraulically operated telescopic screed for paving width upto to 8.5 m and fixed
- ii screed beyond this. The screed shall have tamping and vibrating arrangement for initial compaction of the layer.
- Automatic levelling control system with electronic sensing device to maintain mat
- iii thickness and cross slope of mat during laying procedure.

In exceptional cases where it is not possible for the paver to be utilized, mechanical means like motor grader may be used with the prior approval of the Engineer. The motor grader shall be capable of spreading the material uniformly all over the surface.

The surface of the aggregate shall be carefully checked with templates and all high or low spots remedied by removing or adding aggregate as may be required. The layer may be tested by depth blocks during construction. No segregation of larger and fine particles should be allowed. The aggregates as spread should be of uniform gradation with no pockets of fine materials.

The Engineer may permit manual mixing and /or laying of wet mix macadam where small quantity of wet mix macadam is to be executed. Manual mixing/laying in inaccessible/ remote locations and in situations where use of machinery is not feasible can also be permitted. Where manual mixing/laying is intended to be used, the same shall be done with the approval of the Engineer.

406.3.5 Compaction:

After the mix has been laid to the required thickness, grade and cross fall / camber the same shall be uniformly compacted, to the full depth with suitable roller. If the thickness of single compacted layer does not exceed 100 mm, a smooth wheel roller of 80 to 100 KN weight may be used. For a compacted single layer up to 200 mm, the compaction shall be done with the help of vibratory roller of minimum static weight of 80 to 100 KN or equivalent capacity roller. The speed of the roller shall not exceed 5 km/h.

In portions having unidirectional cross fall / super elevation, rolling shall commence from the lower edge and progress gradually towards the upper edge. Thereafter, roller should progress parallel to the centre line of the road, uniformly over-lapping each preceding track by at least one third width until the entire surface has been rolled. Alternate trips of the roller shall be terminated in stops at least 1 m away from any preceding stop.

In portions in camber, rolling should begin at the edge with the roller running forward and backward until the edges have been firmly compacted. The roller shall then progress gradually towards the centre parallel to the centre line of the road uniformly overlapping each of the preceding tracks by at least one-third width until the entire surface has been rolled.

Any displacement occurring as a result of reversing of the direction of a roller or from any other cause shall be corrected at once as specified and/or removed and made good.

Along forms, kerb, walls or other places not accessible to the roller, the mixture shall be thoroughly compacted with mechanical tampers or a plate compactor. Skin patching of an area without scarifying the surface to permit proper bonding of the added material shall not be

Rolling should not be done when the sub grade is soft or yielding or when it causes a wave-like motion in the sub-base / base course or sub grade. If irregularities develop during rolling which exceed 12 mm when tested with a 3 metre straight edge, the surface should be loosened and premixed material added or removed as required before rolling again so as to achieve a uniform surface conforming to the desired grade and cross fall. In no case should the use of unmixed material be permitted to make up the depressions.

Rolling shall be continued till the density achieved is at least 98 per cent of the maximum dry density for the material as determined by the method outlined in IS: 2720 (Part-8).

After completion, the surface of any finished layer shall be well closed, free from movement under compaction equipment or any compaction planes, ridges, cracks and loose material. All loose, segregated or otherwise defective areas shall be made good to the full thickness of the layer and recomputed.

406.3.6. Setting and drying :

After final compaction of wet mix macadam course, the road shall be allowed to dry for 24 hours.

406.4 Opening to Traffic

Preferably no vehicular traffic of any kind should be allowed on the finished wet mix macadam surface till it has dried and the wearing course lay.

406.5. Surface Finish and Quality Control of Work

406.5.1. Surface evenness : The surface finish of construction shall conform to the requirements of Clause 902.

406.5.2. Quality control: Control on the quality of materials and works shall be exercised by the Engineer in accordance with Section 900.

406.6. Rectification of Surface Irregularity

Where the surface irregularity of the wet mix macadam course exceeds the permissible tolerances or where the course is otherwise defective due to sub grade soil getting mixed with the aggregates, the full thickness of the layer shall be scarified over the affected area, reshaped with added premixed material or removed and replaced with fresh premixed material as applicable and

accordance with Clause 406.3. The area treated in the aforesaid manner shall not be less than 5 in long and 2 in wide. In no case shall depressions be filled up with unmixed and ungraded material or fines.

406.7. Arrangement for Traffic

During the period of construction, arrangement of traffic shall be done as per Clause 112.

406.8. Measurements for Payment

Wet mix macadam shall be measured as finished work in position in cubic metres,

406.9. Rates

The Contract unit rate for wet mix macadam shall be payment in full for carrying out the following operations including full compensation for all components listed below.

1. Making arrangements for traffic to Clause 112 except for initial treatment to verges, shoulders and construction of diversions;
2. Furnishing all materials to be incorporated in the work including all royalties, fees, rents where necessary and all leads and lifts;
3. All labour, tools, equipment and incidentals to complete the work to the Specifications;
4. Carrying out the work in part widths of road where directed and
5. Carrying out the required tests for quality control.

Item No 6.

Providing and laying Bituminous Grout 37.5 mm thick compacted with asphalt VG-30 grade at the rate of 1.99% by weight of total mix with tack coat at 2.50 Kg/10 Sqmt. On existing B.T/ Metal. surface and using B.T. chips of required gradation including cleaning & heating the aggregate and asphalt by Drum Mix Plant & spreading the same by paver finisher & consolidation with vibratory road roller including providing all materials, equipments, tools, plants, fire wood, kerosene, oil and labor charges etc. comp. (using by contractor own machineries)

Scope

The work shall consist of construction, in a single course, of compacted crushed aggregates premixed with a bituminous binder, to serve as base/binder course, laid immediately after mixing, on a base prepared previously in accordance with the requirement of these Specifications and in conformity with the lines, grades and cross sections shown on the drawing or as directed by the Engineer. Thickness of the course shall be 37.5mm materials.

Materials

Bitumen: The bitumen shall be paving bitumen of suitable viscosity grade VG-30 as per IS:73. The actual grade of bitumen to be used shall be decided by the Engineer appropriate to the region, traffic, rainfall and other environmental conditions. Guidelines on selection of the grade of bitumen are given in Appendix-4.

Viscosity Grade (VG) Bitumen Specification as per IS 73 : 2006

Characteristics	VG - 10	VG-20	VG-30	VG-40
Absolute Viscosity 60°C, poises, min	800	1600	2400	3200
Kinematics Viscosity 135°C CSI, min	250	300	350	400
Flash point, C, min	220	220	220	220
Solubility in trichloroethylene, % min	99.0	99.0	99.0	99.0
Penetration at 25°C	80-100	60-80	50-70	40-60
Softening point, C min	40	45	47	50
Test on residue from thin film oven test / RTFOT:				
(A) Viscosity ration at 60°C, max	4.0	4.0	4.0	4.0
(B) Ductility at 25°C, cm, min after thin film over test	75	50	40	25

Aggregates

The aggregates shall consist of crushed stone, crushed gravel/shingle or other stones. They shall be clean, strong, durable, of fairly cubical shape and free from disintegrated pieces, organic or other deleterious matter and adherent coating. The aggregates shall preferably be hydrophobic and of low porosity. If hydrophilic aggregates are to be used, the bitumen shall preferably be treated with anti-stripping agents of approved quality in suitable dose as per Appendix-5. The aggregates shall satisfy the physical requirements set forth in Table 500-3.

TABLE 500-3. PHYSICAL REQUIREMENTS OF AGGREGATES FOR BITUMINOUS MACADAM

Sr. No.	Test	Test Method	Requirement
1	Log Angeles Abrasion Value*	IS 2386 (Part-4)	40 percent Maximum
2	Aggregates Impact Value*	IS 2486 (Part-4)	30 percent Maximum

3	Flakiness and Elongation	IS 2386 (Part-1)	30 percent Maximum
4	Coating and Stripping of Bitumen Aggregate mixtures.	I.S. 6241	Minimum retained coating 95 per cent.
5	5 Soundness (1) Loss with Sodium Sulphate 5 cycles. (2) Loss with Sodium Magnesium 5 cycles.	IS 2386 (Part-V)	12 percent Maximum 18 percent Maximum
6	Water Absorption	IS 2386 (Part-3)	2 percent Maximum.

*** Aggregates may satisfy requirements for either of the two tests.**

****** To determine this combined proportion, the flaky stone from representative sample should first be separated out. Flakiness index is weight of flaky stone metal divided by weight of stone sample. Only the elongated particle be separated out from the remaining (non flaky) stone metal. Elongation index is weight of elongated particles divided by total non flaky particles. The value of flakiness index and elongation index so found are added up.

Proportioning of materials:

The bitumen content for premixing shall be **1.99 % (percent)** by weight of the total mix except when otherwise directed by the Engineer.

The maximum compacted thickness of a layer shall be 37.5mm.

The quantities of aggregates to be used shall be sufficient to yield the specified thickness after compaction.

AGGREGATE GRADING FOR BITUMINOUS GROUT

IS Sieve Designation	Percent by weight passing the sieve
53.0 mm	100
26.5 mm	75 - 100
22.4 mm	50 - 85
13.2 mm	20 - 40
5.6 mm	5 - 20
2.8 mm	0 - 5

Variation in proportioning of materials : The Contractor shall have the responsibility for ensuring proper proportioning of materials and producing a uniform mix. A variation in binder content +0.3 per cent by weight of total mix shall however be permissible for individual specimens taken for quality control tests vide Section 900.

Construction Operations:

Weather and seasonal limitations : The work of laying shall not be taken up during rainy or foggy weather or when the base course is damp or wet, or during dust storm or when atmospheric temperature in shade is 10 degree C or less.

Preparation of base : This work shall consist of preparing an existing granular or black topped surface bituminous course. The work shall be performed on such widths and lengths as shown in application drawing or as directed by the Engineer. The existing surface shall be firm and clean and treated with prime or tack coat as shown on the drawings as otherwise stated in the contract.

Materials:

For scarifying and re-laying the granular surface: The materials used shall be coarse aggregates salvaged from scarification of the existing granular base course supplemented by fresh coarse aggregates and screenings so that aggregates and screening thus supplemented correspond to Clause 404. Water Bound Macadam or Clause 406. Wet Mix Macadam, as the case may be.

For patching potholes and sealing cracks : Where the existing surface to be overlaid is bituminous, any existing potholes and cracks shall be repaired and sealed in accordance with Clauses 3004.2 and 3004.3 or as directed by the Engineer.

For Profile Corrective Course : A profile corrective course for correcting the existing pavement profile shall be laid to varying thickness as shown on the Drawings, or as indicated in the Contract Documents. The profile corrective course shall be laid to tolerances and densities as specified for wearing course if a single layer, or base course, if it is to be covered with a wearing course layer.

Profile corrective course and its application: The type of material for use as a profile corrective course shall be as shown on the drawing. If it is to be laid as part of the overlay/strengthening course, the profile corrective course material shall be of the same specification as that of the overlay/strengthening course. However, if provided as a separate layer, it may be of the same specification as the layer over which it is to be laid or intermediate between underlying layers, as shown on the Drawing.

Surface Levels:

The levels of the sub grade and different pavement courses as constructed shall not vary from those calculated with reference to the longitudinal and cross-profile of the road shown on the drawings or as directed by the engineer beyond the tolerances mentioned in Table 900-1.

Bituminous material shall not be applied to a wet surface or during a dust storm or when the weather is foggy, rainy or windy or when the temperature in the shade is less than 10°C. Where the tack coat consists of emulsion the surface shall be slightly damp, but not wet. Where the tack coat is of cut back bitumen the surface shall be dry.

Construction Equipment:

The tack coat distributor shall be self propelled or towed bitumen pressure sprayer, quipped for spraying the material uniformly at a specified rate. Hand spraying of small areas inaccessible to the distributor or in narrow strips shall be sprayed with a pressure and sprayer or as directed by the Engineer 503.4.2 of MORTH specification. Preparation of base : The surface on which the tack coat is to be applied shall be clean and free from dust, dirt and any extraneous material, and be otherwise prepared in accordance with the requirements of Clauses 501.8 and 902 as appropriate. Immediately before the application of the tack coat, the surface shall be swept clean with a mechanical broom, and high pressure air jet, or by other means as directed by the Engineer.

Application of tack coat:

The application of tack coat shall be at the rate specified in the Contract, and shall be applied uniformly. If rate of application of Tack Coat is not specified in the contract then it shall be at the rate specified in TABLE 500-2 of MORTH specification. The normal range of spraying.

TABLE 500-2 RATE OF APPLICATION OF TACK COAT:

The emulsion asphalt at the rate of **2.50 kg per 10 sq.m.** shall be used for tack coat temperature for a bituminous emulsion shall be 20°C to 70°C and for a cut back 50°C to 80°C if RC-70/MC-70 IS used. Where geosynthetic IS proposed for use, the provisions of Clauses 703.3.2, and 703.4.4 of MORTH specification shall apply. The method of application of the tack coat will depend on the type of equipment to be used, size of nozzles, pressure at the spray bar and speed of forward movement. The Contractor shall demonstrate at a spraying trial, that the equipment and method to be used is capable of producing a uniform spray, within the tolerances specified.

Where the material to receive an overlay is a freshly laid bituminous layer, that has not been subjected to traffic, or contaminated by dust, a tack coat is not mandatory where the overlay is completed within two days.

Curing of tack coat: The tack coat shall be left to cure until all the volatiles have evaporated before any subsequent construction is started. No panning or vehicles shall be allowed on the tack coat other than those essential for the construction.

Quality Control of Work :

TOLERANCES IN SURFACE LEVELS

1. Sub grade	+ 20mm 25mm
2. Sub-base 4 - 10 mm	
(a) Flexible pavement	- 20mm
(b) Concrete pavement	+ 6mm
[Dry clean concrete or Rolled concrete]	- 10mm
3. Base - course for flexible pavement	+ 6mm
(a) Bituminous course	- 6mm
(b) Other than bituminous	+ 10mm
(i) Machine laid - 10mm	- 10mm
(ii) Manually laid + 15mm	+ 15mm 15mm
4. Wearing course for flexible pavement	
(a) Machine laid + 6mm	+ 6mm 6mm
(b) Manually laid + 10mm	+ 10mm 10mm
5. Cement concrete pavement	+ 5mm - 6mm

TACK COAT :

Scope:

This work shall consist of the application of a single coat of high viscosity liquid bituminous material to an existing bituminous road surface preparatory to the superimposition of a bituminous mix, when specified in the Contract or instructed by the Engineer.

Materials:

The binder used for tack coat shall be bitumen emulsion complying with IS:8887 of a type and grade as specified in the Section 500 of MORTH specification Contract or as directed by the Engineer. The use of cut back bitumen as per IS:217 shall be restricted only for sites at sub-zero

temperatures or for emergency applications as directed by the Engineer.

Weather and Seasonal Limitations:

For control of the quality of materials supplied and the works carried out for relevant provisions of Section 900 shall apply.

Specification: The rate shall cover the provision of **tack coat at 0.25 kg** per square meter with provision that the variation in actual quantity of bitumen used will be assessed and the payment adjusted accordingly.

Preparation and transport of mix:

Bituminous grout mix shall be prepared in a drum mix plant of adequate capacity and capable of yielding a mix of proper and uniform quality with thoroughly coated aggregates.

The plant shall be drum mix type. The plant shall have coordinated set of essential units capable of producing uniform mix within the job mix formula such as laid down in Appendix 'A'.

(a) In case of drum mix plant, the cold feed system shall have variable speed conveyors/ or other suitable devices for regulating the accurate proportion of aggregate in to an even flood flow automatically from a control operation/Control Cabin.

(b) **Bitumen Control Unit:** Capable of measuring/metering and spraying required quantity of bitumen at specified temperature with automatic synchronization of bitumen and aggregate feed.

(c) **Filler System :** A fines feeder system suitable to receive bagged or bulk supply of filler materials and its incorporation to the mix in the correct quantity shall be necessary auxiliary.

(d) **Dust Control :** A suitable built in Dust Control Equipment for the dryer to contain the exhaust of fine dust in the atmosphere for environmental control wherever so specified by the Engineer.

(e) Suitable auxiliary Bitumen Boiler of Adequate capacity with self heating arrangement and temperature control device. The boiler should be fitted with temperature indicating instruments.

The temperature of binder at the time of mixing shall be in range of 150 Degree C to 163 degree and that of the aggregate in the range of 155 degree C - 163 degree C provided that the difference in temperature between the binder and aggregate at no time exceeds 14 Degree C.

Mixing shall be thorough to ensure that a homogeneous mixture is obtained in which all particles of the aggregates are coated uniformly and the discharge temperature of mix shall be between 130 Degree C to 160 degree C.

The mixture shall be transported from the mixing place to the point of use in suitable tipper vehicles. The vehicles employed for transport shall be clean and be covered in transit if so directed by the Engineer. Any tipper causing excessive segregation of materials by its spring suspension or other contributing factors or that which shows undue delay shall be removed from the work unit such conditions are corrected.

Spreading: The mix transferred from the tipper at site to the paver shall be spread immediately by means of self-propelled mechanical paver with suitable screeds capable of spreading, tamping and finishing the mix true to the specified lines, grades and cross sections. The paver finisher shall have the following essential features:

- (a) Loading hoppers and suitable distributing mechanism.
- (b) All drives having hydrostatic drive/control.

- (c) The machine shall have a hydraulically extendable screed the appropriate width requirement.
- (d) The screed shall have tamping and vibrating arrangement for initial compaction to the layer as it is spread without rutting or otherwise marring the surface. It shall have adjustable amplitude and variable frequency.
- (e) The paver shall be equipped with necessary control mechanism so as to ensure that the finished surface is free from surface blemishes.
- (f) The paver shall be fitted with an electronic sensing device for automatic leveling and profile control within the specified tolerances.
- (g) The screed shall have the internal heating arrangement.
- (h) The paver shall be capable of laying either 2.5 to 4.0 m width or 4.0 to 7.0 m width as stipulated in the Contract.
- (i) The paver shall be so designed as to eliminate skidding/slippage of the tyres during operation.

However, in restricted locations and in narrow widths where the available plant cannot be operated in the opinion of the Engineer, he may permit manual laying of the mix.

The temperature of the mix at the time of laying shall be in the range of 120°C to 160°C. In multi-layer construction, the longitudinal joint in one layer shall offset that in the layer below by about 150 mm. However, the joint in the top-most layer shall be at the lane line of the pavement.

Longitudinal joints and edges shall be constructed true to the delineating line parallel to the centre line of the road. All joints shall be cut vertical to the full thickness of the previously laid mix and the surface painted with hot bitumen before placing fresh material. Longitudinal and transverse joints shall be offset by at least 250 mm from those in the lower courses and the joint on the top-most layer shall not be allowed to fall within the wheel path. All transverse joints shall be cut vertically to the full thickness of the previously laid mix with asphalt cutter/pavement breaker and surface painted with hot bitumen before placing fresh material. Longitudinal joints shall be preferably hot joints. Cold longitudinal joints shall be properly heated with joint heater to attain a suitable temperature of about 80°C before laying of adjacent material.

Compaction: After the spreading of mix, rolling shall be done by 80 to 100 kN vibratory roller. Rolling shall start as soon as possible after the material has been spread deploying a set of rollers as the rolling is to be completed in limited time frame. The roller shall move at a speed not more than 5 km/h. Rolling shall be done with care to avoid unduly roughening of the pavement surface.

Rolling of the longitudinal joints shall be done immediately behind the paving operation. After this, the rolling shall commence at the edges and progress towards the centre longitudinally except that on super elevated and uni-directional cambered portions, it shall progress from the lower to the upper edge parallel to the centre line of the pavement.

The initial or break-down rolling shall be done with 80-100 kN static weight smooth wheel roller (3 wheels or tandem) as soon as it is possible to roll the mix without cracking the surface or having the mix pick up on the roller wheels. The second or intermediate rolling shall follow the break-down rolling with vibratory roller of 80 to 100 kN static weight or pneumatic tyred roller of 150 to 250 kN weight, with minimum 7 wheels and minimum tyre pressure of 0.7 MPa as closely as possible to the paver and be done while the paving mix is still at a temperature that will result in maximum density. The final rolling shall be done while material is still workable enough for removal of roller marks with 60 - 80 kN tandem roller. During the final rolling, vibratory system shall be switched off. The joints and edges shall be rolled with a 80 to 100 kN static roller.

When the roller has passed over the whole area once, any high spots or depressions which become apparent shall be corrected by removing or adding mix material. The rolling shall then be continued till the entire surface has been rolled to 95 per cent of the average laboratory density (obtained from Marshall specimens compacted as defined in Table 500-10), there is no crushing of aggregates and all roller marks have been eliminated. Each pass of the roller shall uniformly overlap not less than one-third of the track made in the preceding pass. The roller wheel shall be kept damp if necessary to avoid bituminous material from sticking to the wheels and being picked up. In no case shall fuel, lubricating oil used for this purpose, nor excessive water poured on the wheels.

Rolling operations shall be completed in every respect before the temperature of the mix falls below 100°C.

Roller(s) shall not stand on newly laid material while there is a risk that surface will be deformed thereby. The edges along and transverse of the bituminous grout laid and compacted earlier shall be cut to their full depth so as to expose fresh surface which shall be painted with a thin surface coat of approximate binder before the new mix is placed against it.

Surface Finish and Quality Control of Work :

The surface finish of construction shall conform to the requirements of Clause 902. Control on the quality of materials and works shall be exercised by the Engineer in accordance with Section 900.

The built-up spray grout shall be provided with next surfacing without any delay. If there is to be any delay, the course shall be covered by a seal coat to the requirement of Clause 513 before allowing any traffic over it. The seal coat in such cases shall be considered incidental to the work and shall not be paid for separately.

Arrangement for Traffic:

During the period of construction, arrangement of traffic shall be done to Clause 112 of MORTH Specification.

Passage of Traffic along a part of the Existing Carriageway under Improvement:

For widening/strengthening existing carriageway where part width of the existing carriageway is proposed to be used for passage of traffic, treated shoulders shall be provided on the side on which work is not in progress. The treatment to the shoulder shall consist of providing at least 150 mm thick granular base course covered with bituminous surface dressing in a width of at least 1.5 m and the surface shall be maintained throughout the period during which traffic uses the same to the satisfaction of the Engineer. The continuous length in which such work shall be carried out, would be limited normally to 500 m at a place. However, where work is allowed by the Engineer in longer stretches passing places at least 20 m long with additional paved width of 2.5 m shall be provided at every 0.5 km interval.

In case of widening existing two-lane to four-lane the additional two lanes would be constructed first and the traffic diverted to it and only thereafter the required treatment to the existing carriageway would be carried out. However, in case where on the request of the Contractor work on existing two lane carriageway is allowed by the Engineer with traffic using part of the existing carriageway, stipulations as in para above shall apply.

After obtaining permission of the Engineer, the treated shoulder shall be dismantled the debris disposed of and the area cleared as per the direction of the Engineer.

MEASUREMENTS FOR PAYMENT:

The payment shall be made on the tonnage basis of the weight of mix of aggregates and

bitumen. For this purpose, the contractor shall have to install a weight bridge of suitable capacity for the purpose of weighing of dumpers at suitable place at his cost as directed. Weight of empty and weight of loaded dumper will be recorded in bound and numbered register on plant site. Department will be free to get some loaded dumpers test checked at other weight bridge. Weight bridge will be periodically got calibrated and verified from weight and measure authorities.

For the purpose of application of tack coat, if the theoretical area as per sanctioned estimate for basis of tonne differs with the actual area of work done in the field, the reduction in or addition to payment shall have to be decided respectively.

Weight of mix materials will be done in presence of responsible person, not less than the rank : of supervisor of department and the measurement shall be recorded by the Deputy Engineer or Assistant Engineer or Addl. Asst. Engineer. If so authorized, record of each dumper will be maintained separately in bound and numbered register, which will be maintained by the departmental representative and signed by the contractor. Proper gate pass system shall be established for the vehicles coming to the plant site and out going from the plant site. The location of the kilometer, hectometer and meter in which individual dumper are unloaded shall be recorded carefully.

RATE :

The contract unit rate for the work shall be payment in full for carrying out the required operations including full compensation for

- (i) Making arrangements for traffic to Clause 112 of MORTH specification except or initial treatment to verge, shoulders and construction of diversion.
- (ii) Preparation of base except for laying of profile corrective course but including filling of potholes.
- (iii) Providing all materials to be incorporated in the work including arrangement for stock yards, all royalties, fees, rents where necessary and all leads and lift.
- (iv) All labour, tools, equipment, plant including installation of drum mix plant, power supply units and all machineries, incidental to complete the work to the specifications.
- (v) Carrying out the work in part widths of the road where directed.
- (vi) Carrying out all tests for control of quality.

Item No 7.

Clearing and grubbing road land including uprooting trunk vegetation, grass bushes, shrubs, saplings and tree girth up to 300 mm, removal of stumps of trees cut earlier and disposal of unserviceable materials (C) by mechanical means in area of light jungle

201.1 GENERAL :-

This work shall consist of cutting, removing and disposing of all materials such as trees, bushes, shrubs, stumps, roots, grass, weeds, top organic soil not exceeding 300mm in thickness, rubbish etc. which in the opinion of the engineer are unsuitable for incorporation in the works, from the area of road land containing road embankment, drains, cross-drainage, structure and such other areas as may be specified by the Engineer. It shall include necessary excavation, back-filling of pits resulting from uprooting of trees and stumps to required compaction, handling, salvaging, and disposal of cleared materials. Cleaning and grubbing shall be performed in advance of earthwork operations and in accordance with the requirement of this specification.

201.2 Preservation of property / Amenties :-

Road side trees, shrubs and other plants, pole, lines, fences, signs, monuments, buildings, pipe lines, sewers and all highway facilities within or adjacent to the highway which are not to be disturbed shall be protected from injury or damage. The contractor shall provide and install at his own expense suitable safeguards approved by the Engineer for this purpose.

During clearing and grubbing, the contractor shall take all adequate precautions against soil erosion, water pollution etc. and where required undertake additional works to that effect as per Clause 306 of MORTH specification booklet for Roads and Bridge. Before start of operations, the contractor shall submit the engineer for approval, his work plan including the procedure to be followed for disposal of waste materials etc., and the schedule for carrying out temporary and permanent erosion control works as stipulated in Clause 306.3 of MORTH specification booklet for Roads & Bridges.

201.3 Methods, Tools and Equipments :-

Only such methods, tools and equipments as are approved by the Engineer and which will not affect the property to be preserved shall be adopted for the work. If there is thick vegetation / roots / trees a crawler or pneumatic tyred dozer adequate capacity may be used for clearance purpose. The dozer shall have ripper attachments for removal of tree stumps. All trees, stumps etc. falling within excavation and fill lines shall be cut to such depth below ground level that in no case these fall within 500mm of the sub-grade. Also, all vegetation such as roots, under-growth, grass and other deleterious matter unsuitable for incorporation in the embankment / sub-grade shall be removed between fill lines to the satisfaction of the Engineer. On areas beyond these limits, trees and stumps required to be removed as directed by the Engineer shall be cut down to 1 m below ground level so that these do not present an unsightly appearance.

All branches of trees extending above the roadway shall be trimmed as directed by the Engineer.

All excavation below the general ground level arising out of the removal of trees, stumps etc. shall be filled with suitable materials and compacted thoroughly so as to make the surface at these points conform to the surrounding area.

Ant-hills both above and below the ground, as are liable to collapse and obstruct free subsoil water flow shall be removed and their workings, which may extend to several

metres shall be suitably treated.

201.4 Disposal of materials :-

All materials arising from clearing and grubbing operation shall be the property of the government and shall be disposed by the Contractor as herein after provided or as directed by the Engineer-in-charge.

Trunks, branches and stumps of trees shall be cleared of limbs and roots and stacked. Also boulders, stones and other materials usable in road construction, shall be neatly stacked as directed by the Engineer. Stacking of stumps, boulders, stones etc. shall be done at specified spots with all lead and lifts.

All products of clearing and grubbing which in the opinions of the Engineer, cannot be used or auctioned shall be cleared away from the road sides in a manner as directed by the Engineer. Care shall be taken to see that unsuitable waste materials are disposed of in such a manner that there is no likelihood of these getting mixed up with the materials meant of embankment, sub-grade and road construction.

201.5 Measurement for payments :-

Clearing and grubbing for road embankment, drains and cross-drainage structures shall be measured on area basis in terms of **Hectares**. Cutting of trees upto 300mm in girth and removal of their stumps, including removal of stumps upto 300mm in girth left over after trees have been cut by any other agency and trimming of branches of trees extending above the roadway and back filling to the required compaction shall be considered incidental to the clearing and grubbing operations. Clearing and grubbing of borrow areas shall be deemed to have been included in the rates quoted for the embankment construction item and no separate payment shall be made for the same

Ground levels shall be taken prior to and after clearing and grubbing. Levels taken prior to clearing and grubbing shall be the base level and will be accordingly used for assessing the depth of clearing and grubbing and computation of quantity of any unsuitable material which is required to be removed. The levels taken subsequent to clearing and grubbing shall be the base level for computation of earthwork for embankment.

Cutting of trees, excluding removal of stumps and roots of trees of girth above 300 mm shall be measured in terms of number according to the girth sizes given below:-

- (i) Above 300 mm to 600 mm
- (ii) Above 600 mm to 900 mm
- (iii) Above 900 mm to 1800 mm
- (iv) Above 1800 mm

Removal of stumps and roots including back filling with suitable material to required compaction shall be a separate item and shall be measured in terms of number according to the sizes given below:-

- (i) Above 300 mm to 600 mm
- (ii) Above 600 mm to 900 mm
- (iii) Above 900 mm to 1800 mm
- (iv) Above 1800 mm

For this purpose of cutting of trees and removal of roots and stumps, the girth shall be measured at a height of 1 metre above ground or at the top of the stump if the height of the stump is less than one metre from the ground.

201.6 Rates :-

The Contract unit rates for the various items of clearing and grubbing shall be payment in full for carrying out the required operations including full compensation for all labour, materials, tools, equipment and incidentals necessary to complete the work. These will also include removal of stumps of trees less than 300mm girth excavation and back-filling to required density, where necessary and handling, giving credit towards salvage value disposing of the cleared materials with all lifts and leads. Clearing and grubbing done in excess of 150 mm by the Contractor shall be made good by the Contractor at his own cost as per Clause 301.3.3 to the satisfaction of the Engineer prior to taking up earthwork. Where clearing and grubbing is to be done to a level beyond 150 mm, due to site considerations, as directed by the Engineer, the extra quantity shall be measured and paid separately.

The Contract unit rate for cutting trees of girth above 300 mm shall include handling, giving credit towards salvage value disposing of the cleared materials with all lifts and leads.

The Contract unit rate for removal of stumps and roots of trees girth above 300 mm shall include excavation and backfilling with suitable material to required compaction, handling, giving credit towards salvage value disposing of the cleared materials with all lifts and leads.

The Contract unit rate is deemed to include credit towards value of usable materials, salvage value of unusable material and off-set price of cut trees and stumps belonging to the forest Department. The off-set price of cut trees and stumps belonging to the Forest Department shall be deducted from the amount due to the Contractor and deposited with the State Forest Department. In case the cut trees and stumps are required to be deposited with the Forest Department the Contractor shall do so and no deduction towards the off-set price shall be effected. The offset price shall be as per guidelines I estimates of the state Forest Department.

Where a Contract does not include separate items of clearing and grubbing, the same shall be considered incidental to the earthwork items and the Contract unit prices for the same shall be considered as including clearing and grubbing operations.

The Payment shall be made on ONE HECTOR basis.

Item No 8.**Graded II Granular sub base (GSB)**

Providing & Laying of Compacted closed graded Granular Sub base(GSB) in single layer of graded granular material consisting of only black trap crushed stone aggregate as per grading-IV given table 400-1 of the specification MORT & H and compacted to the required density with vibratory roller with plain drum or heavy pneumatic tyred roller of minimum 200 to 300 KN weight in all seasons as per MORT&H, maintaining the required slope & grade during the operation as approved by the engineer in charge & watering to the proper moisture content and sprinkled with the help of truck mounted water tank fitted with suitable arrangements (Fully saturated having CBR value not less than 30)

Scope

This work shall consist of laying and compacting well-graded material on prepared subgrade in accordance with the requirements of these Specifications. The material shall be laid in one or more layers as sub-base or lower sub-base and upper sub-base (termed as sub-base hereinafter) as necessary according to lines, grades and cross-sections shown on the drawings or as directed by the Engineer.

Materials

The material to be used for the work shall be granular sub base in single layer as per gradation made of natural locally available material in proper proportion and approved by engineer in charge as directed (having C.B.R. not less than 25%).

While the gradings in Table 400-1 are in respect of close-graded granular sub-base materials, one each for maximum particle size of 75 mm, 53mm and 9.5 mm, the corresponding gradings for the coarse graded materials for each of the three maximum particle sizes are given at Table 400-2. The grading to be adopted for a project shall be as specified in the Contract.

Physical requirements :-

The materials shall have a 10 percent lines value of 50 kN or more (for sample in soaked condition) when tested in compliance with BS:812 (Part III). The water absorption value of the coarse aggregate shall be determined as per IS: 2386 (Part 3), if this value is greater than 2 percent, the soundness test shall be carried out on the material delivered to site as per IS: 383. For Grading-II and III materials, the CBR shall be determined at the density and moisture content likely to be developed in equilibrium conditions which shall be taken as being the density relating to a uniform air voids content of 5 percent.

TABLE 400-1. GRADING FOR CLOSE GRADED GRANULAR SUB-BASE MATERIALS.

Sieve Designation	Percent by Weight Passing the IS Sieve		
	Grading I	Grading II	Grading III
75.00mm	100	--	--
53.00mm	80-100	100	100
26.5mm	55-90	70-100	55-75
9.50mm	35-65	50-80	--
4.75mm	25-55	40-65	10-30
2.36mm	20-40	30-50	--

0.425mm	10-15	10-15	--
0.075mm	<5	<5	<5
CBR Value	30	25	20

TABLE 400-2, GRADING FOR COARSE GRADED GRANULAR SUB-BASE MATERIALS

Sieve Designation	Percent by Weight Passing the IS Sieve		
	Grading I	Grading II	Grading III
75.00mm	100		
53.00mm		100	
26.5mm	55-75	50-80	100
9.50mm			
4.75mm	10-30	15-35	25-45
2.36mm			
0.425mm			
0.075mm	< 10	< 10	< 10
CBR Value	30	25	20

Note:-The material passing 425 micron (0.425 mm) sieve for all the three grading when tested according to IS: 2720(Part 5) shall have liquid limit and plasticity index not more than 25 and 6 percent respectively.

Strength of sub-base:-

It shall be ensured prior to actual execution that the material to be used in the sub-base satisfies the requirements of CBR and other physical requirements when compacted and finished.

When directed by the Engineer, this shall be verified by performing CBR tests in the laboratory as required on specimens remolded at field dry density and moisture content and any other tests for the "Quality" of materials, as may be necessary.

Construction Operations:

Preparation of subgrade:-

Immediately prior to laying of sub-base, the subgrade already finished to Clause 301 or 305 as applicable shall be prepared by removing all vegetation and other extraneous matter, lightly sprinkled with water if necessary and rolled with two passes of 80-100 kN smooth wheeled roller.

Spreading and compacting:

The sub-base material of grading specified in the Contract shall be spread on the prepared subgrade with the help of a motor grader of adequate capacity, its blade having hydraulic controls suitable for initial adjustment and for maintaining the required slope and grade during the operation or other means as approved by the Engineer.

When the sub-base material consists of combination of materials mentioned in Clause 401.2.1, mixing shall be done mechanically by the mix-in-place method.

Manual mixing shall be permitted only where the width of laying is not adequate for mechanical operations as in small sized jobs. The equipment used for mix-in-place construction shall be a rotavator or similar approved equipment capable of mixing the material to the desired degree. If so desired by the Engineer, trial runs with the equipment shall be carried out to establish its suitability for the work.

Moisture content of the loose material shall be checked in accordance with IS:2720 (Part 2) and suitably adjusted by sprinkling additional water from a truck mounted or trailer mounted water tank and suitable for applying water uniformly and at controlled quantities to variable widths of surface or other means approved by the Engineer so that, at the time of compaction, it is from 1 percent above to 2 percent below the optimum moisture content corresponding to IS:2720 (Part 8). While adding water, due allowance shall be made for evaporation losses. After water has been added, the material shall be processed by mechanical or other approved means like disc harrows, rotavators until the layer is uniformly wet.

Immediately thereafter, rolling shall start. If the thickness of the compacted layer does not exceed 100 mm, a smooth wheeled roller of 80 to 100 kN weight may be used. For a compacted single layer upto 225 mm the compaction shall be done with the help of a vibratory roller of minimum 80 to 100 kN static weight with plain drum or pad foot-drum or heavy pneumatic tyred roller of minimum 200 to 300 kN weight having a minimum tyre pressure of 0.7 MN/m² or equivalent capacity roller capable of achieving the required compaction. Rolling shall commence at the lower edge and proceed towards the upper edge longitudinally for portions having unidirectional crossfall and super elevation and shall commence at the edges and progress towards the center for portions having cross fall on both sides.

Each pass of the roller shall uniformly overlap not less than one third of the track made in the preceding pass. During rolling, the grade and cross fall (Camber) shall be checked and any high spots or depressions which become apparent, corrected by removing or adding fresh material. The speed of the roller shall not exceed 5 Km. Per hour.

Rolling shall be continued till the density achieved is at least 98 per cent of the maximum dry density for the material determined as per IS:2720 (Part 8). The surface of any layer of material on completion of compaction shall be well closed, free from movement under compaction equipment and from compaction planes, ridges, cracks or loose material. All loose, segregated or otherwise defective areas shall be made good to the full thickness of layer and re-compacted.

Surface Finish and Quality Control of Work:-

The surface finish of construction shall conform to the requirements of Clause 902.

Control on the quality of materials and works shall be exercised by the Engineer in accordance with Section 900.

Arrangements for Traffic :-

During the period of construction, arrangement of traffic shall be maintained in accordance with clause 112.

Measurements for payment:-

During granular materials sub-base shall be measured as finished work in position in cubic metres.

The protection of edges of granular materials sub-base extended over the full formation as shown in the drawing shall be considered incidental to the work of providing granular sub-base and as such no extra payment shall be made for the same

RATE:-

The contract unit rate for granular materials sub-base shall be payment in full for carrying out the required operations including full compensation for

- (i)** making arrangements for traffic to Clause 112 except for initial treatment to verges, shoulders and construction of diversions;
- (ii)** furnishing all materials to be incorporated in the work including all royalties, fees, rents where necessary and all leads and lifts;
- (iii)** all labour, tools, equipment and incidentals to complete the work to the specifications;
- (iv)** carrying out the work in part widths of road where directed; and
- (v)** carrying out the required tests for quality control.

Item No 9.

Scarifying gravelled macadam or bitumen macadam surface 6cm to 10 cm depth including stacking useful materials on road side spreading the same in required grade and camber with adding fresh key aggregate 6mm to 10mm nominal size at the rate of 0.18 cum / 10sqm of scarified area including compacting with vibratory roller and disposing of the remaining stuff as directed.

1. The layer of the existing layer metalling / bituminous layer shall excavated for all depth as directed by Engineer-in-charge and shall be screened on site of work. Stacking of 75% of metal obtained from screening shall be done by filling in the standard steel boxes of 2m x 1.5 m x 0.5 mt. size which shall be supplied by department if available on rent, otherwise contractor shall make his own arrangements. No deductions for voids shall be made from the gross measurements. Where any doubt exist as to whether the quantity of stacks of metal in any hectometer is not confirming with cubical content of the standard pharas (2m x 15 mt. x 0.5 mt.) shall be got corrected by the contractor if so ordered by the Engineer-in-charge for which no extra payment shall be claimed by the contractor. If the quantity of metal in -any stack in a particular hectometer is found to be less then the standard measurements viz. 1.5 cmt. the entire collection in the hectometre shall be paid on the basis of the quantity so found. Regular stacks shall be done by the contractor on a tairiy level ground. Stacking of the metal shall be done in a manner as directed by the Engineer-in-charge.
2. The remaining material except 75% of metal obtained from screening process shall be used in embankment with all lead and lift. It shall be directly deposited at the required location in specified layers. No handling or conveyance charges shall be paid if the materials is temporarily deposited else where and subsequently convey to site of deposition. The sequence of operations should be arranged properly. Material not required for any use whatsoever may be disposed off by the contractor at his own cost in manner approved by the Engineer-in-charge. The material utilised in the embankment will be deducted irom the net quantity of earthwork in embankment arrived at within the chainage measured.
3. The payment shall be made on Sq.mt. basis, the contractor shall maintain all stacks in regular and proper size till the whole materials shall not be measured and finally accepted by the department. The spreading of materials shall not be allowed till the materials are fully stacked and completed kilometer wise.
4. The rate includes the cost of scarifying macadam, screening, depositing. conveyance with all lead and lift, filling the boxes including all labour, tools, equipments and all other incidental expenses.

Item No 10.

Providing and Spraying Prime Coat with Bitumen emulsion S S-1 @ 7.50 Kg / 10 SqM including Cost of asphalt

502.1. Scope

This work shall consist of the application of a single coat of low viscosity liquid bituminous material to a porous granular surface preparatory to the superimposition of bituminous treatment or mix. The work shall be carried out on a previously prepared granular/ stabilized surface to Clause 501.8.

502.2. Materials

502.2.1. The primer shall be cationic bitumen emulsion SS1 grade conforming to IS:8887 or medium curing cutback bitumen conforming to IS:217 or as specified in the Contract.

502.2.2. Quantity of SS1 grade bitumen emulsion for various types of granular surface shall be as given in Table 500-3.

Table 500-3 : Quantity of Bitumen Emulsion for Various Types of Granular Surfaces

Type of Surface	Rate of Spray (kg/sq.m)
WMM/WBM	0.7 - 1.0
Stabilized soil bases/Crusher Run Macadam	0.9 - 1.2

502.2.3. Cutback for primer shall not be prepared at the site. Type and quantity of cutback bitumen for various types of granular surface shall be as given in Table 500-4.

Table 500-4 : Type and Quantity of Cutback Bitumen for Various Types of Granular Surface

Type of Surface	Type of Cutback	Rate of Spray (kg/sq.m)
WMM/WBM	MC 30	0.6 - 0.9
Stabilized soil bases/Crusher Run Macadam	MC 70	0.9 - 1.2

502.2.4. The correct quantity of primer shall be decided by the Engineer and shall be such that it can be absorbed by the surface without causing run-off of excessive primer and to achieve desired penetration of about 8-10 mm.

502.3. Weather and Seasonal Limitations

Primer shall not be applied during a dust storm or when the weather is foggy, rainy or windy or when the temperature in the shade is less than 10°C. Cutback bitumen as primer shall not be applied to a wet surface. Surfaces which are to receive emulsion primer should be damp, but no free or standing water shall be present. Surface can be just wet by very light sprinkling of water.

502.4. Construction**502.4.1 Equipment**

The primer shall be applied by a self-propelled or towed bitumen pressure sprayer equipped for spraying the material uniformly at specified rates and temperatures. Hand spraying shall not be allowed except in small areas, inaccessible to the distributor, or in narrow strips where primer shall be sprayed with a pressure hand sprayer, or as directed by the Engineer.

502.4.2 Preparation of Road Surface

The granular surface to be primed shall be swept clean by power brooms or mechanical sweepers and made free from dust. All loose material and other foreign material shall be removed completely. If soil/ moorum binder has been used in the WBM surface, part of this should be brushed and removed to a depth of about 2 mm so as to achieve good penetration.

502.4.3 Application of Bituminous Primer

After preparation of the road surface as per Clause 502.4.2, the primer shall be sprayed uniformly at the specified rate. The method for application of the primer will depend on the type of equipment to be used, size of nozzles, pressure at the spray bar and speed of forward movement. The Contractor shall demonstrate at a spraying trial, that the equipment and method to be used is capable of producing a uniform spray, within the tolerances specified.

No heating or dilution of SS1 bitumen emulsion and shall be permitted at site. Temperature of cutback bitumen shall be high enough to permit the primer to be sprayed effectively through the jets of the spray and to cover the surface uniformly.

502.4.4 Curing of Primer and Opening to Traffic

A primed surface shall be allowed to cure for at least 24 hours or such other higher period as is found to be necessary to allow all the moisture/volatiles to evaporate before any subsequent surface treatment or mix is laid. Any unabsorbed primer shall first be blotted with a light application of sand, using the minimum quantity possible. A primed surface shall not be opened to traffic other than that necessary to lay the next course.

502.5 Quality Control of Work

For control of the quality of materials and the works carried out, the relevant provisions of Section 900 shall apply.

502.6 Arrangements for Traffic

During construction operations, arrangements for traffic shall be made in accordance with the provisions of Clause 112.

502.7 Measurement for Payment

Prime coat shall be measured in terms of surface area of application in square metres.

502.8 Rate

The contract unit rate for prime coat shall be payment in full for carrying out the required operations including full compensation for all components listed in Clause 401.7 (i) to (v) and as applicable to the work specified in these Specifications. Payment shall be made on the basis of the provision of prime coat at an application rate of quantity at 0.6 kg per square metre or at the rate specified in the Contract, with adjustment, plus or minus, for the variation between this quantity and the actual quantity approved by the Engineer after the preliminary trials referred to in Clause 502.4.3.

Item No 11.

Earth work for embankment including breaking clods, dressing with all lead and lift including watering, rolling and consolidation of sub grade in layers at O.M.C to required dry density including filling the depression which occur during the process using vibratory roller 8 to 10 Tonne (c) From Borrow area with in 3.0 KM Lead

305. EMBANKMENT CONSTRUCTION

305.1 General:

305.1.1 Description:

These Specifications shall apply to the construction of embankments including sub grades, earthen shoulders and miscellaneous backfills with approved materials obtained from roadway and drain excavation, borrow pits or other sources. All embankments, sub grades, earthen shoulders and miscellaneous backfills shall be constructed in accordance with the requirements of these specifications and in conformity with the lines, grades, and cross-sections shown on the drawings or as directed by the Engineer.

305.2 Materials and General Requirements.

305.2.1 Physical requirements :

305.2.1.1 The materials used in embankments, sub grades, earthen shoulders and miscellaneous backfills shall be soil, murrum, gravel, a mixture of these or any other material approved by the Engineer. Such materials shall be free of logs, stumps, roots, rubbish or any other ingredient likely to deteriorate or affect the stability of the embankment sub grade.

The following types of material shall be considered unsuitable for embankment:

- (a)** Materials from swamps, marshes and bogs;
- (b)** Peat, log, stump and perishable material; and soil that classifies as OL,OI, OH or Pt in
- (c)** Materials susceptible to spontaneous combustion;
- (d)** Materials in a frozen condition;
- (e)** Clay having liquid limit exceeding 50 and plasticity index exceeding 25; and
- (f)** Materials with salts resulting in leaching in the embankment.

305.2.1.2 Expansive clay exhibiting marked swell and shrinkage, properties ("free swelling index" exceeding 50 percent when tested as per IS:2720-Part 40) shall not be used as a fill material. Where an expansive clay with acceptable "free swelling index" value is used as a fill material, sub grade and top 500mm portion of the embankment just below sub grade shall be non-expansive in nature.

305.2.1.3 Any fill material with a soluble sulphate content exceeding 1.9 grams of sulphate (expressed as SO₃) per liter when tested in accordance with BS:1377 Part-3, but using a 2:1 water-soil ratio shall not be deposited within 500 mm or other distance described in the Contract), permanent works constructed out of concrete, cement bound materials or other cementations materials.

Materials with a total sulphate content (expressed as SO₃) exceeding 0.5 per cent by mass, when tested in accordance with BS: 1377, Part 3 shall not be deposited within 500 mm or other distances described in the contract, of metallic items forming part of the

305.2.1.4 The size of the coarse material in the mixture of earth shall ordinarily not exceed 75mm when being placed in the embankment and 50 mm when placed in the sub grade. However, the Engineer may at his discretion permit the use of material coarser than this also if he is satisfied that the same will not present any difficulty as regards the

placement of fill material and its compaction to the requirements of these specifications. The maximum particle size shall not be more than two-thirds of the compacted layer thickness.

305.2.1.5 Ordinarily, only the materials satisfying the density requirements given in Table 300-1 shall be employed for the construction of the embankment and the sub grade.

TABLE 300-1. DENSITY REQUIREMENTS OF EMBANKMENT AND SUBGRADE MATERIALS

S.No.	Type of work	Maximum laboratory dry unit weight when tested as per IS:2720(Part 8)
1	Embankments upto 3 metres height, not subjected to extensive flooding.	Not less than 15.2 kN/cu.m.
2	Embankments exceeding 3 metres height or embankments of any height subject to long periods of inundation.	Not less than 16.0 kN/cu.m.
3	Subgrade and earthen shoulders/ Verges/backfill	Not less than 17.5 kN/cu.m.

Notes: (1) This Table is not applicable for lightweight fill materials e.g. cinder, fly ash etc.
(2) The materials to be used in sub grade shall be non-expensive and shall satisfy design CBR at the specified dry density and moisture content. In case the available materials fail to meet the requirement of CBR, use of stabilization methods in accordance with Clause 403 and 404 or by any stabilization method approved by the Engineer shall be followed.

305.2.1.6 The materials to be used in sub grade shall conform to the design CBR value at the specified dry density and moisture content of the test specimen. In case the available materials fails to meet the requirement of CBR, use of stabilization methods in accordance with Clause 403 and 404 or by any stabilization method approved by the Engineer or by the IRC Association Committee shall be followed.

305.2.1.7 The materials to be used in high embankment construction shall satisfy the specified requirements of strength parameters.

305.2.2 General Requirements:

305.2.2.2 The materials for embankment shall be obtained from approved sources with preference given to materials becoming available from nearby roadway excavation or any other excavation under the same Contract.

The work shall be so planned and executed that the best available materials are saved for the sub grade and the embankment portion just below the sub grade.

305.2.2.2 Borrow materials:

The arrangement for the source of supply of the materials for embankment and sub grade and compliance with the guidelines, and environmental requirements, in respect of excavation and borrow areas as stipulated, from time to time by the Ministry of Environment and Forests, Government of India and the local bodies, as applicable, shall be the sole responsibility of the Contractor.

Borrow pits along the road shall be discouraged. If permitted by the Engineer, these shall not be dug continuously. Ridges of not less than 8 m width should be left at intervals not exceeding 300m. Small drains shall be cut through the ridges to facilitate drainage.

The depth of the pits shall be so regulated that their bottom does not cut an imaginary line having a slope of 1 vertical to 4 horizontal projected from the edge of the final section of the bank, the maximum depth in any case being limited to 1.5 m. Also, no pit shall be dug within the offset width of a minimum of 10 m.

Haulage of material to embankments or other areas of fill shall proceed only when sufficient spreading and compaction plant is operating at the place of deposition.

Where the excavation reveals a combination of acceptable and unacceptable materials, the Contractor shall, unless otherwise agreed by the Engineer, carry out the excavation in such a manner that the acceptable materials are excavated separately for use in the permanent works without contamination by the unacceptable materials. The acceptable materials shall be stockpiled separately.

The Contractor shall ensure that he does not adversely affect the stability of excavation or fills by the methods of stockpiling materials, use of plants or sitting of temporary buildings or structures.

305.2.2.3 Fly-Ash

User of fly-ash shall conform to the Ministry of Environment and Forest guidelines. Where fly-ash is used the embankment construction shall conform to the physical and chemical properties and requirements of IRC:SP:38-2001, "Guidelines for Use of Flyash in Road Construction". The term fly-ash shall cover all types of coal ash such as ponds ash, bottom ash or mound ash.

Embankment constructed out of fly ash shall be properly designed to ensure stability and protection against erosion in accordance with IRC guidelines. A suitable thick cover may preferably be provided at intervening layers of pond as for this purpose. A thick soil cover shall bind the edge of the embankment to protect it against erosion. Minimum thickness of such soil cover shall be 500mm.

305.2.2.4 Compaction Requirements

The Contractor shall obtain representative samples from each of the identified borrow areas and have these tested at the site laboratory following a testing programme approved by the Engineer. It shall be ensured that the sub grade material when compacted to the density requirements as in Table 300-2 shall yield the design CBR value of the sub grade.

TABLE 300-2. COMPACTION REQUIREMENTS FOR EMBANKMENT AND SUBGRADE.

S.No.	Type of work/material	Relative compaction as percentage of max. laboratory dry density as per IS:2720 (Part 8)
1	Sub grade and earthen shoulders	Not less than 97%
2	Embankment	Not less than 95%
3	Expansive Clays	
	a) Sub grade and 500mm portion Just below the sub grade.	Not allowed.
	b) Remaining portion of embankment	Not less than 90-95%

The Contractor shall at least 7 working days before commencement of compaction submit the following to the Engineer for approval :

- (i) The values of maximum dry density and optimum content obtained in accordance with IS:2720 (Part 8), appropriate for each of the fill materials he intends to use.
- (ii) A graph of density plotted against moisture content from which each of the values in (i) above of maximum dry density and optimum moisture content were determined.

The maximum dry density and optimum moisture content approved by the Engineer, it shall form the basis for compaction.

305.3 Construction Operations :

305.3.1 Setting Out

After the site has been cleared to Clause 201, the work shall be set out to Clause 301.3.1. The limits of embankment/sub grade shall be marked by fixing batter pegs on both sides at regular intervals as guides before commencing the earthwork. The embankment/sub grade shall be built sufficiently wider than the design dimension so that surplus material may be trimmed, ensuring that the remaining material is to be desired density and the position specified and conforms to the specified side slopes.

305.3.2 Dewatering

If the foundation of the embankment is in an area with stagnant water, and in the opinion of the Engineer it is feasible to remove it, the same shall be removed by bailing out or pumping, as directed by the Engineer and the area of the embankment foundation shall be kept dry. Care shall be taken to discharge the drained water so as not to cause damage to the works, crops or any other property. Due to any negligence on the part of the Contractor, if any such damage is caused, it shall be the sole responsibility of the Contractor to repair./restore it to original condition or compensate the damage at his

If the embankment is to be constructed under water, Clause 305.4.6 shall apply.

305.3.3 Stripping and Storing topsoil

In localities where most of the available embankment materials are not conducive to plant growth, or when so directed by the Engineer, the topsoil from all areas of cutting and from all areas to be covered by embankment foundation shall be stripped to specified depths not exceeding 150 mm and stored in stockpiles of height not exceeding 2 m for covering embankment slopes, cut slopes and other disturbed areas where re-vegetation is desired. Topsoil shall not be unnecessarily trafficked either before stripping or when in a stockpile. Stockpiles shall not be surcharged or otherwise loaded and multiple handling shall be kept to a minimum.

305.3.4 Compacting ground supporting embankment/Sub grade:

Where necessary, the original ground shall be leveled to facilitate placement of first layer of embankment, scarified, mixed with water and then compacted by rolling in accordance with Clause 305.3.5 and 305.3.6 so as to achieve minimum dry density as given in Table In case where the difference between the sub grade level (top of the sub grade on which pavement rests) and ground level is less than 0.5 m and the ground does not have 97 per cent relative compaction with respect to the dry density as given in Table 300-2, the ground shall be loosened up to a level 0.5m below the sub grade level, watered and compacted in layers in accordance with Clauses 305.3.5 and 305.3.6 to achieve dry density not less than 97 percent relative compaction as given in Table 300-2.

Where so directed by the Engineer, any unsuitable material occurring in the embankment foundation (500mm portion just below the sub-grade) shall be removed and replaced by approved materials laid in layers to the required degree of compaction.

Any foundation treatment specified for embankments especially high embankments, resting on suspect foundations as revealed by borehole logs shall be carried out in a manner and to the depth as desired by the Engineer. Where the ground on which an embankment is to be built has any of the material types (a) to (f) in Clause 305.2.1, at least 500 mm of such material must be removed and replaced by acceptable fill material before embankment construction commences.

305.3.5 Spreading material in layers and bringing to appropriate moisture content

305.3.5.1 The embankment and sub grade material shall be spread in layers of uniform thickness in the entire width with a motor grader. The compacted thickness of each layer shall not be more than 250mm when vibratory roller / vibratory soil compactor is used and not more than 200 mm when 80-100 kN static roller is used. The motor grader blade shall have hydraulic control suitable for initial adjustment and maintain the same so as to achieve the specific slope and grade. Successive layers shall not be placed until the layer under construction has been thoroughly compacted to the specified requirements as in Table 300-2 and got approved by the Engineer. Each compacted layer shall be finished parallel to the final cross-section of the embankment.

305.3.5.2 Moisture content of the material shall be checked at the site of placement prior to commencement of compaction; if found to be out of agreed limits, the same shall be made good. Where water is required to be added in such constructions, water shall be sprinkled from a water tanker fitted with sprinkler capable of applying water uniformly with a controllable rate of flow to variable widths of surface but without any flooding. The water shall be added uniformly and thoroughly mixed in soil by balding, dicing or barrowing until a uniform moisture content is obtained throughout the depth of the

If the material delivered to the roadbed is too wet, it shall be dried, by aeration and exposure to the sun, till the moisture content is acceptable for compaction. Should circumstances arise, where owing to wet weather, the moisture content can not be reduced to the required amount by the above procedure, compaction work shall be

Moisture content of each layer of soil shall be checked in accordance with IS:2720 (Part 2), and unless otherwise mentioned, shall be so adjusted, making due allowance for evaporation losses, that at the time of compaction it is in the range of 1 per cent above to 2 per cent below the optimum moisture content determined in accordance with IS:2720 (Part 8) as the case may be. Expansive clays shall, however, be compacted at moisture content corresponding to the specified dry density, but on the wet side of the optimum moisture content obtained from the laboratory compaction curve.

After adding the required amount of water, the soil shall be processed by means of graders, harrows, rotary mixers or as otherwise approved by the Engineer until the layer is uniformly wet.

Clods or hard lumps of earth shall be broken to have a maximum size of 75 mm when being placed in the embankment and a maximum size of 50 mm when being placed in the sub grade.

305.3.5.3 Embankment and other areas of fill shall, unless otherwise required in the Contract or permitted by the Engineer, be constructed evenly over their full width and their fullest possible extent and the Contractor shall control and direct construction plant and other vehicular traffic uniformly over them. Damage by construction plant and other vehicular traffic shall be made good by the Contractor with material having the same characteristics and strength as the material had before it was damaged.

Embankments and other areas of unsupported fills shall not be constructed with steeper side slopes, or to greater widths than those shown in the Contract, except to permit adequate compaction at the edges before trimming back, or to obtain the final profile following any settlement of the fill and the underlying material.

Whenever fill is to be deposited against the face of a natural slope, or sloping earthworks face including embankments, cutting, another fills and excavations steeper than 1 vertical on 4 horizontal, such faces shall be benched as per Clause 305.4.1 immediately before placing the subsequent fill.

All permanent faces of side slopes of embankments and other areas of fill formed shall, subsequent to any trimming operations, be reworked and sealed to the satisfaction of the Engineer by tracking a tracked vehicle, considered suitable by the Engineer, on the slope or any other method approved by the Engineer.

305.3.6 Compaction

Only the compaction equipment approved by the Engineer shall be employed to compact the different material types encountered during construction. Static three wheeled roller, self propelled single drum vibratory roller, tandem vibratory roller, pneumatic type roller, pad foot roller etc. of suitable size and capacity as approved by the Engineer shall be used for the different types and grades of materials required to be compacted either individually or in suitable combinations.

The compaction shall be done with the help of self propelled single drum vibratory roller or pad foot vibratory roller of 80 to 100 kN static weight or heavy pneumatic type roller of adequate capacity capable of achieving the required compaction. The contractor shall demonstrate the efficacy of the equipment he intends to use by carrying out compaction trails. The procedure to be adopted for these site trials shall be submitted to the Engineer for approval.

Earthmoving plant shall not be accepted as compaction equipment nor shall the use of a lighter category of plant to provide any preliminary compaction to assist the use of heavier plant be taken into account.

Each layer of the material shall be thoroughly compacted to the densities specified in Table 300-2. Subsequent layers shall be placed only after the finished layer has been tested according to Clause 903.2.2 and accepted by the Engineer. The Engineer may permit measurement of field dry density by a nuclear moisture/density guage used in accordance with agreed procedure and the guage is calibrated to provide results identical to that obtained from tests in accordance with IS: 2720 (Part 28). A record of the same shall be maintained by the Contractor.

When density measurements reveal any soft areas in the embankments / subgrade / earthen shoulders, further compaction shall be carried out as directed by the Engineer. If inspite of that the specified compaction is not achieved, the material in the soft areas shall be removed and replaced by approved material, compacted using appropriate mechanical means such as light weight vibratory roller,

double drum walk behind roller, vibratory plate compactor, trench compactor or vibratory tamper to the density requirements and satisfaction of the Engineer.

305.3.7 Drainage

The surface of the embankment/subgrade at all times during construction shall be maintained at such a cross fall (not flatter than that required for effective drainage of an earthen surface) as will shed water and prevent ponding.

305.3.8 Repairing of damages caused by rain/spillage of water :

The soil in the affected portion shall be removed in such areas as directed by the Engineer before next layer is laid and refilled in layers and compacted using appropriate mechanical means such as small vibratory roller, plate compactor or power rammer to achieve the required density in accordance with Clause 305.3.6. If the cut is not sufficiently wide for use of required mechanical means for compaction, the same shall be widened suitably to permit their use for proper compaction. Tests shall be carried out as directed by the Engineer to ascertain the density requirements of the repaired area. The work of repairing the damages including widening of the cut, if any, shall be carried out by the Contractor at his own cost, including the arranging of machinery/equipment for the purpose.

305.3.9 Finishing operations:

Finishing operations shall include the work of shaping and dressing the shoulders/verge/ roadbed and side slopes to conform to the alignment, levels, cross sections and dimensions shown on the drawings or as directed by the Engineer subject to the surface tolerance described in Clause 902. Both the upper and lower ends of the side slopes shall be rounded off to improve appearance and to merge the embankment with the adjacent terrain.

The topsoil, removed and conserved earlier (Clause 301.3.2 and 305.3.3) shall be spread over the fill slopes as per directions of the Engineer to facilitate the growth of vegetation. Slopes shall be roughened and moisture slightly prior to the application of the topsoil in order to provide satisfactory bond. The depth of the top soil shall be sufficient to sustain plant growth, the usual thickness being from 75 mm to 150 mm.

Where directed, the slopes shall be turfed with sods in accordance with Clause 307. If seeding and mulching of slopes is prescribed, this shall be done to the requirement of Clause 308.

When earthwork operations have been substantially completed, the road area shall be cleared of all debris, and ugly scars in the construction area responsible for objectionable appearance eliminated.

305.4 Construction of Embankment and subgrade under special conditions.

305.4.1 Earthwork for widening existing road embankment :

When an existing embankment and/or subgrade is to be widened and its slopes are steeper than 1 vertical on 4 horizontal, continuous horizontal benches, each at least 300 mm wide, shall be cut into the old slope for ensuring adequate bond with the fresh embankment/subgrade material to be added. The material obtained from cutting of benches could be utilized in the widening of the embankment/subgrade. However when the existing slope against which the fresh material is to be placed is flatter than 1 vertical on 4 horizontal, the slope surface may only be ploughed or scarified instead of resorting to benching.

Where the width of the widened portions is insufficient to permit the use of conventional rollers, compaction shall be carried out with the help of small vibratory rollers/plate compactors/power rammers or any other appropriate equipment approved by the Engineer. End dumping of material from trucks for widening operations shall be avoided except in difficult circumstances when the extra width is too narrow to permit the movement of any other types of hauling equipment.

305.4.2 Earthwork for embankment and subgrade to be placed against sloping ground

Where an embankment /subgrade is to be placed against sloping ground, the latter shall be appropriately benched or ploughed/scarified as required in Clause 305.4.1 before placing the embankment/subgrade material. Extra earthwork involved in benching or due to ploughing/scarifying etc. shall be considered incidental to the work.

For wet conditions, benches with slightly inward fall and subsoil drains at the lowest point shall be provided as per the drawings, before the fill is placed against sloping

Where the contract requires construction of transverse subsurface drain at the cut-fill interface, work on the same shall be carried out to Clause 309 in proper sequence with the embankment and subgrade work as approved by the Engineer.

305.4.3 Earthwork over existing road surface:-

Where the embankment is to be placed over an existing road surface, the work shall be carried out as indicated below:-

(i) If the existing road surface is of granular or bituminous type and lies within 1 m of the new formation levels, it shall be scarified to a depth of 50mm or as directed so as to provide ample bond between the old and new material ensuring that at least 500 mm portion below the top of new subgrade level is compacted to the desired density.

(ii) If the existing road surface is of bituminous type or cement concrete type and lies within 1 m of the new formation level, the bituminous or cement concrete layer shall be removed completely.

(iii) If the level difference between the existing road surface and the new formation level is more than 1 m. the existing surface shall be roughened after ensuring that the minimum thickness of 500mm of subgrade is available.

305.4.4 Embankment and subgrade around structures :-

To avoid interference with the construction of abutments, wing walls or return walls of culvert/bridge structures, the Contractor shall, at points to be determined by the Engineer suspend work on embankment forming approaches to such structures, until such time as the construction of the latter is sufficiently advanced to permit the completion of approaches without the risk of damage to the structure.

Unless directed otherwise, the filling around culverts, bridges and other structures upto a distance of twice the height of the road from the back of the abutment shall be carried out independent of the work on the main embankment. The fill material shall not be placed against any abutment or wing wall, unless permission has been given by the Engineer but in any case not until the concrete or masonry has been in position for 14 days. The embankment and subgrade shall be brought up simultaneously in equal layers on each side of the structure to avoid displacement and unequal pressure. The sequence of work in this regard shall be got approved from the Engineer.

The material used for backfill shall not be an organic soil or highly plastic clay having plasticity index and liquid limit more than 20 and 40 respectively when tested according to IS: 2720 (Part 5). Filling behind abutments and wing walls for all structures shall conform to the general guidelines given in IRC: 78. The fill material shall be deposited in horizontal layers in loose thickness and compacted thoroughly to the requirements of

Where the provision of any filter medium is specified behind the abutment, the same shall be laid in layers simultaneously with the laying of fill material. The material used for filter shall conform to the requirements for filter medium spelt out in Clause 2504 unless otherwise specified in the Contract.

Where it may be impracticable to use conventional rollers, the compaction shall be carried out by appropriate mechanical means such as small vibratory roller, plate compactor or power rammer. Care shall be taken to see that the compaction equipment does not hit or come too close to any structural member so as to cause any damage to them or excessive pressure against the structure.

305.4.5 Construction of embankment over ground incapable of supporting construction equipment.

Where embankment is to be constructed across ground which will not support the weight of repeated heavy loads of construction equipment, the first layer of the fill may be constructed by placing successive loads of material in a uniformly distributed layer of a minimum thickness required to support the construction equipment as permitted by the Engineer. The Contractor, if so desired by him, may also use suitable geosynthetic material to increase the bearing capacity of the foundation. This exception to normal procedure will not be permitted where, in the opinion of the Engineer, the embankments could be constructed in the approved manner over such ground by the use of lighter or modified equipment after proper ditching and drainage have been provided. Where this exception is permitted, the selection of the material and the construction procedure to obtain an acceptable layer shall be the responsibility of the Contractor. The cost of providing suitable traffic conditions for construction equipment over any area of the Contract, will be the responsibility of the Contractor and no extra payment will be made to him. The remainder of the embankment shall be constructed as specified in Clause 305.3.

305.4.6 Embankment construction under water and Water logged areas

305.4.6.1 Embankment construction under water

Where filling or backfilling is to be placed under water, only acceptable granular material or rock shall be used unless otherwise approved by the Engineer. Acceptable granular material shall be of GW, SW, GP, SP as per IS:1498 and consist of graded, hard durable particles with maximum particle size not exceeding 75mm. The material should be non-plastic having uniformity coefficient of not less than 10. The material placed in open water shall be deposited by end tipping without compaction.

305.4.6.2 Embankment construction in waterlogged and Marshy Areas :

The work shall be done as per IRC:34.

305.4.7 Earthwork for high embankment :-

The material for high embankment construction shall conform to Clause 302.2.1.7. In the case of high embankments (more than 6 m), the Contractor shall normally use fly ash in conformity with Clause 305.2.1.1 or the material from the approved borrow area.

Where provided, stage construction of embankment and controlled rates of filling shall be carried out in accordance with the Contract including installation of instruments and its monitoring.

Where required, the contractor shall surcharge embankments or other areas of fill with approved material for the periods specified in the Contract. If settlement of surcharged fill results in any surcharging fill results the Contractor shall bring the resultant level upto formation level with acceptable materials for use in fill.

305.4.8 Settlement period

Where settlement period is specified in the Contract, the embankment shall remain in place for the required settlement period before excavating for abutment, wing wall, retaining wall, footings, etc. or driving foundation piles. The duration of the required settlement period at each location shall be as provided for in the contract or as directed by the Engineer.

305.5 Plying of Traffic

Construction and other vehicular traffic shall not use the prepared surface of the embankment and/or subgrade without the prior permission of the Engineer. Any damage arising out of such use shall, however be made good by the Contractor at his own expense as directed by the Engineer.

305.6 Surface Finish and Quality Control of Work

The surface finish of construction of subgrade shall conform to the requirements of Clause 902. Control on the quality of materials and works shall be exercised in accordance with Clause 903.

305.7 Subgrade Strength

It shall be ensured prior to actual execution that the borrow area material to be used in the subgrade satisfies the requirements of design CBR.

Subgrade shall be compacted and finished to the design strength consistent with other physical requirements. The actual laboratory CBR values of constructed subgrade shall be determined on remoulded samples, compacted to the field density at the field moisture content and tested for soaked / unsoaked condition as specified in the contract.

305.8 Measurements for Payment

305.8.1 Earth embankment/subgrade construction shall be measured separately by taking cross sections at intervals given in Sub-section 113.3 after completion of clearing and grubbing and after completion of embankment / sub-grade. The volume of earthwork in cubic metres by the method of average end areas.

305.8.2 The measurement of fill material from borrow areas shall be the difference between the net quantities of compacted fill and the net quantities of suitable material brought from roadway and drainage excavation. For this purpose, it shall be assumed that one cum. of suitable material brought to site from road and drainage excavation forms one cu.m. of compacted fill and all bulking or shrinkage shall be ignored.

305.8.3 The embankment constructed with fly ash will be measured in cum, separately for the fly ash portions and for the soil cover and intervening layers of soil, unless otherwise specified in the contract.

- 305.8.4** Construction of embankment under water shall be measured in cu.m.
- 305.8.5** Construction of high embankment with specified material and in specified manner shall be measured in cu.m.
- 305.8.6** Stripping including storing and reapplication of topsoil shall be measured in cu.m.
- 305.8.7** Work involving loosening and recompacting of ground supporting embankment / subgrade shall be measured in cu.m.
- 305.8.8** Removal of unsuitable material at embankment/subgrade foundation and replacement with suitable material shall be measured in Cu.m.
- 305.8.9** Scarifying existing granular/bituminous road surface shall be measured in Square metres.
- 305.8.10** Dismantling and removal of existing cement concrete pavement shall be measured vide Clause 202.6.
- 305.8.11** Filter medium and backfill material behind abutments, wing walls and other retaining structures shall be measured as finished work in position in cu.m.

305.9 RATES:

The Contract unit rates for the items of embankment and subgrade construction shall be payment in full for carrying out the required operations including full compensation for :

- (i) Cost of arrangement of land as a source of supply of material of required quantity for construction unless provided other wise in the contract.
- (ii) Setting out;
- (iii) Compacting ground supporting embankment/subgrade except where removal and replacement of unsuitable material or loosening and recompacting is involved;
- (iv) Scarifying or cutting continuous horizontal benches 300mm wide on side slopes of existing embankment and subgrade as applicable;
- (v) Cost of watering or drying of material in borrow areas and/or embankment and subgrade during construction as required;
- (vi) Spreading in layers, bringing to appropriate moisture content and compacting to specification requirements;
- (vii) Shaping and dressing top and slopes of the embankment and subgrade including rounding of corners;
- (viii) Restricted working at sites of structures;
- (ix) Working on narrow width of embankment and subgrade,
Excavation in all soils from borrow pits/designated borrow areas including clearing and grubbing and transporting the material to embankment and subgrade site with all lifts and leads unless otherwise provided for in the contractor.
- (x) All labour, material, tools, equipment and incidentals necessary to complete the work to the Specifications;
- (xi) Dewatering, and
- (xii) Keeping the embankment/completed formation free of water as per Clause 311.
- (xiii) Transporting unsuitable excavated material for disposal with all leads and lifts.

- 305.9.2** Clause 301.9.5 shall apply as regards Contract unit rates for items of stripping and storing top soil and of reapplication of topsoil.

- 305.9.3** Clause 301.9.2 shall apply as regards Contract unit rate for the item of loosening and recompacting the embankment / subgrade foundation.
- 305.9.4** Clauses 309.1.1 and 305.8 shall apply as regards Contract rates for items of removal of unsuitable material and replacement with suitable material respectively.
- 305.9.5** The Contract unit rate for scarifying existing granular/bituminous road surface shall be payment in full for carrying out the required operations including full compensation for all labour, materials, tools, equipment and incidentals, necessary to complete the work. This will also comprise of handling, giving credit towards salvage value and disposal of the dismantled materials with all leads and lifts or as otherwise specified.
- 305.9.6** Clause 202.7 shall apply as regards Contract unit rate for dismantling and removal of existing cement concrete pavement.
- 305.9.7** The Contract unit rate for providing and laying filter material behind abutments shall be payment in full for carrying out the required operations including all materials, labour, tools, equipment and incidentals to complete the work to Specifications.
- 305.9.8** The Contract unit rate for providing and compacting backfill material behind abutments and retaining walls shall be payment in full for carrying out the required operations including all materials, labour, tools, equipment and incidentals to complete the work to Specifications.
- 305.9.9** Clause 305.4.6 shall apply as regards Contract unit rate for construction of embankment under water.
- 305.9.10** Clause 305.4.7 shall apply as regards Contract unit rate for construction of high embankment. It shall include cost of instrumentation, its monitoring and settlement period, where specified in the Contract or directed by the Engineer.

In case the Contract unit rate specified is not inclusive of all leads, the unit rate for transporting material beyond the initial lead, as specified in the contract for construction of embankment and subgrade shall be inclusive of full compensation for all labour, equipment, tools and incidentals necessary on account of the additional haul or transportation involved beyond the specified initial lead.

Measurement shall be taken and paid in Cu.m.

Item No 12.

Rolling and watering of earth work in layers with power roller including filling in depression which occur during the process

1. For spreading materials in layers and bringing the appropriate moisture content, the embankment materials shall be spread uniformly over the entire width of the embankment in layers not exceeding 250mm in loose thickness. Successive layers of embankment shall not be placed until the layer under construction has been thoroughly compacted to the requirements set down here under :-

Moisture content of the materials shall be checked at the source of supply and if found less than that specified for compaction, the same, shall be made good either at the source or after spreading the soil in loose thickness for compaction. In the latter case, water shall be sprinkled directly from a hoseline or from a truck mounted water tank, and flooding shall not be permitted under any circumstances.

If the materials delivered to the road bed is too wet it shall be dried, by evaporation and exposure to the sun. till the moisture content is brought done to acceptable standard for compaction Should circumstances arise. Where owing to wet weather, the moisture content cannot be reduced to the required level by the above procedure, work of compaction shall be suspended.

Moisture content of each layer of soil shall be checked in accordance with IST 2720 (Part-II) and unless otherwise mentioned shall be so adjusted, making due allowance for evaporation losses, that at the time of the compaction it is in the range of 1 percent to 2 percent below the optimum moisture content determined in accordance with ISI (Part-VII). Highly expansive clays shall however be compacted at 2 to 4 percent above the optimum moisture content

After adding the required amount of water, the soil shall be processed by means of harrows, rotary mixers or as otherwise approved until the layer is uniformly wet. Clods or hard lumps of earth shall be broken to have maximum size of 150mm when being placed in the lower layers of the embankment and a maximum size of 60mm when being placed in the top 0.5 meter portion of the embankment below the subgrade.

Hauling equipment shall be dispersed uniformly over entire surface of the previously constructed layer to minimize cutting of uneven compaction Where the embankment is to be constructed on low area ground that will not support the weight of trucks of other hauling equipment, the lower part of the fill should be constructed by dumping successive loads in a uniformly distributed layers of a thickness not greater than that necessary to support the hauling equipment while placing subsequent layers.

2. COMPACTION :

Only compacting equipment approved by the Engineer-in-charge shall be employed to compact the materials. The contractor shall demonstrate the efficiency of the plants he intends to use for carrying out compaction trials.

Each layer of the materials shall be thoroughly compacted to the densities specified in Table 1.2 Table.

1.2 Compaction requirements for embankment.

Sr.No.	Type of Work/materials	Field dry density as per centage of maximum laboratory dry density as per IS:2720 (Part-VII)
1.	Top 0.5 meter portion of embankment below subgrade level and shoulders.	Not less than 100.
2.	Other portion of embankment.	Not less than 95
3.	Highly expensive class	85 to 90

Subsequent layers shall be placed only after finished layer has been tested according to M.O.S.T. specification clause 902 and accepted by the Engineer-in-charge.

When density measurements reveal any soft areas in the embankment further compaction shall be carried out as directed by the Engineer-in-charge. If insite of that the specified compaction is not achieved, the materials in the soft areas shall be removed and replaced by approved materials and compacted to the density requirement to the satisfaction of the Engineer-in-charge.

3. Measurements for Payment :

Consolidation of earth embankment construction shall be measured by taking cross section at intervals in the original position before the work starts and after its completion and computing of the volume of earthwork in cubic meters by the method of average and areas. The measurement of fill material from borrow area shall be the difference between the net quantities of suitable materials brought from roadway and drainage excavation. For this purpose it shall be assumed that one cubic meter of suitable materials brought to site from roadway and drainage excavation from one cubic meter of compacted fill and all bulking or shrinkage shall be ignored Stripping including storing and reapplication of top soil shall be measured as volume in **cubic meter**.

- 4.** The contract unit rate includes cost of mechanical roller required for consolidation including ail labour, equipments fuel, hire charges, tolls, and incidentals necessary.

Item No 13.

Earthwork in cutting including preparing the slope and camber and stacking or utilising the cutting stuff in bank as directed upto 200 meters from the end of cutting with all lead and lift (III) Hard rock

304.1 Scope

Excavation for structures shall consist of the removal of material for the construction of other similar structures, in accordance with the requirements of these Specifications and the lines and dimensions shown on the drawings or as indicated by the Engineer. The work shall include construction of the necessary cofferdams and cribs and their subsequent removal; all necessary sheeting, shoring, bracing, draining and pumping; the removal of all logs, stumps, grubs and other deleterious matter and obstruction, necessary for placing the foundations; trimming bottoms of excavations; backfilling and clearing up the site and the disposal of all surplus material.

304.2 Classification of Excavation

301.2.1. Classification : All materials involved in excavation shall be classified by the Engineer in the following manner:

(a) Soil

This shall comprise topsoil, turf, sand, silt, loam, clay, mud, peat, black cotton soil, soft shale or loose murrum, a mixture of these and similar material which yields 10 the ordinary application of pick, spade and/or shovel, rake or other ordinary digging equipment. Removal of gravel or any other modular material having dimension in any one direction not exceeding 75 mm shall be deemed to be covered under this category.

(b) Ordinary Rock (not requiring blasting) this shall include:

- (i) Rock types such as laterites, shales and conglomerates, varieties of limestone and sandstone etc., which may be quarried or split with crow bars, also including any rock which in dry state may be hard, requiring blasting but which, when wet, becomes soft and manageable by means other than blasting;
- (ii) macadam surfaces such as water bound and bitumen bound; soling of roads, cement concrete pavement, coddle stone etc. compacted murrum or stabilized soil requiring use of pick axe or shovel or both.
- (iii) lime concrete, stone masonry and brick work in lime/cement mortar below ground level, reinforced cement concrete which may be broken up with crow bars or picks and stone masonry in cement mortar below ground level; and
- (iv) boulders which do not require blasting found lying loose on the surface or embedded in river bed, soil, talus, slope wash and terrace material of dissimilar origin.

(c) Hard Rock (requiring blasting)

This shall comprise:

- (i) Any rock or cement concrete for the excavation of which the use of mechanical plant and/or blasting is required;
- (ii) Reinforced cement concrete below ground level and in bridge / ROB / RUB / fly over piers and abutments,
- (iii) boulders requiring blasting.

(d) Hard Rock (using controlled blasting)

Hard rock requiring blasting as described under (c) but where controlled blasting is to be carried out in locations where built-up area, huts and are situated at within 200m of the blast site.

(e) Hard Rock (blasting prohibited)

Hard rock requiring blasting as described under (c) but where blasting is prohibited for any reason like people living within 20m of blast sites etc. and excavation has to be carried out by chiselling, wedging or any other agreed method.

(f) Marshy Soil

This shall include soils like soft clays and peats excavated below the original ground level of marshes and swamps and soils excavated from other areas requiring continuous pumping or bailing out of water.

304.3 Construction Operations

304.3.1 Setting Out

After the site has been cleared according to Clause 201, the limits of excavation shall be set out true to lines, curves and slopes, curves, slopes, grades and sections as shown on the drawings or as directed by the Engineer. The Contractor shall provide all labour, survey instruments and materials such as strings, pegs, nails, bamboos, stones, lime, mortar, concrete etc. required in connection with the setting out of works and the establishment of bench marks. The Contractor shall be responsible for the maintenance of bench marks and other marks and stakes as long as in the opinion of the Engineer, they are required for the work.

304.3.2 Excavation

Excavation shall be taken to the width of the lowest step of the footing including additional width as required for construction operation. The sides shall be left plumb where the nature of soil allows it. Where the nature of soil or the depth of the trench and season of the year do not permit vertical sides, the Contractor at his own cost shall put up necessary shoring; strutting and planking or cut slopes to a safer angle or both with due regard to the safety of personnel and works and to the satisfaction of the Engineer.

The depth to which the excavation is to be carried out shall be as shown on the drawings, unless the type of material encountered is such as to require changes, in which case the depth shall be as ordered by the Engineer. Propping shall be undertaken when any foundation or stressed zone from an adjoining structure is within a line of 1 vertical to 2 horizontal from the bottom of the excavation.

Where blasting is to be resorted to, the same shall be carried out in accordance with Clause 302 and all precautions indicated therein observed. Where blasting is likely to endanger adjoining foundations or other structures, necessary precautions such as controlled blasting, providing rubber mat cover to prevent flying of debris etc. shall be taken to prevent any damage.

304.3.3 Dewatering and Protection

Normally, open foundations shall be laid dry. Where water is met with in excavation due to stream flow, seepage, springs, rain or other reasons, the Contractor shall take adequate measures such as bailing, pumping, constructing diversion channels, drainage channels, bunds, depression of water level by well-point system, cofferdams and other necessary works to keep the foundation trenches dry when so required and to protect the green concrete/ masonry against damage by erosion or sudden rising of water level. The methods to be adopted in this regard and other details thereof shall be left to the choice of the Contractor but subject to the approval of the Engineer. Approval of the Engineer shall, however, not relieve the Contractor of the responsibility for the adequacy of dewatering and protection arrangements for the quality and safety of the

works.

Where cofferdams are required, these shall be carried to adequate depths and heights, be safely designed and constructed and be made as watertight as is necessary for facilitating construction to be carried out inside them. The interior dimensions of the cofferdams shall be such as to give sufficient clearance for the construction and inspection and to permit installation of pumping equipment's etc. inside the enclosed area.

If it is determined beforehand that the foundations cannot be laid dry or the situation is found that the percolation is too heavy for keeping the foundation dry, the foundation concrete shall be laid under water by tremie pipe only. In case of flowing water or artesian springs, the flow shall be stopped or reduced as far as possible at the time of placing the concrete.

Pumping from the interior of any foundation enclosure shall be done in such a manner as to preclude the possibility of the movement of water through any fresh concrete. No pumping shall be permitted during the placing of concrete and for a period of at least 24 hours thereafter, unless it is done from a suitable sump separated from the concrete work by a watertight wall or other similar means.

At the discretion of the Contractor, cement grouting or other approved methods may be used to prevent or reduce seepage and to protect the excavation area.

The Contractor shall take all precautions in diverting channels and in discharging the drained water as not to cause damage to the works, crops or any other property.

304.3.4 Preparation of Foundation

The bottom of the foundation shall be levelled both longitudinally and transversely or stepped as directed by the Engineer. Before footing is laid, the surface shall be slightly watered and rammed. In the event of excavation having been made deeper than that shown on the drawings or as otherwise ordered by the Engineer, the extra depth shall be made up with concrete as per Clause 2104.1 at the cost of the Contractor. Ordinary filling shall not be permitted to bring the foundation to the design level as shown in the drawing.

When rock or other hard strata is encountered, it shall be freed of all soft and loose material, cleaned and cut to a firm surface either level or stepped as directed by the Engineer. All seams shall be cleaned out and filled with cement mortar or grout to the satisfaction of the Engineer. In the case of excavation in rock, annular space around footing shall be filled with lean concrete M 15 up to the top level of rock.

If the depth of fill required is more than 1.5 m in soft rock or 0.6 m in hard rock above the foundation level, the filling up to this level shall be done with M-15 concrete and portion above shall be filled by concrete or by boulders grouted with cement.

When foundation piles are used, the excavation for pile cap shall be done after driving/casting of all piles forming the group. After pile driving operations in a given pit are completed, all loose and displaced materials therein shall be removed to the level of the bottom of the pile cap.

304.3.5 Slips and Slip-Outs

If there are any slips or slip-outs in the excavation, these shall be removed by the Contractor at his own cost.

304.3.6 Public Safety

Near towns, villages and all frequented places, trenches and foundation pits shall be securely fenced, provided with proper caution signs and marked with red lights at night to avoid accidents. The Contractor shall take adequate protective measures to see that the excavation operations do not affect or damage adjoining structures. For safety precautions, guidance may be taken from IS:3764.

304.3.7 Backfilling

Backfilling shall be done with approved material after concrete or masonry is fully set and carried out in such a way as not to cause undue thrust on any part of the structure. All space between foundation masonry or concrete and the sides of excavation shall be refilled to the original surface in layers not exceeding 150 mm compacted thickness. The compaction shall be done with the help of suitable equipment such as trench compactor, mechanical tamper, rammer, plate vibrator etc. after necessary watering, so as to achieve the maximum dry density.

304.3.8 Disposal of Surplus Excavated Materials

All the excavated materials shall either be reused with the approval of the Engineer or disposed off with all leads and lifts as directed by Engineer in charge.

304.4 Measurements for Payment

Excavation for structures shall be measured in Cu.m for each class of material encountered, limited to the dimensions shown on the drawings or as directed by the Engineer. Excavation over increased width, cutting of slopes, production/support to the existing structures shoring, shuttering and planking shall be deemed as incidental to the main work and shall not be measured and paid separately.

304.5 Rates

- (i) setting out;
- (ii) transporting the excavated materials for use or disposal with all leads and lifts;
- (iii) construction of necessary cofferdams, cribs/sheeting, shoring and bracing and their subsequent removal;
- (iv) removal of all logs, stumps, grubs and other deleterious matter and obstructions, for placing the foundations including trimming of bottoms of excavations;
- (v) foundation sealing, dewatering including pumping when no separate provision for it is made in the Contract;
- (vi) backfilling, clearing up the site and disposal of all surplus material with all leads and lifts or as otherwise specified; and
- (vii) all labour, materials, tools, equipment, safety measures, diversion of traffic and incidentals necessary to complete the work to Specifications.

- 304.5.2** The Contract unit rate for preparation of rock foundation shall be full compensation for cutting, trimming and cleaning the foundation surface and filling/sealing of all seams with cement grout or mortar including all materials, labour and incidentals required for completing the work.

Item No 14. 15.

Excavating in situ soil and spreading available soil in the subgrade on a prepared surface, pulverising, mixing and spread soil in place with rotavator with 2 to 3 % Slaked lime + 15 to 20 % Flyash, Slaked lime having minimum 70 per cent of contents of CaO and Flyash of required properties, grading with hydraulic tractor grader and compacting with the smooth wheel road roller at OMC to achieve the desired density & CBR to form a layer of improved Sub grade as per Technical Specification clause 403.

Excavation for foundation up to 1.50 mt depth including sorting out and stacking of useful material and disposing of the excavated stuff up to 50 mt. lead (1) Loose or soft soil

The work shall be carried out in Sand, Gravel, Clay, Soft soils and Murrum including strutting and dewatering if required and disposing off the excavated stuff with all lead and lift as directed

1. Excavation for structures shall consist of the removal of material for the construction of foundations for bridges, culverts, retaining walls, headwalls, cut off walls, pipe culverts and other similar structures, in accordance with the requirements, of these specifications and the lines and dimensions shown on the drawings or as indicated by the Engineer in charge. The work shall include all necessary sheeting, shoring, bracing, draining and Pumping and the removal of all logs, stumps, shrubs, and other deleterious matter and obstruction necessary for the foundations, trimming bottoms of excavations; back filling and clearing up the site and the disposal of all surplus material.
2. After the site has been cleared the limits of excavation shall be set out true to lines, curves, slopes, grades and sections as shown on the drawings or as directed by the Engineer in charge. The contractor shall provide all labour, survey instruments and materials such as strings, pegs, nails, bamboos, stories, lime, mortar, concrete, etc. required in connection with the setting out of works and the establishment of bench mark, centre line stones and other marks and stakes as long as in the opinion of the Engineer in charge, they are required for the work.
3. Excavation shall be taken to the width of the lowest step of the footing. The contractor at his own expense shall put up necessary shoring, strutting and planking or cut slopes to a safer angle or both with due regard to the safety of persons and works and to the satisfaction of the Engineer in charge.
4. The depth to which the excavation is to be carried out shall be as shown on the drawings; unless the type of material encountered is such as to require changes, in which case the depth shall be as ordered by the Engineer in charge.
5. Where water is met with in excavation due to stream flow, seepage, springs, rain or other reasons, the contractor shall take adequate measures such as bailing, pumping, to keep the foundation trenches dry when so required and to protect the green concrete/masonry against damage by erosion or sudden rising of water level. The methods to be adopted in this regard and other details thereof shall be left to the choice of the contractor but subject to approval of the Engineer in charge. Approval of the Engineer in charge shall, however not relieve the contractor of the responsibility for the adequacy of dewatering, and production arrangements and for the quality and safety of the works.

- 6.** Pumping from the interior of any foundation enclosure shall be done in such a manner as to preclude the possibility of movement of water through any fresh concrete. No. pumping shall be permitted during the placing of concrete or for any period of at least 24 hours thereafter, unless it is done from a suitable sump separated from the concrete work by a water tight wall or other similar means.
- 7.** The bottom of the foundation shall be leveled both longitudinally and transversely or stepped as directed by the Engineer in charge. Before footing, is laid, the surface shall be slightly watered and rammed. In the event of excavation having been made deeper than that shown on the drawings or as otherwise ordered by the Engineer in charge, the extra depth shall be made up with concrete or masonry of the foundation grade at the cost of the contractor. Ordinary filling shall not be used for the purpose to bring the foundation to level. If there are any slips or blows in the excavation, these shall be removed by the contractor at his own cost.
- 8.** Near towns, villages and all frequented places, trenches and foundation pits shall be securely fenced, provided with proper caution signs and marked with red lights at night to avoid accidents. The contractor shall take adequate protective, measures to see that the excavation operations do not affect or damage adjoining structures.
- 9.** Backfilling shall be done with approved materials after concrete or masonry is fully set and carried out in such a way as not to cause undue thrust on any part of the structure. All space between foundation masonry or concrete and the sides of excavation shall be refilled to the original surface, making due allowance for settlement in 250 mm. loose layers, which shall be watered and compacted.
- 10.** All the excavated materials shall be the property of the Government. Where the excavated material is to be used in the construction of embankment, it shall be directly deposited at the required location, within all lead.
- 11.** All useful materials not intended for use in the bank, shall be stacked neatly on Government land as directed by the Engineer in charge within all lead. Unsuitable and surplus materials not intended for use shall be disposed off as directed by the Engineer in charge.
- 12.** Excavation for structures shall be measured in cubic metres for each class of materials encountered, limited to the dimensions shown on the drawing or as directed by the Engineer in charge. Excavation over increased width cutting of slopes, shoring, shuttering and planking shall be deemed as convenience for the contractor in executing the work and shall not be measured and paid for separately.
- 13.** The contract unit rate for the items of excavation for structures shall be paid in full for carrying out the required operations including :-
 1. Setting out and fixing bench marks and centre lines stones.
 2. Construction of necessary shoring and bracing and their subsequent removal.
 3. Removal of all logs, stumps, Grubs and other deleterious matter and obstructions for placing the foundations including trimming of bottoms of excavations;
 4. Foundation sealing, dewatering including pumping;
 5. Backfilling, Clearing up the site and disposal of all surplus material within all lifts and lead upto 100 metres.
 6. All labour, materials, tools equipment, safeguards and incidentals necessary to complete the work to the specification.

- 14.** Excavation shall be for ordinary soil such as vegetation or organic soil, turf, sand, silt, loam, clay, mud, black cotton soil, soft shale or soft murrum a mixture of these and similar material which yields to the ordinary application of pick and shovel, or other ordinary digging equipment. Removal of gravel or any other nodular material having diameter in any one direction not exceeding 75 mm. occurring in such strata shall be deemed to be covered under this category. The classification of excavation shall be decided by the Engineer in charge and his decision shall be final and binding on the

Unit rate for payment of this item shall be per 1-Cum. basis of complete item.

Item No 16.

Providing and filling in foundation with ordinary cement concrete M.100 mix and providing necessary vertical pin headers including form work vibrating ramming and curing complete.

**The work shall be carried out in Ordinary Cement Concrete M-100
with Necessary vertical pin headers including form work
for filling in Foundation with all lead and lift.**

1. In case of ordinary concrete, mix is not required to be designed by preliminary tests and proportions of cement, fine aggregates and coars aggregates are specified by volume as given in table below for different grades of concrete designated as ordinary M. 100, M. 150, M.200 and M.250
2. In the designation of a concrete mix, letter "M" refers to the mix and the number the specified 28 days works cube compressive strength of that mix on 100 mm cubes expressed in kg./cm²
3. The ordinary concrete mix shall generally be specified by volume. For cement which normally comes in bags and is used by weight, volume shall be worked out taking 50 kg. of cement as 0.035 cubic metre in volume. While measuring aggregate by volume, shaking, ramming or hammering shall not be done. Proportioning of sand shall be as per its dry volume. In case it is dump, allowance for "bulking" shall be made as per IS : 2386 (Part III).
4. Ingredients required for ordinary concrete containing one 50 Kg. bag of cement of different proportions of mix shall be as given in Table below.

Grade of concrete	Mix by volume	Total quantity of dry agreegates by volume per 50 Kg. Of cement, to be taken as sum of the individul volumes of fine and coarse aggregates max.	Proportion of fine aggregate to coarse aggregate	Quantity of water per 50 Kg. Of cement max.
1	2	3	4	5
(1 cubic metre = 1000 litres)				
Ordinary	Litres		General 1:2 for fine aggregate to coarse aggregate by volume but subject to a upper limit of 1:1 1/2 & a lower limit of 1:3	Litres
M.100	1 : 3 : 6	300		34
M.150	1 : 2 : 4	220		32
M.200	1 : 1 : 1 / 2 : 3	160		30
M.250	1 : 1 : 2	100		27

NOTE:- The proportions of the aggregates shall be adjusted from upper limit to lower limit progressively as the grading of the fune aggregates becomes finer & the maximum size of coarse aggregate becomes larger.

Example:- For an average grading of fine aggregate (that is Zone II of IS : 383 1963) the proportions shall be 1: 11/2, 1:2 and 1:3 for maximum size of aggregates 10 mm, 20 mm. and 40 mm. respectively (after carrying out sieve analysis).

NOTE 2 :- A mix leaner than M.100 (1:3:6) may be used for non structural parts, if provided in the contract. In such case grading of aggregates shall be by volume. Other requirements for mixing, placing & curing shall be the same.

5. Following shall be the maximum nominal size of coarse aggregate for the different items of work :-

Sr. no.	Item of construction	Maximum nominal size of coarse aggregate
i	R.C.C. well curb, R.C.C. well steining and R.C.C. Piles	40 mm.
ii	R.C.C. well steining	63 mm.
iii	Well cap or pile cap; solid type piers, abutment and wing walls, and their pier	40 mm.
iv	R.C.C. works in cross girders deck slab, wearing coars, kerb, light posts, blast walls, approach slab etc. and hollow type piers, abutments, wing walls and their pier caps,	20 mm.
v	R.C.C. bearings.	20 mm.
vi	For any other item of construction not covered by items (i) to (v)	As specified on the Drawing or as desired by the Engineer-in charge in case it is not Specified on drawing

For heavily reinforced concrete members as in the case of ribs of main beams nominal maximum size of aggregate shall usually be restricted to 5 mm. less than the minimum lateral clear distance between the main bars or 5 mm. less than the minimum cover to the reinforcement, whichever is the smaller.

6. Fine aggregate shall be clean, hard, coarse sand. It shall be free from dust and such other substances. The sand be got approved by the Engineer in charge.
7. All materials shall be stored as to prevent their deterioration or intrusion of their quality and fitness for the work. Any material which has deteriorated or has been damaged or is otherwise considered defective by the Engineer in charge shall not be used in the works.
8. Cement shall be stored above the ground level in perfectly dry and water tight sheds. Wherever bulk storage containers are used, their capacity should be sufficient to cater to the requirements at site and should be cleaned at least once every 3 to 4 months. The aggregate shall be stored in such a way as to prevent admixture of foreign materials. Different size of fine or coarse aggregate shall be stored in separate stock piles sufficiently away from the each other to prevent; intermixing the materials.
9. The water for mixing shall be potable water to satisfaction of the Engineer in charge. The quantity of water shall be just sufficient to produce a dense concrete of required workability for the job.
10. For all work concrete shall be mixed in a mechanical mixer which along with other accessories shall be kept in first class working condition and so maintained throughout

construction. Mixing shall be continued till materials are uniformly distributed and uniform colour of the entire mass is obtained and each individual particle of the coarse aggregate show complete coating of mortar containing its proportionate amount of cement. In no case shall the mixing be done for less than 2 minutes after all ingredients have been put into the mixer.

11. When hand mixing is permitted by the Engineer in charge for small jobs or for certain other reasons. It shall be done on a smooth watertight platform large enough to allow efficient turning over of the ingredients of concrete before and after adding water. Mixing platform shall be so arranged that no foreign material shall get mixed with concrete nor does the mixing water flow out. cement in required number of bags shall be placed in a uniform layer on top of the measured quantity of fine and coarse aggregate, which shall also be spread in a layer of uniform thickness on the mixing platform. Dry coarse and fine aggregate and cement shall then be mixed thoroughly by turning over to get a mixture of uniform colour. Enough water shall then be added gradually through a rose can and the mass turned over till a mix of required consistency is obtained. In hand mixing quantity of cement shall be increased by 10 per cent above that specified.
12. Mixers which have been out of use for more than 30 minutes shall be thoroughly cleaned before putting in a new batch. Unless otherwise agreed to be the Engineer in charge the first batch of concrete from the mixer shall contain only two thirds of normal quantity of coarse aggregate Mixing plant shall be thoroughly cleaned before changing from one type of cement to another.
13. The method of transporting and placing concrete shall be approved by the Engineer in charge. Concrete shall be so transported and placed that no contamination, segregation or loss of its constituent material takes places. All form work and reinforcement contained in it shall be cleaned and made free from standing water, dust, snow or ice immediately before placing of concrete. No concrete shall be placed in any part of the structure until the approval of the Engineer in charge has been obtained.
14. If concreting is not started within 24 hours of the approval being given, it shall have to be obtained again from the Engineer in charge. Concreting being given, it shall proceed continuously over the area between construction joints. Fresh concrete shall not be placed against concrete which has been in position for more than 30 minutes unless a proper construction joint is formed. Concrete shall be compacted in its final position within 30 minutes of its discharge from the mixer unless carried in properly design agitators, operating continuously, when this time shall be within 2 hours of the addition of cement to the mix and within 30 minutes of its discharge from the agitator. Except where otherwise agreed to be the Engineer in charge, concrete shall be deposited in horizontal layers to a compacted depth of not more than 0.45 metre when internal vibrators are used and not exceeding 0.30 more in all other cases.
15. Unless otherwise agreed to by the Engineer in charge concrete shall not be dropped into place from a height exceeding 2 metres. When trunking or chutes are used they shall be kept clean and used in such a way as to avoid segregation. When concreting has to be resumed on a surface which has hardened, it shall be roughened, swept, clean, thoroughly wetted and covered with a 13 mm thick layer of mortar composed of cement and sand in the same ratio as in the concrete, mix itself. This 13 mm. layer of mortar shall be freshly mixed and placed immediately before placing of new concrete. Where concrete has not fully hardened, all laitance shall be removed by scrubbing the well surface with wire or bristle brushes, care being taken to avoid dislodgement of any particles of coarse aggregate. The surface shall then be thoroughly wetted, all free water removed and then

coated with neat cement grout. The first layer of concrete to be placed on this surface shall not exceed 150 mm. in thickness, and shall be well rammed against old work particular attention being given to corners and close Spots.

- 16.** All concrete shall be compacted to produce a dense homogeneous mass with the assistance of vibratorys, unless otherwise permitted by the Engineer in charge for exceptional cases; such is concreting under water, where vibratorys can not be used. Sufficient vibratorys in seviceable condition shall be kept at site so that spare equipment is always available in the event of break downs.
- 17.** Immediately after compaction, concrete shall be protected against harmful effects of weather, including rain, running water, shocks, vibration, traffic, rapid temperature changes, frost and driving out process. It shall be covered with wet sacking, hessian or other similar absorbent; material approved by the Engineer in charge soon after the initial set, and shall be kept continuously wet for a period of not less than 14 days from the date of placement. Masonary work over the foundation concrete may be started after 48 hours of its laying but the curing of concrete shall be, continued for a minimum period of 14 days.
- 18.** From work shall include all temporary or permanent forms required for forming the concrete, together with all temporary construction required for their support. Form work shall however he divided into following two distinct categories :
 1. Shuttering i.e., form work required for forming the concrete.
 2. Scaffolding i.e., form work required for supporting shuttering.

Forms for shuttering shall be constructed only in metal suitably lined. Forms for scaffolding be constructed of metal or timber. Both shuttering and scaffolding shall be or substantial rigid construction and shuttering shall be true to shape and dimensions shown on the drawings. All bolts and rivets shall be counter sunk and well ground to provide a smooth, plane surface.

- 19.** Forms shall be mortar tight and shall be made sufficiently rigid by the use of ties and bracings to prevent any displacement or sagging between supports. They shall be strong enough to withstand all pressure, ramming and vibration, without deflection from the prescribe lines occurring during and after placing the concrete. Screw jacks or hard wood wedges where required shall be provided to make up any settlement in the formwork either before or during the placing of concrete, Suitable comber shall be provided in horizontal members of structure, specially in long spans to counteract the effects of any fixed as to provide for such camber. Forms shall be so constructed as to be removable in sections in the desired sequence, without damaging the surface of concrete or disturbing other sections. Unless otherwise specified or directed, chambers or fillets of sizes 25 mm x 25 mm shall be provided at all angles of formwork to avoid sharp corners.
- 20.** The inside surfaces of shuttering shall, except in the case of permanent form work or where otherwise agreed to by the Engineer in charge, be coated with an approved material to prevent adhesion of concrete to the form work. Release agents shall be applied strictly in accordance with the manufacturer's instructions and shall not be allowed to come into contact with any reinforcement or prestressing tendons and anchorages. Different release agents shall not be used in form work for concrete which will be visible in the finished works.

- 21.** Special measures shall be taken to ensure that the form work does not hinder the shrinkage of concrete because without these cracking could occur before the form work is removed. Where ever applicable arrangements must be made to ensure that the form work does not restrain the shortening and hogging of the beams or slabs during tensioning of the tendons, The form work should take due account of the calculated amount of positive or negative camber so as to ensure the correct final shape the structures having regard to the deformation of a false work, scaffolding or propping and the instantaneous or deferred deformation due to various causes affecting prestressed structures. Where there a reentrant angles in the concrete sections the form work should be removed at those sections as soon as possible after the concrete has set in order to avoid cracking due to shrinkage of concrete. Formwork shall be tight enough to prevent any appreciable loss of cement during vibrations, suitable tolerances should be provided in the harmwork. Immediately 'before concreting all forms shall be thoroughly cleaned. Contractor shall give the Engineer in charge due notice before palcing any concrete in the forms to permit him to inspect and accept the false work and forms as to their strength aligement and general fitness, but such inspection shall not relieve the contractor of his responsibility for safety of men, machinery, materials and for results obtained.
- 22.** The Engineer in charge shall be informed in advance be the contractor of his intention to strike any formwork While fixing the time for removal of formwork, due consideration shall he given to local conditions, character of the structure, the weather and other conditions that influence the setting of concrete and of the materials used in the mix. Where field operations are controlled by strength tests of concrete, the removal of the load supporting or soffit forms may commence when concrete has attained strength equal to atleast twice the stress to which the concrete will be subjected at the time of striking props including the effect of any further addition of loads. When field operations are not controlled by strenght tests of concrete the vertical forms of beams, columns and walls may be removed after 2 days. The props of slabs and beams may be removed after 14 and 21 days respectively. All formwork shall be removed without causing any damage to the concrete. Centering shall be gradually and uniformly lowered in such a manner as to permit the concrete to take stresses due to its own weight uniformly and gradually. Where internal metal ties are permitted, they or their removable parts shall be extracted without causing any damage to the concrete and remaining holes filled with mortar. No permanently embeded metal part shall have less than 25 mm. cover to the finished concrete surface. Where it is intended to refuse the formwork, it shall be cleaned and made good to the saitisfaction of the Engineer in charge
- 23.** Immediately after the removal of forms, all exposed bars or bolts passing through the Cement concrete member and used for shuttering or any other purpose shall be cut inside the cement concrete member to a depth of atleast 25 mm. below the surface of the concrete and the resulting holes be filled by cement mortar. All fins caused by form joints, all cavities produced by the removal of form ties and all other holes and depresssions, honecomb spots, broken edges or corners and other defects, shall be thoroughly cleaned, saturated with water and carefully pointed and rendered true with mortar of cement and fine aggregate mixed in the proportions used in the grade of concrete that is being finished and of as dry as consistency as is possible to use. Considerable pressure shall be applied in filling and pointing to ensure thorough filling in all voids. Surfaces which have been pointed shall be kept moist for a period of twenty four hours. If rock pockets / honeycombs, in the opinion of the Engineer in charge are of such an extent or character as to affect the strenght of the structure materially or to endanger the life of the steel

reinforcement, he may declare the concrete defective and require the removal and replacement of the portions of the structure affected.

- 24.** In the case of reinforced concrete work workability shall be such that the concrete surrounds and properly grips all reinforcement. The degree of consistency, which shall depend upon the nature of work and methods of vibration of concrete shall be determined by regular slump tests. Following slump shall be adopted for different types of works.

Type of work	Slumps	
	Where vibratorys are used	Where vibratorys are not used
i) Mass concrete in R.C.C. roundations, footings and retaining walls	10mm to 25mm	80mm
ii) Beams, slabs and columns simply reinforced.	25mm to 40mm	100mm to 120mm
iii) Thin R.C.C. section or section with congested steel	40mm to 50 mm	125mm to 150 mm

- 25.** Works strength tests shall be made in accordance with IS : 516. Each test shall be conducted on ten specimens, five of which shall be tested at seven days and the remaining five at 28 days. The samples of concrete shall be taken on each day of concreting and cubes shall be made at the rate of one for every 5 cubic metre of concrete or a part thereof. However, if concreting done in & day is less than 15 cubic metre, the minimum number of cubes can be reduced to 6 with the specific permission of the Engineer in charge. Similar works tests shall be carried out whenever the quality and grading of materials is charged irrespective of the quantity of concrete proud. The number of specimens may be suitably increased as deemed necessary by the Engineer in charge when procedure of tests given above reveal a poor quality of concrete and in other special cases.
- 26.** The average strength of the group of cubes cast for each day shall not be less than the specified works cube strength. 20 per cent of the cubes cast for each day may have values less than the specified strength, provided the lowest value is not less than 85 per cent of the specifies strength.
- 27.** R.C.C. work shall have exposed concrete surface. Centering design and its erection shall approved by he Engineer in charge. One carpentre with helper will invariably be kept present throughout the period of concreting. Movement of labour and other persons shall be totally prohibited over reinforcement laid in position. For access to different parts, suitable mobile platforms shall provided so steel reinforcement in position is not disturbed. For ensuring proper cover, motar blocks of suitable size shall be cast and tied to the reinforcement. Timber, kapachi or matal pieces shall not be used for this purpose. Concreting of important structural members shall always be done in the presence and under the supervision of departmental person not below the rank of Astt. Engineer /Addi. Astt. Engineer Overseer or as instructed by the Engineer in charge. After removal of form work checks that concrete produced is of good quality. Plastering shall not be allowed to the expressed faces of concrete.
- 28.** In reinforced concrete the volume occupied by reinforcement shall not be deducted. The slab shall be measured as running continuously through and the beam as the portion below the slab.

- 29.** All necessary labour materials, equipment, etc., for sampling, preparing test cubes, curing etc., shall be provided by the Contractor. Testing of the materials and concrete may be arranged by the Engineer in charge in an approved laboratory at the cost of the contractor.
- 30.** The unit rate for concrete shall include the cost of all materials, labour tools and plan required for mixing, placing in position, vibrating and compacting finishing as per directions of the Engineer in charge curing and all other incidental expenses for producing concrete of specified strength to complete the structure or its components as show on the

Item No 17.

Providing and casting in-situ ordinary cement concrete M150 mix and providing necessary pin headers including shuttering, scaffolding, laying, vibrating and finishing without V-grooves (A) Height from 0.0 to 5 Mt.

**This item shall be carried out as per detailed specification of
Item No. [16] below in Design Mix Concrete M-150 grade
for R.C.C. return (A) Height from 0.0 to 5 Mt. as directed including cost of shuttering,
scaffolding, laying, vibrating, curing and finishing as per design**

Item No 18.

Supplying and fixing reinforced concrete heavy duty non pressure pipes with collars for culverts including setting and joining the pipes in C.M. 1:2 watering and laying (to level or slope) of I.S. 458/1971 Class NP3 casted by vertically vibrated technology of following internal diameter. 900mm dia.

900mm dia.

1. This shall consist of furnishing and installing reinforced cement concrete pipe of the type diameter and length required at the location shown on the drawings or as ordered by the Engineer-in-charge.
2. Reinforced concrete pipe shall be of NP 3 type conforming to the requirements of IS : 458 and shall be of dia. as specified in the item.

Pipes shall be durable & its durability shall be achieved as a result of low water cement ratio & high compaction with the use of latest "Vertical Casting Technology" with preciously controlled socket & spigot joints & quality of pipes and its inner surface shall be smooth and strictly as per I.S. 458/1971. Each consignment of cement concrete pipes shall be inspected, if necessary and approved by the Engineer-in-charge either at the place of manufacture or at the site before their incorporation in the works.

NP4, NP3, NP2 and NP1 pipes are used for R.C.C. Pipes. Where the testing of pipes will not be feasible the contractors will have to produce a certificate from the manufacturer on company's letter head in the given hereinafter from.

Production of such certificate will not however relieve the Contractor from his responsibility of supplying pipes of required standard and will have to bear the loss or damage caused to the work on account of defects found subsequently during execution. It will also be necessary to purchase these pipes from manufacturer having standard equipments for carrying out various tests as per IS : 458 at his factory.

Form of Certificate for NP4, NP-3, NP-2, NP-1 Pipes

We _____

Manufacturer or R.C.C. Pipes produce R.C.C. pipes as per the requirement of IS : 458 and also carry out the required test at our place, We have acquired equipments for carrying out test and are prepared to carry out tests at our factory sites. We have experience of manufacturing of pipes of years. The pipes supplied by us to M/S. _____.

Satisfy the requirement of IS:458.

Date: _____

Place: _____

3. No pipes shall be placed in position until the foundations have been approved by the Engineer-in charge.

Where two or more pipes are to be laid adjacent to each other, they shall be separated by a distance equal to at least half the diameter of the pipe subject to minimum of 900 mm.

The laying of pipes on the prepared foundation shall start from the outlet and proceed towards the inlet and be completed to the specified lines and grades. The pipes shall be fitted and matched so that when laid in works they form a culvert with a smooth uniform invert. Any pipe found defective or damaged during laying shall be removed at there cost of Contractor.

4. The pipes shall be jointed either by collar joint or by flush joint in the former case the collars shall be of R.C.C. 150 to 200 mm. wide and having the same strength as the pipes to be jointed. Caulking space shall be between 13 and 20 mm. according to the diameter of the pipes caulking material shall be slightly wet mix of cement and sand in the ratio of 1:2 rammed with caulking irons. Before caulking the collar shall be so placed that its centre coincides with that of pipes and an even annular space is left between the collar and the pipes. Flush joint may be shaped to form a self centering joint with a joining space 13 mm wide. The joining space shall be filled with cement mortar 1:2 (1 cement : 2 sand) mixed sufficiently dry to remain in position when forced with a trowel or rammer. Care shall be taken to fill all voids and excess mortar shall be removed. All joints shall be made with care so that their interior surface is smooth and consistent with the interior surface of the pipes. After finishing, the joint shall be kept covered and damp for at least four days.
5. R. C. C. pipes shall be measured along their centre between their inlet and outlet ends in linear metres.
6. The rate for the pipes shall include the cost of pipe including loading, unloading, handling, storing laying in position and joining complete.
7. The rate shall be for a unit of one **running meter**.

Item No 19.

Supplying and fixing reinforced concrete heavy duty non pressure pipes with collars for culverts including setting and joining the pipes in C.M. 1:2 watering and laying (to level or slope) of I.S. 458/1971 Class NP3 casted by vertically vibrated technology of following internal diameter.
900mm dia.

1200mm dia.

1. This shall consist of furnishing and installing reinforced cement concrete pipe of the type diameter and length required at the location shown on the drawings or as ordered by the Engineer-in-charge.
2. Reinforced concrete pipe shall be of NP 3 type conforming to the requirements of IS : 458 and shall be of dia. as specified in the item.

Pipes shall be durable & its durability shall be achieved as a result of low water cement ratio & high compaction with the use of latest "Vertical Casting Technology" with preciously controlled socket & spigot joints & quality of pipes and its inner surface shall be smooth and strictly as per I.S. 458/1971. Each consignment of cement concrete pipes shall be inspected, if necessary and approved by the Engineer-in-charge either at the place of manufacture or at the site before their incorporation in the works.

NP4, NP3, NP2 and NP1 pipes are used for R.C.C. Pipes. Where the testing of pipes will not be feasible the contractors will have to produce a certificate from the manufacturer on company's letter head in the given hereinafter from.

Production of such certificate will not however relieve the Contractor from his responsibility of supplying pipes of required standard and will have to bear the loss or damage caused to the work on account of defects found subsequently during execution. It will also be necessary to purchase these pipes from manufacturer having standard equipments for carrying out various tests as per IS : 458 at his factory.

Form of Certificate for NP4, NP-3, NP-2, NP-1 Pipes

We _____

Manufacturer or R.C.C. Pipes produce R.C.C. pipes as per the requirement of IS : 458 and also carry out the required test at our place, We have acquired equipments for carrying out test and are prepared to carry out tests at our factory sites. We have experience of manufacturing of pipes of years. The pipes supplied by us to M/S. _____.

Satisfy the requirement of IS:458.

Date: _____

Place: _____

3. No pipes shall be placed in position until the foundations have been approved by the Engineer-in charge.

Where two or more pipes are to be laid adjacent to each other, they shall be separated by a distance equal to at least half the diameter of the pipe subject to minimum of 1200 mm.

The laying of pipes on the prepared foundation shall start from the outlet and proceed towards the inlet and be completed to the specified lines and grades. The pipes shall be fitted and matched so that when laid in works they form a culvert with a smooth uniform invert. Any pipe found defective or damaged during laying shall be removed at there cost of Contractor.

4. The pipes shall be jointed either by collar joint or by flush joint in the former case the collars shall be of R.C.C. 150 to 200 mm. wide and having the same strength as the pipes to be jointed. Caulking space shall be between 13 and 20 mm. according to the diameter of the pipes caulking material shall be slightly wet mix of cement and sand in the ratio of 1:2 rammed with caulking irons. Before caulking the collar shall be so placed that its centre coincides with that of pipes and an even annular space is left between the collar and the pipes. Flush joint may be shaped to form a self centering joint with a joining space 13 mm wide. The joining space shall be filled with cement mortar 1:2 (1 cement : 2 sand) mixed sufficiently dry to remain in position when forced with a trowel or rammer. Care shall be taken to fill all voids and excess mortar shall be removed. All joints shall be made with care so that their interior surface is smooth and consistent with the interior surface of the pipes. After finishing, the joint shall be kept covered and damp for at least four days.
5. R. C. C. pipes shall be measured along their centre between their inlet and outlet ends in linear metres.
6. The rate for the pipes shall include the cost of pipe including loading, unloading, handling, storing laying in position and joining complete.
7. The rate shall be for a unit of one **running meter**.

Item No 20.

Providing and filling sand around the pipe including hand packing ramming, watering, filling measure boxes etc. complete as directed.

Area around pipes shall be filled with sand immediately after the pipes have been laid and the joining material has hardened. The material shall be clean, free from boulders large roots, excessive amount of sods or other vegetable matter and lumps and shall be approved by the Engineer-in charge. Filling up to 0.3 metre above the top of the pipe shall be carefully done and the soil thoroughly rammed, temped or vibrated in layers of not exceeding 150 mm. particular care being taken to thoroughly consolidate the materials under the launches of the pipe. Filling shall be carried out simultaneously on both sides of the pipes in such a manner that unequal pressures do not occur. In case of high embankments after filling up to the top in the above said manner a loose fill of a depth equal to external diameter of the pipe shall be placed over the pipe before further

Materials shall be filled in pharas 3m. x 1.5. m x 0.5 m size and shall be measured in Cu.M. unit.

Rate includes cost of materials and spreading including labour and tools needed for the above operations.

Item No 21.

Providing Diversion of road 5.50 mt width (Having 7.50 mt formation width) For structure by providing & spreading Earth work , 100 mm GSB-III, 100 mm GSB -V, 100 mm WMM ,BUSG Manually Width Side shoulder and loose pipe. The length of Road is depend on site condition etc as directed by Engineer in Charge .

Providing Diversion of road 5.50 mt width (Having 7.50 mt formation width) For structure by providing and laying 37.5 mm BM, 18 Sealcoat. The length of Road is depend on site condition etc as directed by Engineer in Charge .

The temporary diversion shall be prepared as per the instruction of the Engineer-in-charge of the work. The complete diversion shall be maintained in trafficable condition till completion of the whole work. The diversion shall be well dressed and smooth so that traffic can be ply smoothly on the same. The necessary provision of caution / warning boards, red reflector at night time and guards stones on both sides shall be provided for the safety purpose.

Diversion shall start and end well out side the work site so that no accident take place. Embankment of earth shall be carried out with proper watering and rolling to form level surfaces. It shall have gentle slope or grade so that every vehicle including bullock cart can pass on it. Uniform layer of locally available GSB type material form river bed shall be spreaded on earthen embankment for hard and uniform riding surface. If work will be continued till monsoon season, agency has to provide pipes to allow water flow and shall be responsible for repair of diversion if washed out or damaged. Original road shall be completely blocked to avoid accident.

Diversion shall be maintained till traffic is restored on original road by filling depressions or cuts by GSB material and rolling and spraying water to reduce dust at site of work.

Diversion of road 5.50 mt width (having 7.50 mt formation width) for structure by providing & spreading earth work, 100 mm GSB-III, 100 mm GSB-V, 100 mm WMM, BUSG manually width side shoulder and loose pipe & also provide necessary traffic sign, diversion board for smooth & safe traffic. Proper maintaining the diversion during the whole work of completed and open for traffic. After completion works removing the same diversion for clearing the water way. Demolition of diversion serviceable materials shall be stacking as directed by Engineer-in-charge.

The length of road is depend on site condition etc. as directed by Engineer in charge.

Payment shall be made on Rmt. basis.

Item No 1.

Providing Diversion of road 5.50 mt width (having 7.50 mt formation width) for structure by providing and laying 37.5mm B.M., 18 sealcoat. The length of road is depend on site condition etc. as directed by Engineer in charge.

The temporary diversion shall be prepared as per the instruction of the Engineer-in-charge of the work. The complete diversion shall be maintained in trafficable condition till completion of the whole work. The diversion shall be well dressed and smooth so that traffic can be ply smoothly on the same. The necessary provision of caution / warning boards, red reflector at night time and guards stones on both sides shall be provided for the safety purpose.

Diversion shall start and end well out side the work site so that no accident take place. Embankment of earth shall be carried out with proper watering and rolling to form level surfaces. It shall have gentle slope or grade so that every vehicle including bullock cart can pass on it. Uniform layer of locally available GSB type material form river bed shall be spreaded on earthen embankment for hard and uniform riding surface. If work will be continued till monsoon season, agency has to provide pipes to allow water flow and shall be responsible for repair of diversion if washed out or damaged. Original road shall be completely blocked to avoid accident.

Diversion shall be maintained till traffic is restored on original road by filling depressions or cuts by GSB material and rolling and spraying water to reduce dust at site of work.

Providing Diversion of road 5.50 mt width (having 7.50 mt formation width) for structure by providing and laying 37.5mm B.M., 18 seal coat.

The length of road is depend on site condition etc. as directed by Engineer in charge.

Payment shall be made on Rmt. basis.

Item No 23.

Dry Lean Cement Concrete Sub- base (Construction of dry lean cement concrete Sub- base over a prepared sub-grade with coarse and fine aggregate conforming to IS: 383, the size of coarse aggregate not exceeding 25 mm, aggregate cement ratio not to exceed 15:1, aggregate gradation after blending to be as per table 600-1, cement content not to be less than 150 kg/ cum, optimum moisture content to be determined during trial length construction, concrete strength not to be less than 10 Mpa at 7 days, mixed in a batching plant, transported to site, laid with a paver with electronic sensor, compacting with 8-10 tonnes vibratory roller, finishing and curing.)

601. CEMENT CONCRETE PAVEMENT (MORTH)**601.1. Scope**

601.1.1. The work shall consist of construction of (zero slump) dry lean concrete sub-base for cement concrete pavement in accordance with the requirements of these Specifications and in conformity with the lines, grades and cross-sections shown on the drawings or as directed by the Engineer. The work shall include furnishing of all plant and equipment, materials and labour and performing all operations, in connection with the work, as approved by the Engineer.

601.1.2. The design parameters of dry lean concrete sub-base, viz., width, thickness, grade of concrete, details of joints, if any, etc. shall be as stipulated in the drawings.

601.2. Materials**601.2.1. Sources of Materials**

The Contractor shall indicate to the Engineer the source of all materials with relevant test data to be used in the dry lean concrete work sufficiently in advance and the approval of the Engineer for the same shall be obtained at least 45 days before the scheduled commencement of the work in trial length. If the Contractor later proposes to obtain the materials from a different source during the execution of main work, he shall notify the Engineer with relevant test data for his approval at least 45 days before such materials are to be used.

601.2.2. Cement:

Any of the following types of cement may be used with prior approval of the Engineer:

Sr. No	Type	Conforming to
i)	Ordinary Portland Cement 43 Grade	IS:8112
ii)	Portland Slag Cement	IS:455
iii)	Portland Pozzolana Cement	IS:1489-Part I

If the subgrade soil contains soluble sulphates in a concentration more than 0.5 percent, sulphate resistant cement conforming to IS:6909 shall be used.

Cement to be used may preferably be obtained in bulk form. It shall be stored in accordance with stipulations contained in Clause 1014 and shall be subjected to acceptance test prior to its immediate use.

601.2.3. Fly-ash

Fly-ash upto 20 percent by weight of cementitious material (cement+flyash) may be

used along with 43/53 grade cement may be used to replace OPC cement grade 43 upto 30 percent by weight of cement. Fly-ash shall conform to IS:3812 (Part 1) and its use shall be permitted only after ensuring that facilities exist for uniform blending through a proper mechanical facility with automated process control like batch mix plant conforming to IS:4925 and IS:4926.

601.2.4. Aggregates

601.2.4.1 Aggregates for lean concrete shall be natural material complying with IS:383. The aggregates shall not be alkali reactive. The limits of deleterious materials shall not exceed the requirements set forth in Table 600-2. In case the Engineer considers that the aggregates are not free from dirt, the same may be washed and drained for at least 72 hours before batching, or as directed by the Engineer.

601.2.4.2 Coarse aggregate:

Coarse aggregates shall comply with Clause 602.2.6.2, except that the maximum size of the coarse aggregate shall be 26.5 mm, and aggregate gradation shall comply with Table 600-1.

601.2.4.3 Fine aggregate:

The fine aggregate shall comply with Clause 602.2.6.3.

601.2.4.4 The material after blending shall conform to the grading as indicated in Table 600-1.

Table 600-1 : Aggregate Gradation for Dry Lean Concrete

Sieve Designation	Percentage by Weight Passing the Sieve
26.5 mm	100
19.0 mm	75-95
9.50 mm	50-70
4.75 mm	30-55
2.36 mm	17-42
600 Micron	8-22
300 Micron	7-17
150 Micron	2-12
75 Micron	0-10

601.2.5 Water:

Water used for mixing and curing of concrete shall comply with Clause 602.2.7.

601.2.6 Storage of Materials

All materials shall be stored in accordance with the provisions of Clauses 602.2.12 of these Specifications and other relevant IS Specifications.

601.3 Proportioning of Materials for the Mix

601.3.1 The mix shall be proportioned with a maximum aggregate cementitious material ratio of 15:1. The water content shall be adjusted to the optimum as per Clause 601.3.2 for facilitating compaction by rolling. The strength and density requirements of concrete shall be determined in accordance with Clauses 601.7 and 601.8 by making trial mixes. Care should be taken to prevent one size of aggregate falling into the other size of the hopper of the feeding bin while loading the individual size of aggregates into the bins.

601.3.2 Moisture Content

The optimum water content shall be determined and demonstrated by rolling during trial length construction and the optimum moisture content and degree of compaction shall be got approved from Engineer. While laying in the main work, the lean concrete shall have a moisture content between the optimum and optimum +2 percent, keeping in view the effectiveness of compaction achieved and to compensate for evaporation losses.

601.3.3 Cement Content

The cement content in the dry lean concrete shall be such that the strength specified in Clause 601.3.4 is achieved. The minimum cement content shall be 150 kg/cu.m of concrete. In case flyash is blended at site as part replacement of cement, the quantity of flyash shall not be more than 20 percent by weight of cementitious material and the content of OPC shall not be less than 120 kg/cu.m.

If this minimum is not sufficient to produce dry lean concrete of the specified strength, it shall be increased as necessary by the Contractor at his own cost.

601.3.4 Cement Content

The average compressive strength of each consecutive group of 5 cubes made in accordance with Clause 903.5.1.1 shall not be less than 10 MPa at 7 days. In addition, the minimum compressive strength of any individual cube shall not be less than 7.5 MPa at 7 days. The design mix complying with the above Clauses shall be got approved from the Engineer and demonstrated in the trial length construction.

601.4 Sub-grade

The sub-grade shall conform to the grades and cross-sections shown on the drawings and shall be laid and compacted in accordance with Clause 305. The subgrade strength shall correspond to the design strength specified in the Contract. As far as possible, the construction traffic shall be avoided on the prepared sub-grade.

601.5 Drainage Layer

A drainage layer conforming to Clause 401 shall be laid above the subgrade before laying the Dry Lean Concrete sub-base, as specified in the drawings and the Contract.

601.6 Construction

601.6.1 General

The Dry Lean Concrete shall be laid on the prepared granular drainage layer. The pace and programme of the Dry Lean Concrete sub-base construction shall be matching suitably with the programme of construction of the cement concrete pavement over it. The Dry Lean Concrete sub-base shall be overlaid with concrete pavement only after 7 days of sub-base construction.

601.6.2 Batching and Mixing

The batching plant shall be capable of proportioning the materials by weight, each type of material being weighed separately in accordance with Clauses 602.9.2, 602.9.3.1 and 602.9.3.2.

The design features of Batching Plant should be such that the plant can be shifted

601.6.3 Transporting

Plant mix lean concrete shall be discharged immediately from the mixer, transported directly to the point where it is to be laid and protected from the weather by covering the tipping trucks with tarpaulin during transit. The concrete shall be transported by tipping trucks, sufficient in number to ensure a continuous supply of material to feed the laying equipment to work at a uniform speed and in an uninterrupted manner. The lead of the batching plant to paving site shall be such that the travel time available from mixing to paving as specified in Clause 601.6.5.2 will be adhered to. Tipping truck shall not have old concrete sticking to it. Each tipping truck shall be washed with water jet before next loading as and when required after inspection.

601.6.4 Placing

Lean concrete shall be placed by a paver with electronic sensor on the drainage layer or as specified in the Contract. The equipment shall be capable of laying the material in one layer in an even manner without segregation, so that after compaction the total thickness is as specified. The paving machine shall have high amplitude tamping bars to give good initial compaction to the sub-base. One day before placing of the dry lean cement concrete sub- base, the surface of the granular sub-base/drainage layer shall be given a fine spray of water and rolled with a smooth wheeled roller.

Preferably the lean concrete shall be placed and compacted across the full width of the two lane carriageway, by constructing it in one go. In roads with carriageway more than 2 lanes a longitudinal joint shall be provided. Transverse butt type joint shall be provided at the end of the construction in a day. Transverse joints in the concrete pavement shall not be coterminous with the transverse construction joint of the Dry Lean Concrete.

The Dry Lean Concrete shall be laid in such a way that it is atleast 750 mm wider on each side than the proposed width including paved shoulders of the concrete pavement. The actual widening shall be decided based on the specifications of the paver, such that the crawler moves on the Dry Lean Concrete, and the cost of extra width shall be borne by the Contractor.

601.6.5 Placing

601.6.5.1 The compaction shall be carried out immediately after the material is laid and levelled. In order to ensure thorough compaction, rolling shall be continued on the full width till there is no further visible movement under the roller and the surface is well closed. The minimum dry density obtained shall not be less than 98 percent of that achieved during the trial length construction in accordance with Clause 601.7. The densities achieved at the edges i.e. 0.5 m from the edge shall not be less than 96 percent of that achieved during the trial construction.

601.6.5.2 The spreading, compacting and finishing of the lean concrete shall be carried out as rapidly as possible and the operation shall be so arranged as to ensure that the time between the mixing of the first batch of concrete in any transverse section of the layer and the final finishing of the same shall not exceed 90 minutes when the temperature of concrete is between 25°C and 30°C, and 120 minutes if less than 25°C. This period may be reviewed by the Engineer in the light of the results of the trial run but in no case shall it exceed 120 minutes. Work shall not proceed when the temperature of

the concrete exceeds 30°C. If necessary, chilled water or addition of ice may be resorted to for bringing down the temperature. It is desirable to stop concreting when the ambient temperature is above 35°C. After compaction has been completed, roller shall not stand on the compacted surface for the duration of the curing period except during commencement of next day's work near the location where work was terminated the previous day.

601.6.5.3 Double drum smooth-wheeled vibratory rollers of minimum 80 to 100 kN static weight are suitable for rolling dry lean concrete. In case any other roller is proposed, the same shall be got approved from the Engineer, after demonstrating its performance. The number of passes required to obtain maximum compaction depends on the thickness of the dry lean concrete, the compactibility of the mix and the weight and type of the roller and the same as well as the total requirement of rollers for the jobs shall be determined during trial run by measuring in-situ density and the scale of the work to be undertaken.

Except on super elevated portions where rolling shall proceed from the inner edge to the outer, rolling shall begin from the edges gradually progressing towards the centre. First, the edge/edges shall be compacted with a roller running forward and backward. The roller shall then move inward parallel to the centerline of the road, in successive passes uniformly lapping preceding tracks by at least one half width.

601.6.5.4 A preliminary pass without vibration to bed the Dry Lean Concrete down shall be given followed by the required number of passes to achieve the desired density and, a final pass without vibration to remove roller with vibration marks and to smoothen the surface.

Special care and attention shall be exercised during compaction near joints, kerbs, channels, side forms and around gullies and manholes. In case adequate compaction is not achieved by the roller at these locations, use of plate vibrators shall be made, if so directed by the Engineer.

601.6.5.5 The final lean concrete surface on completion of compaction shall be well closed, free from movement under roller and free from ridges, low spots, cracks, loose material, pot holes, ruts or other defects. The final surface shall be inspected immediately on completion and all loose, segregated or defective areas shall be corrected by using fresh lean concrete material, laid and compacted. For repairing honeycombed/hungry surface, concrete with aggregates of size 10 mm and below shall be spread and compacted as per Specifications. It is necessary to check the level of the rolled surface for compliance. Any level/thickness deficiency shall be corrected after applying concrete with aggregates of size 10 mm and below after roughening the surface. Surface regularity also shall be checked with 3 m straight edge. Strength tests shall be carried out, and if deficiency in strength is noticed, at least three (evenly spread) cores of minimum 100 mm dia per km shall be cut to check deficiency in strength. The holes resulting from cores shall be restored by filling with concrete of the specified strength and compacted by adequate rodding.

601.6.5.6 Segregation of concrete in the tipping trucks shall be controlled by moving the dumper back and forth while discharging the mix into the same or by any appropriate means. Paving operation shall be such that the mix does not segregate.

601.6.6 Joints

Construction and longitudinal joints shall be provided as per the drawings.

Transverse butt type joint shall be provided at the end of the construction in a day. Longitudinal construction joint shall be provided only when full width paving is not possible. Transverse joints in Dry Lean concrete shall be staggered from the construction butt type joint in Concrete pavement by 800-1000 mm.

Longitudinal joint in Dry Lean Concrete shall be staggered by 300-400 mm from the longitudinal joint of concrete pavement.

At longitudinal or transverse construction joints, unless vertical forms are used, the edge of compacted material shall be cut back to a vertical plane where the correct thickness of the properly compacted material has been obtained.

601.6.7 Curing

As soon as the lean concrete surface is compacted, curing shall commence. One of the following methods shall be adopted:

- a) Curing may be done by covering the surface by gunny bags/hessian, which shall be kept wet continuously for 7 days by sprinkling water.
- b) The curing shall be done by spraying with approved resin based aluminized reflective curing compound conforming to ASTM-C 309-81 in accordance with Clause 602.9.12. As soon as the curing compound has lost its tackiness, the surface shall be covered with wet hessian for three days. The rate of application shall be as recommended by the supplier.
- c) Wax-based white pigmented curing compound with water retention index of not less than 90 percent shall be used to cure the dry lean concrete. The curing compound shall conform to BS:7542. The compound shall be applied uniformly with a mechanical sprayer and with a hood to protect the spray from the wind. The curing compound shall be applied over the entire exposed surface of the Dry Lean Concrete, including sides and edges, at the rate of 0.2 litres/sq.m, or as recommended by the supplier.

The first application, referred to as curing application shall be applied immediately after the final rolling of Dry Lean Concrete is completed. As soon as the curing compound loses tackiness, the surface shall be covered with wet hessian for three days. The second application of curing compound also referred to as the debonding application, shall be applied 24 to 48 hours prior to the placement of the concrete pavement. Any damaged Dry Lean Concrete shall be corrected prior to the second application. Normally, the manufacturer's instructions shall be followed for its application.

601.7 Trial Mixes

The Contractor shall make trial mixes of dry lean concrete with moisture contents like 5.0, 5.5, 6.0, 6.5 and 7.0 percent using specified cement content, specified aggregate grading and aggregate-cement ratio specified in Clause 601.3.1. Optimum moisture and density shall be established by preparing cubes with varying moisture contents. Compaction of the mix shall be done in three layers with vibratory hammer fitted with a square or rectangular foot as described in Clause 903.5.1.1. After establishing the optimum moisture, a set of six cubes shall be cast at optimum moisture for the determination of compressive strength on the third and the seventh day. Trial mixes shall be repeated if the strength is not satisfactory by increasing cement content. After the mix design is approved, the Contractor shall construct a trial section in accordance with Clause 601.8.

If during the construction of the trial length, the optimum moisture content determined as above is found to be unsatisfactory, the Contractor may make suitable changes in the moisture content to achieve the satisfactory mix. The cube specimens prepared with the changed mix content should satisfy the strength requirement. Before production of the mix, natural moisture content of the aggregate should be determined on a day-to-day basis so that the moisture content could be adjusted. The mix finally designed should neither stick to the rollers nor become too dry resulting in ravelling of surface.

601.8 Trial Length

601.8.1 The trial length shall be constructed at least 14 days in advance of the proposed date of commencement of work. At least 30 days prior to the construction of the trial length, the Contractor shall submit for the Engineer's approval a "Method Statement" giving detailed description of the proposed materials, plant, equipment, mix proportions, and procedure for batching, mixing, laying, compaction and other construction procedures. The Engineer shall also approve the location and length of trial construction which shall be a minimum of 100 m length laid in two days and for full width of the pavement. The trial length shall be outside the main works. The trial length shall contain the construction of at least one transverse construction joint involving hardened concrete and freshly laid Dry Lean Concrete sub-base. The construction of trial length shall be repeated till the Contractor proves his ability to satisfactorily construct the Dry Lean Concrete sub-base.

601.8.2 After the construction of the trial length, the in-situ density of the freshly laid material shall be determined by sand replacement method. Three density holes shall be made at locations equally spaced along a diagonal that bisects the trial length and average of these densities shall be determined. The density holes shall not be made in the strip 500 mm from the edges. The average density obtained from the three samples collected shall be the reference density and is considered as 100 percent. The field density of regular work will be compared with this reference density in accordance with Clauses 601.6.5.1 and 903.5.1.2.

601.8.3 The hardened concrete shall be cut over 3 m width and reversed to inspect the bottom surface for any segregation taking place. The trial length shall be constructed after making necessary changes in the gradation of the mix to eliminate segregation of the mix. The lower surface shall not have honey-combing and the aggregates shall not be held loosely at the edges.

601.8.4 The main work shall not start until the trial length has been approved by the Engineer. After approval has been given, the materials, mix proportions, moisture content, mixing, laying, compaction plant and construction procedures shall not be changed without the approval of the Engineer.

601.9 Tolerances for Surface Regularity, Level, Thickness, Density and Strength

Control of quality of materials and works shall be exercised by the Engineer in accordance with Section 900

601.10 Traffic

No heavy commercial vehicles like trucks and buses shall be permitted on the dry lean concrete sub-base. Construction vehicles at slow speed may be permitted after 7 days of its construction with the prior approval of the Engineer.

601.11 Measurement for Payment

The unit of measurement for dry lean concrete pavement shall be in cubic metre of concrete placed, based on the net plan area for the accepted thickness shown on the drawings or as directed by the Engineer.

601.12 Rate

The Contract unit rate payable for dry lean concrete sub-base shall be for carrying out the required operations including full compensation for all labour, materials and equipment, mixing, transport, placing, compacting, finishing, curing, rectification of defective surface testing and incidentals such as trial length to complete the work as per Specifications, all royalties, fees, storage and rents where necessary and all leads and lifts.

Item No 24.

Cement Concrete Pavement (Construction of un-reinforced, dowel jointed, plain cement concrete pavement over a prepared sub base with 43 grade cement @ 400 kg per cum, coarse and fine aggregate conforming to IS 383, maximum size of coarse aggregate not exceeding 25 mm, mixed in a batching and mixing plant as per approved mix design, transported to site, laid with a fixed form or slip form paver, spread, compacted and finished in a continuous operation including provision of contraction, expansion, construction and longitudinal joints, joint filler, separation membrane, sealant primer, joint sealant, debonding strip, dowel bar, tie rod, admixtures as approved, curing compound, finishing to lines and grades as per drawing)

602. CEMENT CONCRETE PAVEMENT (MORTH)**602.1. Scope**

602.1.1. The work shall consist of construction of (zero slump) dry lean concrete sub-base for cement concrete pavement in accordance with the requirements of these Specifications and in conformity with the lines, grades and cross-sections shown on the drawings or as directed by the Engineer. The work shall include furnishing of all plant and equipment, materials and labour and performing all operations, in connection with the work, as approved by the Engineer.

602.1.2. The design parameters, viz., thickness of pavement slab, grade of concrete, joint details etc. shall be as stipulated in the drawings.

602.2. Materials**602.2.1 Source of Materials**

The Contractor shall indicate to the Engineer the source of all materials to be used in the concrete work with relevant test data sufficiently in advance, and the approval of the Engineer for the same shall be obtained at least 45 days before the scheduled commencement of the work in trial length. If the Contractor subsequently proposes to obtain materials from a different source during the execution of main work, he shall notify the Engineer, with relevant test data, for his approval, at least 45 days before such materials are to be used.

602.2.2 Cement

Any of the following types of cement capable of achieving the design strength may be used with prior approval of the Engineer, but preference shall be to use at least the 43 grade or higher.

Sr. No	Type	Conforming to
i)	Ordinary Portland Cement 43 Grade	IS:8112
ii)	Ordinary Portland Cement 53 Grade	IS:12269
iii)	Portlant slag cement	IS:455
iv)	Portland Pozzolana Cement	IS:1489-Part I

If the soil around concrete pavement has soluble salts like sulphates in excess of 0.5 percent, the cement used shall be sulphate resistant and shall conform to IS:12330.

Cement to be used may preferably be obtained in bulk form. If cement in paper bags is proposed to be used, there shall be bag-splitters with the facility to separate pieces of paper bags and dispose them off suitably. No paper pieces shall enter the concrete mix. Bulk cement shall be stored in accordance with Clause 1014. The cement shall be subjected to acceptance test.

Fly-ash upto 20 percent by weight of cementitious material may be used in Ordinary Portland Cement 43 and 53 Grade as part replacement of cement provided uniform blending with cement is ensured. The fly ash shall conform to IS:3812 (Part I).

Site mixing of fly ash shall be permitted only after ensuring availability of the equipments at site for uniform blending through a specific mechanised facility with automated process control like batch mix plants conforming to IS:4925 and IS:4926. Site mixing will not be allowed otherwise.

The Portland Pozzolana Cement produced in factory as per IS:1489-Part I shall not have fly-ash content more than 20 percent by weight of cementitious material. Certificate from the manufacturer to this effect shall be produced before use.

602.2.3 Chemical Admixtures

Admixtures conforming to IS:9103 and IS:6925 shall be permitted to improve workability of the concrete and/or extension of setting time, on satisfactory evidence that they will not have any adverse effect on the properties of concrete with respect to strength, volume change, durability and have no deleterious effect on steel bars. The particulars of the admixture and the quantity to be used, must be furnished to the Engineer in advance to obtain his approval before use. Satisfactory performance of the admixtures should be proved both on the laboratory concrete trial mixes and in the trial length paving. If air entraining admixture is used, the total quantity of air shall be 5 ± 1.5 percent for 31.5 mm maximum nominal size aggregate (in air-entrained concrete as a percentage of the volume of the mix).

602.2.4 Silica Fumes

Silica fume conforming to a standard approved by the Engineer may be used as an admixture in the proportion of 3 to 10 percent of cement. Silica fume shall comply with the requirements given in IS:15388-2003, IS:456-2000, IRC:SP:76 and IRC:44-

602.2.5 Fibres

Fibres may be used subject to the provision in the design/approval by the Engineer to reduce the shrinkage cracking and post-cracking. The fibres may be steel fibre as per IRC:SP:46 or polymeric Synthetic fibres within the following range of

Effective Diameter	10 micron – 100 micron
Length	6-48 mm
Specific gravity	more than 1.0
Suggested dosage	0.6-2.0 kg/cu.m (0.2 - 0.6% by weight of cement)
Water absorption	less than 0.45 percent
Melting point of this fibre shall not be less than 160°C.	
The aspect ratio generally varies from 200 to 2000.	
These synthetic fibres will have good alkali and UV light resistance.	

When fibres are used, the mix shall be so designed that the slump of concrete at paving site is 25 ± 15 mm.

602.2.6 Aggregates

602.2.6.1 Aggregates for pavement concrete shall be natural material complying with IS:383 but with a Los Angeles Abrasion Test value not exceeding 35 percent. The limits of deleterious materials shall not exceed the requirements set out in Table 600-2.

Table 600-2 : Permissible Limits of Deleterious Substances in Fine and Coarse Aggregates

Sr No	Deleterious Substance	Method of Test	Fine Aggregate Percentage by Weight, (Max)		Coarse Aggregate Percentage by Weight (Max)	
			Uncrushed	Crushed*	Uncrushed	Crushed*
(1)	(2)	(3)	(4)	(5)	(6)	(7)
i)	Coal and lignite	IS:2386 (Part II)-1963	1.0	1.0	1.0	1.0
ii)	Clay lumps	do	1.0	1.0	1.0	1.0
iii)	Materials finer than 75μ IS Sieve	IS:2386 (Part I)-1963	3.0	8.0	3.0	3.0
iv)	Soft fragments	IS:2386 (Part II)-1963	-	-	3.0	-
v)	Shale	IS:2386 (Part II)-1963	1.0	-	-	-
vi)	Total of percentages of all deleterious materials (except mica) including Sl No. (i) to (v) for col 4, 6 and 7 and Sl No. (i) and (ii) for col 5 only		5.0	2.0	5.0	5.0

* Crushed aggregate at least one face fractured

Note: The presence of mica in the fine aggregate has been found to reduce considerably the durability and compressive strength of concrete and further investigations are underway to determine the extent of the deleterious effect of mica. It is advisable, therefore, to investigate the mica content of fine aggregate and make suitable allowances for the possible reduction in the strength of concrete or mortar; in cases where the stretch of the project road passes through micaceous belt.

The aggregates shall be free from chert, flint, chalcedony or other silica in a form that can react with the alkalies in the cement. In addition, the total chlorides content expressed as chloride ion content shall not exceed 0.06 percent by weight and the total sulphate content expressed as sulphuric anhydride (SO₃) shall not exceed 0.25 percent by weight. In case the Engineer considers that the aggregates are not free from dirt, the same may be washed and drained for atleast 72 hours before batching, as directed by the Engineer.

602.2.6.2 Coarse Aggregates

Coarse aggregates shall consist of clean, hard, strong, dense, non-porous and durable pieces of crushed stone or crushed gravel and shall be devoid of pieces of disintegrated stone, soft, flaky, elongated, very angular or splintery pieces.

The maximum size of coarse aggregate shall not exceed 31.5 mm for pavement concrete. No aggregate which has water absorption more than 2 percent shall be used in the concrete mix. The aggregates shall be tested for soundness in accordance with IS:2386 (Part-5). After 5 cycles of testing, the loss shall not be more than 12 percent if sodium sulphate solution is used or 18 percent if magnesium sulphate solution is used. The Los Angeles Abrasion value shall not exceed 35. The combined flakiness and elongation index of aggregate shall not be more than 35 percent.

602.2.6.3 Fine Aggregates

The fine aggregates shall consist of clean natural sand or crushed stone sand or a combination of the two and shall conform to IS:383. Fine aggregate shall be free from soft particles, clay, shale, loam, cemented particles, mica and organic and other foreign matter. The fine aggregates shall have a sand equivalent value of not less than 50 when tested in accordance with the requirement of IS:2720 (Part 37).

602.2.6.4 Combined Gradation of Fine and Coarse

The combined gradation of fine and coarse aggregates shall be as per Table 600-3.

Table 600-3 : Aggregate Gradation for Pavement Quality Concrete

Sieve Designation	Percentage by Weight Passing the Sieve
31.5 mm	100
26.5 mm	85-95
19.0 mm	68-88
9.5 mm	45-65
4.75 mm	30-55
600 micron	8-30
150 micron	5-15
75 micron	0-5

602.2.7 Water

Water used for mixing and curing of concrete shall be clean and free from injurious amount of oil, salt, acid, vegetable matter or other substances harmful to the finished concrete. It shall meet the requirements stipulated in IS:456.

602.2.8 Steel for Dowels and Tie Bars

Steel shall conform to the requirements of IS:432 and IS:1786 as relevant. The dowel bars shall conform to IS:432 of Grade I. Tie bars shall be either High yield Strength Deformed bars conforming to IS:1786 and grade of Fe 500 or plain bars conforming to IS:432 of Grade I. The steel shall be coated with epoxy paint for protection against corrosion.

602.2.9 Joint Filler Board

Synthetic Joint filler board for expansion joints shall be used only at abutting structures like bridges and shall be of 20-25 mm thickness within a tolerance of ± 1.5 mm and of a firm compressible material and complying with the requirements of compressibility more than 25 percent. It shall be 25 mm less in depth than the thickness of the slab within a tolerance of ± 3 mm and provided to the full width between the side forms. It shall be in suitable lengths which shall not be less than one lane width. If two pieces are joined to make up full width, the joint shall be taped such that no slurry escapes through the joint. Holes to accommodate dowel bars shall be accurately bored or punched out to give a sliding fit on the dowel bars.

602.2.10 Joint Sealing Compound

The joint sealing compound shall be of hot poured, elastomeric type or cold polysulphide/ polyurethane/silicone type having flexibility, resistance to age hardening and durability as per IRC:57. Manufacturer's certificate shall be produced by the Contractor for establishing that the sealant is not more than six months old and stating that the sealant complies with the relevant standard mentioned below. The samples shall meet the requirements as mentioned in IRC:57.

If sealant is of hot poured type, it shall conform to

Hot applied sealant : IS:1834 or ASTM : 3406-95, as applicable

Cold poured sealants shall be one of the following :

- | | | |
|------|--------------|--------------------------------------|
| i) | polysulphide | IS:11433 (Part I), BS:5212 (Part II) |
| ii) | polyurethane | BS:5212 |
| iii) | silicone | ASTM 5893-04 |

602.2.11 Preformed Seals

The pre-formed joint sealing material shall be a vulcanized elastomeric compound using polychloroprene (Neoprene) as the base polymer.

The joint seal shall conform to requirements of ASTM D 2628 as given in Table 600-

Table 600-4 : Requirement of Preformed Seals as per ASTM D 2628

Sr. No.	Description	Requirements	ASTM Test Methods
1)	Tensile strength, min	13.8 Mpa	D 412
2)	Elongation at break	Min. 250%	D 412
3)	Hardness, Type A durometer	55 +/-5 points	D 412
4)	Oven aging, 70 h at 100°C Tensile strength loss	20% max	D 573
5)	Elongation loss	20% max	

6)	Hardness Change Type A durometer	0 to +10 points	D 471
7)	Oil Swell, ASTM Oil 3, 70 h at 100°C Weight Change	45% max	D 1149
8)	Ozone resistance 20 percent strain, 300 pphm in air, 70 h at 40°C	No cracks	D 2240
9)	Low temperature stiffening, 7 days at -10°C Hardness Change type A durometer	0 to +15 points	
10)	Low temperature recovery, 22h at -10°C, 50% deflection	88% min	D 2628
11)	Low temperature recovery, 22h at -29°C, 50% deflection	83% min	D 2629
12)	Low temperature recovery, 70h at -100°C, 50% deflection	85% min	D 2630
13)	Compression, deflection, at 80% of normal width (min)	613 N/m	D 2631

602.2.12 Storage of Materials

All materials shall be stored in accordance with the provisions of Clause 1014 of the Specifications. All efforts shall be made to store the materials in proper places so as to prevent their deterioration or contamination by foreign matter and to ensure their satisfactory quality and fitness for the work. The platform where aggregates are stock piled shall be paved and elevated from the ground atleast by 150 mm. The area shall have slope to drain off rain water. The storage space must also permit easy inspection, removal and storage of the materials. Aggregates of different sizes shall be stored in partitioned stack-yards. All such materials even though stored in approved godowns must be subjected to acceptance test as per Clause 903 of these Specifications prior to their use.

602.3 Proportioning of Concrete

602.3.1 After approval by the Engineer of all the materials to be used in the concrete, the Contractor shall submit the mix design based on weighed proportions of all ingredients for the approval of the Engineer vide Clause 602.3.4. The mix design shall be submitted at least 30 days prior to the paving of trial length and the design shall be based on laboratory trial mixes using the approved materials and methods as per IRC:44 or IS:10262. The target mean strength for the design mix shall be determined as indicated in Clause 602.3.3.1. The mix design shall be based on the

602.3.2 Cement Content

When Ordinary Portland Cement (OPC) is used the quantity of cement shall not be less than 360 kg/cu.m. In case fly ash grade I (as per IS:3812) is blended at site as part replacement of cement, the quantity of fly ash shall be upto 20 percent by weight of cementitious material and the quantity of OPC in such a blend shall not be less than 310 kg/cu.m. The minimum of OPC content, in case ground granulated blast furnace slag cement blended, shall also not be less than 310 kg/m³. If this minimum cement content is not sufficient to produce concrete of the specified strength, it shall be increased as necessary by the contractor at his own cost.

602.3.3 Concrete Strength

602.3.3.1 The characteristic flexural strength of concrete shall not be less than 4.5 MPa unless specified otherwise. Target mean flexural strength for mix design shall be more than $4.5 \text{ MPa} + 1.65s$, where s is standard deviation of flexural strength derived by conducting test on minimum 30 beams. While designing the mix in the laboratory, correlation between flexural and compressive strengths of concrete shall be established on the basis of at least thirty tests on specimens. However, quality control in the field shall be exercised on the basis of flexural strength. It may, however, be ensured that the materials and mix proportions remain substantially unaltered during the daily concrete production. The water content shall be the minimum required to provide the agreed workability for full compaction of the concrete. The characteristic flexural strength of concrete shall not be less than 4.5 MPa unless specified otherwise. Target mean flexural strength for mix design shall be more than $4.5 \text{ MPa} + 1.65s$, where s is standard deviation of flexural strength the trial mixes or as approved by the Engineer and the maximum free water cement ratio shall be 0.45 when only OPC is used and 0.50 when blended cement (Portland Pozzolana Cement or Portland Slag Cement or OPC blended with fly ash or Ground Granulated Blast Furnace Slag, at site) is used.

602.3.3.2 The ratio between the 7 and 28 day strength shall be established for the mix to be used in the slab in advance, by testing pairs of beams and cubes at each stage on at least six batches of trial mix. The average strength of the 7 day cured specimens shall be the average strength of the 28 day specimens for each batch, and the ratio 'R' shall be determined. The ratio 'R' shall be expressed to three decimal places.

If during the construction of the trial length or during some normal working, the average value of any four consecutive 7 day test results falls below the required 7 day strength as derived from the value of 'R' then the cement content of the concrete shall, without extra payment, be increased by 5 percent by weight or by an amount agreed by the Engineer. The increased cement content shall be maintained at least until the four corresponding 28 day strengths have been assessed for in conformity with the requirements as per Clause 602.3.3.1. Whenever the cement content is increased, the concrete mix shall be adjusted to maintain the required workability.

602.3.4 Workability

602.3.4.1 The workability of the concrete at the point of placing shall be adequate for the concrete to be fully compacted and finished without undue flow. The optimum workability for the mix to suit the paving plant being used shall be determined by the Contractor and approved by the Engineer. The control of workability in the field shall be exercised by the slump test as per IS:1199.

602.3.4.2 The workability requirement at the batching and mixing plant and paving site shall be established by slump tests carried during trial paving. These requirements shall be established from season to season and also when the lead from batching and mixing plant site to the paving site changes. The workability shall be established for the type of paving equipment available. A slump value in the range of $25 \pm 15 \text{ mm}$ is reasonable for paving works but this may be modified depending upon the site requirement and got approved by the Engineer. These tests shall be carried out on every tipping truck/dumper at batching and mixing plant site and paving site initially when the work commences but subsequently the frequency can be reduced to alternate tipping trucks or as per the instructions of the Engineer.

602.3.5 Design Mix

- 602.3.5.1** The Contractor shall carry out laboratory trials of design mix with the materials from the approved sources to be used as per IRC:44. Trial mixes shall be made in presence of the Engineer or his representative and the design mix shall be subject to the approval of the Engineer. They shall be repeated, if necessary, until the proportions, that will produce a concrete which complies in all respects with these Specifications, and conform to the requirements of the design/drawings.
- 602.3.5.2** The proportions determined as a result of the laboratory trial mixes may be adjusted, if necessary, during the construction of the trial length. Thereafter, neither the materials nor the mix proportions shall be varied in any way except with the of the Engineer.
- 602.3.5.3** Any change in the source of materials or mix proportions proposed by the Contractor during the course of work shall be assessed by making laboratory trial mixes and the construction of a further trial length of length not less than 50 m unless approval is given by the Engineer for minor adjustments like compensation for moisture content in aggregates or minor fluctuations in the grading of aggregate.

602.4 Sub-base

The cement concrete pavement shall be laid over the sub-base constructed in accordance with the relevant drawings and Specifications. It shall be ensured that the sub-base is not damaged before laying the concrete pavement. If the dry lean concrete sub-base is found damaged at some places or it has cracks wider than 10 mm, it shall be repaired with fine cement concrete (aggregate size 10 mm and down) or bituminous concrete before laying separation membrane layer.

602.5 Separation Membrane

A separation membrane shall be used between the concrete slab and the sub-base. Separation membrane shall be impermeable PVC sheet 125 micron thick transparent or white in colour laid flat with minimum creases. Before placing the separation membrane, the sub-base shall be swept clean of all the extraneous materials using air compressor. Wherever overlap of plastic sheets is necessary, the same shall be at least 300 mm and any damaged sheathing shall be replaced at the Contractor's cost. The separation membrane may be nailed to the lower layer with concrete nails. The separation membrane shall be omitted when two layers of wax-based curing compound is used.

602.6 Joints

- 602.6.1** The locations and type of joints shall be as shown in the drawing. Joints shall be constructed depending upon their functional requirement. The location of the joints should be transferred accurately at the site and mechanical saw cutting of joints done as per stipulated dimensions. It shall be ensured that the required depth of cut is made from edge- to-edge of the pavement. Transverse and longitudinal joints in the pavement and Dry Lean Concrete sub-base shall be staggered so that they are not coincident vertically and are at least 800 to 1000 mm and 300 to 400 mm apart respectively. Sawing of joints shall be carried out with diamond studded blades soon after the concrete has hardened to take the load of the sawing machine and crew members without damaging the texture of the pavement.

Sawing operation could start as early as 4-8 hours after laying of concrete pavement but not later than 8 to 12 hours depending upon the ambient temperature, wind velocity, relative humidity and required maturity of concrete achieved for this

When the kerb is cast integrally with the main pavement slab, the joint cutting shall also be extended to the kerb.

Where the use of maturity meter is specified, sawing should not be initiated when the compressive strength of the concrete is less than 2 MPa and should be completed before it attains the compressive strength of 7 MPa.

602.6.2 Transverse Joints

602.6.2.1 Transverse joints shall be contraction, construction and expansion joints constructed at the spacing described in the drawings. Transverse joints shall be straight within the following tolerances along the intended line of joints.

- (i) Deviations of the performed filler board (IS:1838) in the case of expansion joints from the intended line of the joint shall not be greater than ± 10 mm.
- (ii) The best fit straight line through the joint grooves as constructed shall be not more than 25 mm from the intended line of the joint.
- (iii) Deviations of the joint groove from the best fit straight line of the joint shall not be greater than 10 mm.
- (iv) Transverse joints on each side of the longitudinal joint shall be in line with each other and of the same type and width. Transverse joints shall have a sealing groove which shall be sealed in compliance with Clause 602.10.

602.6.2.2 Contraction Joints

The contraction joints shall be placed transversely at pre-specified locations as per drawings/ design using dowel bars. These joints shall be cut as soon as the concrete has undergone initial hardening and is hard enough to take the load of joint sawing machine without causing damage to the slab.

Contraction joints shall consist of a mechanical sawn joint groove, 3 to 5 mm wide and one-fourth to one-third depth of the slab ± 5 mm or as stipulated in the drawings and dowel bars complying with Clause 602.6.5.

Contraction joint shall be widened subsequently to accommodate the sealant as per Clause 602.10, to dimensions shown on drawings or as per IRC:57.

602.6.2.3 Expansion Joints

The expansion joint shall consist of a joint filler board complying with Clause 602.2.9 and dowel bars complying with Clause 602.6.5 and as detailed in the drawings. The filler board shall be positioned vertically with the prefabricated joint assemblies along the line of the joint within the tolerances given in Clause 602.6.2.1. The adjacent slabs shall be completely separated from each other by the joint filler board.

602.6.3 Transverse Construction Joint

Transverse construction joint shall be placed whenever concreting is completed after a day's work or is suspended for more than 30 minutes. These joints shall be provided at location of contraction joints using dowel bars. If sufficient concrete has not been mixed to form a slab extending upto a contraction joint, and if an interruption occurs, the concrete placed shall be removed upto the last preceding joint and disposed of. At all construction joints, steel bulk heads shall be used to retain the concrete. The surface of the concrete laid subsequently shall conform to the grade and cross sections of the previously laid pavement. When positioning of bulk head/stop-end is not possible, concreting to an additional 1 or 2 m length may be carried out to enable the movement of joint cutting machine so that joint grooves may be cut and the extra 1 or 2 m length is cut out and removed subsequently after

After minimum 14 days of curing, in case OPC cement is used and 16 days of curing when flyash or blended cement is used, the construction joint shall be widened to accommodate the sealant as per Clause 602.10 to dimensions shown on drawing or as per IRC:57.

602.6.4 Longitudinal Joint

602.6.4.1 The longitudinal joints shall be constructed by forming or by sawing as per details of the joints shown in the drawing. Sawed longitudinal joints shall be constructed when the concrete pavement placement width exceeds 4.5 m. The groove may be cut after the final set of the concrete. Joints should be sawn to at least one-third the depth of the slab ± 5 mm as indicated in the drawing. The joint shall be widened subsequently to dimensions shown on the drawings.

Where adjacent lanes of pavement are constructed separately using slip form pavers or side forms, the tie bars may be bent at right angles against the vertical face/ side of the first lane constructed and straightened before placing concrete in the adjacent lane. Broken or damaged tie bars shall be repaired or replaced as required.

The groove for sealant shall be cut in the pavement lane placed later.

602.6.4.2 Tie Bars

Tie bars shall be provided at the longitudinal joints as per dimensions and spacing shown in the drawing and in accordance with Clause 602.6.6. The direction of the tie bars at curves shall be radial in the direction of the radius.

602.6.5 Dowel Bars

602.6.5.1 Dowel bars shall be mild steel rounds in accordance with Clause 602.2.8 with details/dimensions as indicated in the drawings and free from oil, dirt, loose rust or scale. They shall be straight, free of irregularities and burring restricting slippage in the concrete. The sliding ends shall be sawn or cropped cleanly with no protrusions outside the normal diameter of the bar. Any protrusions shall be removed by grinding the ends of the dowel bars. The dowel bar shall be supported on cradles/dowel chairs in pre-fabricated joint assemblies positioned prior to the construction of the slabs or mechanically inserted with vibration into the plastic concrete by a method which ensures correct placement of the bars besides full re-compaction of the concrete around the dowel bars.

602.6.5.2 Unless shown otherwise on the drawings, dowel bars shall be positioned at mid depth of the slab within a tolerance of ± 20 mm, and centered equally about intended lines of the joint within a tolerance of ± 25 mm. They shall be aligned parallel to the finished surface of the slab and to the centre line of the carriageway and to each other within tolerances given here-in-under, the compliance of which shall be

- i) For bars supported on cradles prior to the laying of the slab:
 - a) All bars in a joint shall be within ± 2 mm per 300 mm length of bar
 - b) 2/3rd of the number of bars shall be within ± 3 mm per 500 mm length of bar
 - c) No bar shall differ in alignment from an adjoining bar by more than 3 mm per 300 mm length of bar in either the horizontal or vertical plane
 - d) Cradles supporting dowel bar shall not extend across the line of joint i.e. no steel bar of the cradle assembly shall be continuous across the joint.
- ii) For all bars inserted after laying of the slab except those inserted by a Dowel Bar Inserter the tolerance for alignment may be twice as indicated in (i) above.

The transverse joints at curves shall be radial in the direction of the radius.

602.6.5.3 Dowel bars, supported on cradles in assemblies, when subject to a load of 110 N applied at either end and in either the vertical or horizontal direction (upwards and downwards and in both directions horizontally) shall conform to be within the limits given in Clause 602.6.5.2.

602.6.5.4 The assembly of dowel bars and supporting cradles, including the joint filler board in the case of expansion joints, shall have the following degree of rigidity when fixed in position:-

- i) For expansion joints, the deflection of the top edge of the filler board shall be not greater than 13 mm, when a load of 1.3 kN is applied perpendicular to the vertical face of the joint filler board and distributed over a length of 600 mm by means of a bar or timber packing, at mid depth and midway between individual fixings, or 300 mm from either end of any length of filler board, if a continuous fixing is used. The residual deflection after load shall be not more
- ii) The fixings for joint assembly shall not fail under 1.3 kN load and shall fail before the load reaches 2.6 kN when applied over a length of 600 mm by means of a bar or timber packing placed as near to the level of the line of
- iii) Fixings shall be deemed to fail when there is displacement of the assemblies by more than 3 mm with any form of fixing, under the test load. The displacement shall be measured at the nearest part of the assembly to the centre of the bar or timber packing.

602.6.5.5 Dowel bars in the contraction joints, construction joints and expansion joints shall be covered by a thin plastic sheath. The thickness of the sheath shall not exceed 0.5 mm and shall be tightly fitted on the bar for at least two-thirds of the length from one end for dowel bars in contraction/construction joints and half the length plus 50 mm for expansion joints. The sheathed bar shall comply with the following pull-out

Four bars shall be taken at random from stock and without any special preparation shall be covered by sheaths as required in this Clause. The ends of the dowel bars which have been sheathed shall be cast centrally into concrete specimens 150 mm x 150 mm x 600 mm, made of the same mix proportions to be used in the pavement, but with a maximum nominal aggregate size of 20 mm and cured in accordance with IS:516. At 7 days a tensile load shall be applied to achieve a movement of the bar of at least 0.25 mm. The average bond stress to achieve this movement shall not be

602.6.5.6 For expansion joints, a closely fitting cap 100 mm long consisting of waterproofed cardboard or an approved synthetic material like PVC or GI pipe shall be placed over the sheathed end of each dowel bar. An expansion space (about 25 mm) at least equal in length to the thickness of the joint filler board shall be formed between the end of the cap and the end of the dowel bar by using compressible sponge. To block the entry of cement slurry into the annular space between the sheathing and dowel bar shall be taped around its mouth.

602.6.6 Tie Bars

602.6.6.1 Tie bars in longitudinal joints shall be deformed steel bars of strength 500 MPa complying with IS:1786 and in accordance with the requirements given in this Clause. The bars shall be free from oil, dirt, loose rust and scale.

602.6.6.2 Tie bars projecting across the longitudinal joint shall be protected from corrosion for 75 mm on each side of the joint by a protective coating of bituminous paint with the approval of the Engineer. The coating shall be dry when the tie bars are used. In the case of coastal region and high rainfall areas, tie bars shall be epoxy coated in their full length as per IS:13620.

602.6.6.3 Tie bars in longitudinal joints shall be made up into rigid assemblies with adequate supports and fixings to remain firmly in position during the construction of the slab. Alternatively, tie bars at longitudinal joints may be mechanically or manually inserted into the plastic concrete from above by vibration using a method which ensures correct placements of the bars and recompaction of the concrete around the

602.6.6.4 Tie bars shall be positioned to remain in the middle from the top or within the upper middle third of the slab depth as indicated in the drawings and approximately parallel to the surface and approximately perpendicular to the line of the joint, with the centre of each bar on the intended line of the joints within a tolerance of ± 50 mm, and with a minimum cover of 30 mm below the joint groove. Spacing of tie bars on curves of radius less than 360 m shall not be less than 350 mm.

602.6.6.5 To check the position of the tie bars, one metre length, 0.5 m on either side of the longitudinal joint shall be opened when the concrete is green (within 20 to 30 minutes). The pit shall be refilled with the fresh concrete of same mix after checking.

602.7 Weather and Seasonal Limitations

602.7.1 Concreting during Monsoon Months

Concreting should be avoided during rainy season. However, when concrete is being placed during monsoon months and when it may be expected to rain, sufficient supply of tarpaulin or other waterproof cloth shall be provided along the line of the work. Any time when it rains, all freshly laid concrete which had not been covered for curing purposes shall be adequately protected. Any concrete damaged by rain shall be removed and replaced. If the damage is limited to texture, it shall be retextured in accordance with the directions of the Engineer.

602.7.2 Temperature Limitation

No concreting shall be done when the temperature of the concrete reaching the paving site is above 30°C. Besides, in adverse conditions like high temperature, low relative humidity, excessive wind velocity, imminence of rains etc., tents on mobile trusses may be provided over the freshly laid concrete for a minimum period of 3 hours as directed by the Engineer. To bring down the temperature, if necessary, chilled water or ice flakes should be made use of. When the ambient temperature is more than 35°C, no concreting shall be permitted. The ice flakes should not be manufactured from chlorinated water. Generally the rate of evaporation of water shall not exceed 1 kg/sqm/hour as per IRC:15.

No concreting shall be done when the concrete temperature is below 5°C and the temperature is further falling.

602.8 Fixed Form Paving

602.8.1 Side Forms and Rails

These shall be provided in case of fixed form paving. All side forms shall be of mild steel of depth equal to the thickness of pavement or slightly less to accommodate the surface irregularity of the sub-base. The forms can be placed in series of steel packing plates or shims to take care of irregularity of sub-base. They shall be sufficiently robust and rigid to support the weight and pressure caused by a paving equipment. Side forms for use with wheeled paving machines shall incorporate metal rails firmly fixed at a constant height below the top of the forms. The forms and rails shall be firmly secured in position by not less than 3 stakes/pins for every 3 m length so as to prevent movement in any direction. Forms and rails shall be straight within a tolerance of 3 mm in 3 m and when in place shall not settle in excess of 1.5 mm in 3 m while paving is being done. Forms shall be cleaned and oiled immediately before each use. The forms shall be bedded on a continuous bed of low moisture content lean cement mortar or concrete and set to the line and levels shown on the drawings within tolerances ± 10 mm and ± 3 mm respectively. The bedding shall not extend under the slab and there shall be no vertical step between adjacent forms of more than 3 mm. The forms shall be got inspected by the Engineer for his approval 12 hours before construction of the slab and shall not be removed until at least 12 hours afterwards. No concreting shall commence till formwork has

602.8.2 At all times sufficient forms shall be used and set to the required alignment for at least 300 m length of pavement immediately in advance of the paving operations, or the anticipated length of pavement to be laid within the next 24 hours whichever is

602.8.3 Slip Form Paving

602.8.3.1 Use of Guidewires

Where slip form paving is proposed, a guidewire shall be provided along both sides of the slab. Each guidewire shall be at a constant height above and parallel to the required edges of the slab as described in the contract drawing within a vertical tolerance of ± 3 mm. Additionally, one of the wires shall be kept at a constant horizontal distance from the required edge of the pavement as indicated in the contract drawing within a lateral tolerance of ± 10 mm.

602.8.3.2 The guidewires shall be supported on stakes 5–6 m apart by connectors capable of fine horizontal and vertical adjustment. The guidewire shall be tensioned on the stakes so that a 500 gm weight shall produce a deflection of not more than 20 mm when suspended at the mid point between any pair of stakes. The ends of the guidewires shall be anchored to fixing point or winch and not on the stakes. On the curves, the stakes shall be fixed at not more than 3 m centre-to-centre.

602.8.3.3 The stakes shall be positioned and hammered into the ground and the connectors will be maintained at their correct height and alignment from 12 hours on the day before concreting takes place till after finishing of texturing and spraying of curing compound on the concrete.

However, the guidewire shall be erected and tensioned on the connectors at any section for at least 2 hours before concreting that section.

602.8.3.4 The Contractor shall submit to the Engineer for his approval of line and level, the stakes and connectors which are ready for use in the length of road to be constructed. Such approval shall be obtained at least 12 hours before commencement of paving operation. Any deficiencies noted by the Engineer shall be rectified by the Contractor who shall then re-apply for approval of the affected stakes. Work shall not proceed until the Engineer has given his approval. It shall be ensured that the stakes and guidewires are not affected by the construction equipment when concreting is in

602.9 Construction

602.9.1 General

A systems approach may be adopted for construction of the pavement, and the Method Statement for carrying out the work, detailing all the activities, indication of time-cycle, equipment, personnel etc., shall be got approved from the Engineer before the commencement of the work. This shall include the type, capacity and make of the batching and mixing plant besides the hauling arrangement and paving equipment. The capacity of paving equipment, batching plant as well as all the ancillary equipment shall be adequate for a paving rate of at least 500 m in one day. The paving speed of slip-form paver shall not be less than 1.0 m per minute. The concreting should proceed continuously without stops and starts.

602.9.2 Batching and Mixing

Batching and mixing of the concrete shall be done at a central batching and mixing plant with automatic controls, located at a suitable place which takes into account sufficient space for stockpiling of cement, aggregates and stationary water tanks. This shall be located at an approved distance, duly considering the properties of the mix and the transporting arrangements available with the Contractor.

602.9.3 Equipment for Proportioning of Materials and

602.9.3.1 Proportioning of materials shall be done in the batching plant by weight, each type of material being weighed separately. The cement from the bulk stock may be weighed separately from the aggregates. Water shall be measured by volume. Specified percentage of plasticizer in volume will be added by weight of cement. Wherever properly graded aggregate of uniform quality cannot be maintained as envisaged in the mix design, the grading of aggregates shall be controlled by appropriate blending techniques. The capacity of batching and mixing plant shall be at least 25 percent higher than the proposed capacity of the laying/paving equipment.

602.9.3.2 Batching Plant and Equipment :

1) General : The batching plant shall include minimum four bins, weighing hoppers, and scales for the fine aggregates and for each size of coarse aggregate. If cement is used in bulk, a separate scale for cement shall be included. There shall be a separate bin for flyash, if this additive is specified. The weighing hoppers shall be properly sealed and vented to preclude dust during operation. Approved safety devices shall be provided and maintained for the protection of all personnel engaged in plant operation, inspection and testing. The batch plant shall be equipped with a suitable non-resettable batch counter which will correctly indicate the number of batches proportioned. A continuous type of mixing plant can also be used provided the ingredients are weighed through electronic sensors before feeding.

2) Automatic weighing devices : Batching plant shall be equipped to proportion aggregates and bulk cement by means of automatic weighing devices using load cells. The weighing devices shall have an accuracy within $\pm 1\%$ in respect of quantity of cement, admixtures and water and $\pm 2\%$ in respect of aggregates and the accuracy shall be checked at least once a month

3) Mixer : Mixers shall be pan type, reversible type or any other mixer capable of combining the aggregates, cement, and water into a thoroughly mixed and uniform mass within the specified mixing period, and of discharging the mix, without segregation. Each stationary mixer shall be equipped with an approved timing device which will automatically lock the discharge lever when the drum has been charged and release it at the end of the mixing period. The device shall be equipped with a bell or other suitable warning device adjusted to give a clearly audible signal each time the lock is released. In case of failure of the timing device, the mixer may be used for the balance of the day while it is being repaired, provided that each batch is mixed in 90 seconds or as per the manufacturer's recommendation. The mixer shall be equipped with a suitable non-resettable batch counter which shall correctly

The mixer shall be cleaned at suitable intervals. The pick-up and throw-over blades in the drum or drums shall be repaired or replaced when they are worn down 20 mm or more. The Contractor shall (1) have available at the job site a copy of the manufacturer's design, showing dimensions and arrangements of blades in reference to original height and depth, or (2) provide permanent marks on blade to show points of 20 mm wear from new conditions. Drilled holes of 5 mm diameter near each end and at midpoint of each blade are recommended. Batching Plant shall be calibrated in the beginning and thereafter at suitable interval not exceeding 1 month.

4) Control cabin : An air-conditioned centralized computer control cabin shall be provided for automatic operation of the equipment.

5) The design features of the batching plant should be such that it can be shifted quickly.

602.9.3.3 Paving Equipment

The concrete shall be placed with an approved fixed form or slip form paver with independent units designed to (i) spread, (ii) consolidate, screed and float-finish, (iii) texture and cure the freshly placed concrete in one complete pass of the machine in such a manner that a minimum of hand finishing will be necessary and so

Vibrators shall operate at a frequency of 8000-10000 impulses per minute under load at a maximum spacing of 600 mm. The variable vibration setting shall be provided in the machine.

602.9.3.4 Concrete Saw

The Contractor shall provide adequate number of concrete saws with sufficient number of diamond-edge saw blades. The saw machine shall be either electric or petrol/diesel driven type. A water tank with flexible hose and pump shall be made available for this activity on priority basis. The Contractor shall have at least one standby saw in good working condition. The concreting work shall not commence if the saws are not in working condition.

602.9.4 Hauling and Placing of Concrete

602.9.4.1 Freshly mixed concrete from the central batching and mixing plant shall be transported to the paver site by means of tipping trucks or transit mixers of sufficient capacity and approved design in sufficient numbers to ensure a constant supply of concrete. Covers shall be used for protection of concrete against the weather. While loading the concrete truck shall be moved back and forth under the discharge chute to prevent segregation. The tipping trucks shall be capable of maintaining the mixed concrete in a homogeneous state and discharging the same without segregation and loss of cement slurry. The feeding to the paver is to be regulated in such a way that the paving is done in an uninterrupted manner with a uniform speed throughout the day's work. Tipping trucks shall be washed at a regular frequency as prescribed by the Engineer to ensure that no left-over mix of

602.9.4.2 Placing of Concrete

The total time taken from the addition of the water to the mix, until the completion of the surface finishing and texturing shall not exceed 120 minutes when concrete temperature is less than 25°C and 90 minutes when the concrete temperature is between 25°C and 30°C. When the time between mixing and laying exceed these

The placing of concrete in front of the PQC paver should preferably be from the side placer to avoid damage to DLC by concrete tipping trucks. In case of unavoidable situation, truck supplying concrete to the paver may be allowed to ply on the DLC with the approval of the Engineer. The paver shall be capable of paving the

602.9.4.3 Where fixed form pavers are to be used, forms shall be fixed in advance as per Clause 602.8. Before any paving is done, the site shall be shown to the Engineer, in order to verify the arrangement for paving besides placing of dowels, tie-bars etc., as per the relevant Clauses of these Specifications. The mixing and placing of concrete shall

- 602.9.4.4** In areas inaccessible to paving equipment, the pavement shall be constructed using side forms, as per Clause 602.9.7.
- 602.9.4.5** In all cases, the temperature of the concrete shall be measured at the point of discharge from the delivery vehicle.
- 602.9.4.6** The addition of water to the surface of the concrete to facilitate the finishing operations will not be permitted except with the approval of the Engineer when it shall be applied as a mist by means of approved equipment.
- 602.9.4.7** If considered necessary by the Engineer, the paving machines shall be provided with approved covers to protect the surface of the slab under construction from direct sunlight and rain or hot wind.
- 602.9.4.8** While the concrete is still plastic, its surface shall be textured by brush or tines as per the instructions of the engineer in compliance with Clause 602.9.11. The surface and edges of the slab shall be cured by the application of a sprayed liquid curing membrane in compliance with Clause 602.9.12. After the surface texturing, but
- 602.9.4.9** As soon as the side forms are removed, edges of the slabs shall be corrected wherever irregularities have occurred by using fine concrete composed of 1:1:2, cement: sand : coarse agg (10 mm down) with water cement ratio not more than 0.4 under the supervision of the Engineer.
- 602.9.4.10** If the requirement of Clause 902.4. for surface regularity fails to be achieved on two consecutive working days, then normal working shall cease until the cause of the excessive irregularity has been identified and remedied.

602.9.5 Construction by Slip Form Paver

- 602.9.5.1** The slip form paving train shall consist of a power machine which spreads, compacts and finishes the concrete in a continuous operation. The slip form paving machine shall compact the concrete by internal vibration and shape it between the side forms with either a conforming plate or by vibrating and oscillating finishing beams. The concrete shall be deposited without segregation in front of slip form paver across the whole width and to a height which at all times is in excess of the required surcharge. The deposited concrete shall be struck off to the necessary average and differential surcharge by means of the strike off plate or a screw auger device extending across the whole width of the slab. The equipment for striking-off the concrete shall be capable of being rapidly adjusted for changes of the average and differential surcharge necessitated by change in slab thickness or crossfall.
- 602.9.5.2** The level of the conforming plate and finishing beams shall be controlled automatically from the guide wires installed as per Clause 602.8 by sensors attached at the four corners of the slip form paving machine. The alignment of the paver shall be controlled automatically from the guide wire by at least one set of sensors attached to the paver. The alignment and level of ancillary machines for finishing, texturing and curing of the concrete shall be automatically controlled relative to the guide wire or to the surface and edge of the slab.

602.9.5.3 Slip-form paving machines shall have vibrators of variable output, with a maximum energy output of not less than 2.5 KW per metre width of slab per 300 mm depth of slab for a laying speed upto 1.5 m per minute. The machines shall be of sufficient mass to provide adequate reaction during spreading and paving operations on the traction units to maintain forward movements during the placing of concrete in all situations. Normal paving speed shall be maintained as per Clause 602.9.1.

602.9.5.4 If the edges of the slip formed slab slump to the extent that the surface of the top edge of the slab does not comply with the requirements of Clause 902.3, the work shall be stopped until such time as the Contractor can demonstrate his ability to slip form the edges to the required levels. The deficient edge shall be temporarily supported by a side form and the thickness deficiency shall be made good by adding fresh concrete to the newly formed edge and compacting.

602.9.5.5 Slip-form pavers with adequate width to pave the entire carriageway width in one go shall be employed unless specified in the Contract. In situations where full-width paving is not possible, paving in part widths may be permitted by the Engineer. Paving in part will be avoided, except in unavoidable circumstances. In case of part width paving, care shall be taken to ensure that while laying the next lane, bond between the remaining half length of tie bar or subsequently inserted tie bars and the newly laid concrete is adequately developed. Care shall be taken to avoid damage

602.9.5.6 In case paving in separate lanes is allowed, work on the adjacent lane shall be permitted when the previously paved lane is cured for at least 14 days and is in a position to bear the weight of paving machine. When the wheels or crawler tracks are to ply on the already paved surface, necessary precautions shall be taken by placing protective pads of rubber or similar material so that texture is not damaged. reasonably away from the edge to avoid damage to the previously laid slab.

602.9.5.7 Tube Floating

Upon the instructions of the Engineer, Contractor shall scrape the concrete surface when in plastic state with a 3 m long tube float fixed with a long and stable handle before texturing. Tube float shall be of an alloy steel tube of 50 to 60 mm diameter with a long and stable handle. The length of tube float shall preferably be longer than half the length of slab i.e., half the distance between two transverse contraction joints. This operation shall be done to minimise surface irregularity caused due to varied causes like frequent stoppages of work, surface deformation due to plastic flow etc. The tube float shall be placed at the centre of the slab parallel to longitudinal joint and pulled slowly and uniformly towards the edges. After the use of float tube, it shall be frequently cleaned before further use. The slurry removed shall be discarded. This activity shall be advanced laterally by providing an overlap of half the length of tube float. The removal of the cement slurry from the surface shall be sufficient enough such that the texture is formed on a firm surface and is more durable. This operation, however, shall be carried out after removing bleeding

602.9.6 Construction by Fixed Form Paver

602.9.6.1 The fixed form paving train shall consist of separate powered machines which spread, compact and finish the concrete in a continuous operation.

602.9.6.2 The concrete shall be discharged without segregation into a hopper spreader which is equipped with means for controlling its rate of deposition on to the sub-base. The spreader shall be operated to strike off concrete upto a level requiring a small amount of cutting down by the distributor of the spreader. The distributor of spreader shall strike off the concrete to the surcharge adequate to ensure that the vibratory compactor thoroughly compacts the layer. If necessary, poker vibrators shall be used adjacent to the side forms and edges of the previously constructed slab. The vibratory compactor shall be set to strike off the surface slightly high so that it is cut down to the required level by the oscillating beam. The machine shall be capable of being rapidly adjusted for changes in average and differential surcharge necessitated by changes in slab thickness or crossfall. The final finisher shall be able to finish the surface to the required level and smoothness as specified, care being taken to avoid bringing up of excessive mortar to the surface by over working.

602.9.7 Semi-mechanised Construction

Areas in which hand-guided methods of construction become indispensable shall be got approved by the Engineer in writing in advance. Such work may be permitted only in restricted areas in small lengths. Work shall be carried out by skilled personnel as per methods approved by the Engineer. The acceptance criteria regarding level, thickness, surface regularity, texture, finish, strength, of concrete and all other quality control measures shall be the same as in the case of machine laid work. Guidelines on the use of plants, equipment, tools, hauling of mix, compaction floating, straight edging, texturing, edging etc. shall be as per IRC:15.

602.9.8 Transition Slabs

At the interface of rigid and flexible pavement, at least 3 m long reinforced buried slab shall be provided to give a long lasting joint at the interface. The details shall be as given in IRC:15.

602.9.9 Anchor Beam and Terminal Slab Beam

RCC anchor beams shall be provided in the terminal slab adjoining bridge structures as per drawings and IRC:15.

602.9.10 The Treatment of Concrete Pavement on

The concrete pavement shall be taken over the culverts. At both ends of the culvert slab, a contraction joint shall be provided in the concrete pavement. Nominal reinforcement of 10 mm dia bars at 150 mm spacing in both directions shall be provided at 50 mm below the top of the slab. The reinforcement shall be stopped 50 mm short of the contraction joint. Such reinforcement shall also be provided in the next slab panel on either side.

602.9.11 Surface Texture

602.9.11.1 Tining

After final floating and finishing of the slab and before application of the liquid curing membrane, the surface of concrete slabs shall be textured either in the transverse direction (i.e., at right angles to the longitudinal axis of the road) or in longitudinal direction (i.e., parallel to the centreline of the roadway). The texturing

- a) **Transverse tining** : When the texturing is specified in transverse direction, a beam of at least 3 m length mounted with tines shall be moved in transverse direction to produce the texture. The grooves produced shall be at random spacing of grooves but uniform in width and depth. The spacing shall conform to a pattern shown below:

Random spacing in mm

10	14	16	11	10	13	15	16	11	10	21	13	10
----	----	----	----	----	----	----	----	----	----	----	----	----

The above pattern shall be repeated. Texturing shall be done at the right time such that the grooves after forming shall not close and they shall not get roughened. Swerving of groove patterns will not be permitted. The completed textured surface shall be uniform in appearance.

- b) **b) Longitudinal tining** : Longitudinal tining shall be done, if specified in the Contract. The texturing bridge shall be wide enough to cover the entire width of the carriageway but within 75 mm from the pavement edge. The centre to centre spacing between the tines shall be 18 to 21 mm. The width of tine texture shall be 3 mm and depth shall be 3 to 4 mm.

602.9.11.2 Brush Texturing

Alternatively on the instructions of the Engineer, the brush texturing shall be applied. The brushed surface texture shall be applied evenly across the slab in one direction by the use of a wire brush not less than 450 mm wide but wider brushes normally of 3 m length are preferred. The brush shall be made of 32 gauge tape wires grouped together in tufts placed at 10 mm centres. The tufts shall contain an average of 14 wires and initially be 100 mm long. The brush shall have two rows of tufts. The rows shall be 20 mm apart and the tufts in one row shall be opposite the centre of the gap between tufts in the other row. The brush shall be replaced when the shortest tuft wears down to 90 mm long.

The texture depth shall be determined by the Sand Patch Test as described in the Clause 602.12. This test shall be performed at least once for each day's paving and wherever the Engineer considers it necessary at times after construction as under:

Five individual measurements of the texture depth shall be taken at least 2 m apart anywhere along a diagonal line across a lane width between points 50 m apart along the pavement. No measurement shall be taken within 300 mm of the longitudinal edges of a concrete slab constructed in one pass.

Texture depths shall not be less than the minimum required depth when measurements are taken as given in Table 600-5 nor greater than an average of 1.25

Table 600-5 : Texture Depth

Time of Test		Number of Measurements	Required Texture Depth (mm)	
			Specified Value	Tolerance
1)	Between 24 hours and 7 days after the construction of the slab or until the slab is first used by vehicles	An average of 5 measurements	1	±0.25

2)	Not later than 6 weeks before the road is opened to traffic	An average of 5 measurements	1	+0.25 -0.35
----	---	------------------------------	---	----------------

After the application of the brushed texture, the surface of the slab shall have a uniform appearance.

Where the texture depth requirements are found to be deficient, the Contractor shall make good the texture across the full lane width over the length directed by the Engineer, by retexturing the hardened concrete surface in an approved manner.

602.9.12 Curing

602.9.12.1 Immediately after the surface texturing, the surface and sides of the slab shall be cured by the application of approved resin-based aluminized reflective curing compound which hardens into an impervious film or membrane with the help of mechanical sprayer.

602.9.12.2 The curing compound shall not react chemically with the concrete and the film or membrane shall not crack, peel or disintegrate within three weeks of application. Immediately prior to use, the curing compound shall be thoroughly agitated in its containers. The rate of spread shall be in accordance with the manufacturer's instructions checked during the construction of the trial length and subsequently whenever required by the Engineer. The mechanical sprayer shall incorporate an efficient mechanical device for continuous agitation and mixing of the compound during spraying. The curing compound shall be sprayed in two applications to ensure uniform spread.

Curing compounds shall contain sufficient flake aluminum in finely divided dispersion to produce a complete coverage of the sprayed surface with a metallic finish. The compound shall become stable and impervious to evaporation of water from the surface of the concrete within 60 minutes of application and shall be of approved type. The curing compounds shall have a water retention efficiency index not less than 90 percent in accordance with BS Specification No. 7542 or as per C-309-81 Type 2.

602.9.12.3 In addition to spraying of curing compound, the fresh concrete surface shall be protected for at least 3 hours by covering the finished concrete pavement with tents mounted on mobile trusses as described in Clause 602.7.2, during adverse weather conditions as directed by the Engineer. After three hours, the pavement shall be covered by moist hessian laid in two layers and the same shall then be kept damp for a minimum period of 14 days after which time the hessian may be removed. The hessian shall be kept continuously moist. All damaged/torn hessian shall be removed and replaced by new hessian on a regular basis.

602.9.12.4 The Contractor shall be liable at his cost to replace any concrete damaged as a result of incomplete curing or cracked on a line other than that of a joint as per procedure in IRC:SP:83.

602.10 Preparation and Sealing of Joint Grooves

602.10.1 General

All joints shall be sealed using sealants described in Clause 602.2.10.

602.10.2 Preparation of Joint Grooves for Sealing

602.10.2.1 Grooves are saw cut in the first instance just to provide minimum width (3-5 mm) to facilitate development of crack at joint locations, as shown in the drawing.

Subsequently before sealing, grooves are widened by sawing as per the dimensions in the drawing. Dimension of the grooves shall be controlled by depth/width gauge.

602.10.2.2 If rough arrises develop when grooves are made, they shall be ground to provide a chamfer approximately 5 mm wide. If the groove is at an angle upto 10° from the perpendicular to the surface, the overhanging edge of the groove shall be sawn or ground perpendicular. If spalling occurs or the angle of the former is greater than 10 degree, the joint sealing groove shall be sawn wider and perpendicular to the surface to encompass the defects upto a maximum width, including any chamfer, of 20 mm for transverse joints and 10 mm for longitudinal joints. If the spalling cannot be so eliminated then the arises shall be repaired by an approved thin bonded arrises repair using cementitious/epoxy mortar materials.

602.10.2.3 All grooves shall be cleaned of any dirt or loose material by air blasting with filtered, oil-free compressed air. The Engineer shall instruct cleaning by pressurized water jets. Depending upon the requirement of the sealant manufacturer, the sides of the grooves shall be sand blasted to increase the bondage between sealant and concrete.

602.10.2.4 The groove shall be cleaned and dried at the time of priming and sealing. If sand blasting is recommended by the supplier, the same shall be carried out.

602.10.2.5 Before sealing the temporary seal provided for blocking the ingress of dirt, soil etc., shall be removed. A highly compressible heat resistant paper-backed debonding strip as per drawing shall be inserted in the groove to serve the purpose of breaking the bond between sealant and the bottom of the groove and to plug the joint groove so that the sealant may not leak through the cracks. The width of debonding strip shall be more than the joint groove width so that it is held tightly in the groove. In the case of longitudinal joints, heat resistant tapes may be inserted to block the leakage through bottom of the joint where hot poured sealant is used. When cold sealant is used a debonding tape of 1.0-2.0 mm thickness and 6 to 8 mm width shall be inserted to plug the groove so that the sealant does not enter in the initially cut groove.

602.10.3 Sealing with Sealants

602.10.3.1 When sealants are applied, an appropriate primer shall also be used if recommended by the manufacturer and it shall be applied in accordance with his instructions. The sealant shall be applied within the minimum and maximum drying times of the primer recommended by the manufacturer. Priming and sealing with applied sealants shall not be carried out when the naturally occurring temperature in the joint groove to be sealed, is below 7°C.

- 602.10.3.2** If hot applied sealant is used it shall be heated and applied from a thermostatically controlled, indirectly heated preferably with oil jacketed melter and pourer having recirculating pump and extruder. For large road projects, sealant shall be applied with extruder having flexible hose and nozzle. The sealant shall not be heated to a temperature higher than the safe heating temperature and not for a period longer than the safe heating period, as specified by the manufacturer. The dispenser shall be cleaned out at the end of each day in accordance with the manufacturer's recommendations and reheated material shall not be used. The Movement Accomodation Factor of the sealant shall be more than 10 percent.
- 602.10.3.3** Cold applied sealants with chemical formulation like polysulphide/ polyurethane/ silicone as per IRC:57 shall be used These shall be mixed and applied within the time limit specified by the manufacturer. If primers are recommended they shall be applied neatly with an appropriate brush. The Movement Accomodation Factor shall be more than 25 percent.
- 602.10.3.4** The sealants applied at contraction phase of the slabs would result in bulging of the sealant over and above the slab. Therefore, the Contractor in consultation with the Engineer, shall establish the right temperature and time for applying the sealant. Thermometer shall be hung on a pole at the site for facilitating control during the sealing operation.
- 602.10.3.5** Sealant shall be applied, slightly to a lower level than the slab with a tolerance of 3 ± 1 mm.
- 602.10.3.6** During sealing operation, it shall be seen that no air bubbles are introduced in the sealant either by vapours or by the sealing process. The sealant after pouring, shall be allowed to cure for 7 days or for a period as per instructions of manufacturers.

602.10.3 Trial Length

- 602.11.1** The trial shall be constructed at least one month in advance of the proposed start of concrete paving work. At least one month prior to the construction of the trial length, the Contractor shall submit for the Engineer's approval a detailed method statement giving description of the proposed materials, plant, equipment and construction methods. All the major equipments like paving train, batching plant, tipping trucks etc., proposed in the construction are to be approved by the Engineer before their
- 602.11.2** The Contractor shall demonstrate the materials, plant, equipment and methods of construction that are proposed for concrete paving, by first constructing a trial length of slab, at least 100 m long for mechanised construction and at least 50 m long hand guided methods. The width of the trial section shall be the full carriageway width as shown in the drawings. If the first trial is unsatisfactory, the Contractor shall have to demonstrate his capability to satisfactorily construct the pavement in subsequent trials.
- 602.11.3** The trial length shall be constructed in two parts over a period comprising at least part of two separate working days, with a minimum of 50 m constructed each day for mechanised construction and a minimum of 25 m on each day for hand guided construction. The trial length shall be constructed at a paving rate which is proposed for the main work.
- 602.11.4** Transverse joints including expansion joint and longitudinal joint that are proposed in the main work shall be constructed and assessed in the trial length.

602.11.5 The trial length shall comply with the Specifications in all respects including the test requirement of Table 900-6 with the following additions.

602.11.5.1 Surface Levels and Regularity

- a) In checking for compliance with Clause 902.3 the levels shall be taken at intervals at the locations specified in this Clause along any line or lines parallel to the longitudinal centre line of the trial length.
- b) The maximum number of permitted irregularities of pavement surface shall comply with the requirements of Clause 902.4. Shorter trial lengths shall be assessed pro-rata based on values for a 300 m length.

602.11.5.2 Joints

- a) Alignment of dowel bars shall be inspected in any two consecutive transverse joints in a trial length construction by removing the fresh concrete in a width of 0.5 m on either side of the joint. The joint pit shall be refilled with freshly prepared concrete, after inspection. Alternatively, it can be tested by suitable device like MIT SCAN with the permission of the Engineer. If the position or alignment of the dowel bars at one of these joints does not comply with the requirements and if that joint remains the only one that does not comply after the next 3 consecutive joints of the same type have been inspected, then the method of placing dowels shall be deemed to be satisfactory. In order to check sufficient joints for dowel bar alignment without extending the trial length unduly joints may be constructed at more frequent joint intervals than the normal spacing required in trial slabs.
- b) if there are deficiencies in the first expansion joint that is constructed as a trial, the next expansion joint shall be a trial joint. Should this also be deficient, further trial of expansion joints shall be made as part of the trial length which shall not form part of the permanent works, unless agreed by the Engineer.

602.11.5.3 Density

In-situ density in trial length shall be assessed as described in Clause 903.5.2.2 from at least 3 cores drilled from each part of the trial length when the concrete is not less than 7 days old. Should any of the cores show honey-combing in the concrete, the trial length shall be rejected and the construction in the main carriageway shall not be permitted until further trials have shown that modification has been made which would result in adequate compaction.

602.11.5.4 Strength

Minimum of thirty (30) beams for flexural strength and thirty (30) cubes for compressive strength shall be prepared from the concrete delivered in front of the paving plant. Each pair of beams and cubes shall be from the same location/batch but different sets of beams and cubes shall be from different locations/batches. Compressive and flexural strength shall be tested after 28 days water curing in the laboratory.

At the age of 28 days, thirty (30) cores with diameter 150 mm shall be cut from the pavement slab when the thickness of concrete pavement is more than 300 mm. In case the concrete pavement thickness is less than 300 mm, the dia of core shall be 100 mm. The cores shall be suitably cut at both ends to provide a specimen of plain surface on both ends. The dia to height ratio of core shall be 1 to 2. For cylindrical specimen of PQC of dia 150 mm, the variation in dia shall be ± 0.5 mm, a tolerance on height shall be ± 1 mm for a specimen of height 300 mm or more. For cylindrical specimen of dia 100 mm, the variation in dia shall be ± 0.3 mm, and a tolerance on height shall be ± 1 mm for a specimen height of 200 mm. The compressive strength test shall be conducted as per IS:516.

Concrete in the member represented by a core test shall be considered acceptable, if the average equivalent cube strength of the cores is equal to at least 85 percent of the cube strength (characteristic strength) of the grade of the concrete specified for the corresponding age of 28 days and no individual core has a strength less than 75 percent.

602.11.6 Approval and Acceptance

602.11.6.1 Approval of the materials, plant, equipment and construction methods shall be given when the trial length complies with the Specifications. The Contractor shall not proceed with normal working until the trial length has been approved. If the Engineer does not notify the Contractor of any deficiencies in any trial length within 7 days after the completion of that trial length, the Contractor may assume that the trial length, and the materials, plant, equipment and construction methods adopted are acceptable, provided that the 28 days strength of cubes and cores extracted from trial length meet the requirement of the Specified strength.

602.11.6.2 When approval has been given, the materials, plant, equipment and construction methods shall not thereafter be changed, except for normal adjustments and maintenance of plant, without the approval of the Engineer. Any changes in materials, plant, equipment, and construction methods shall entitle the Engineer to require the Contractor to lay a further trial length as described in this Clause to demonstrate that the changes will not adversely affect the permanent works.

602.11.6.3 Trial lengths which do not comply with the Specifications, with the exception of areas which are deficient only in surface texture and which can be remedied in accordance with Clause 602.9.11.6 shall be removed immediately upon notification of deficiencies by the Engineer and the Contractor shall construct a further trial

602.11.7 Inspection of Dowel Bars

602.11.7.1 Compliance with Clause 602.6.5. for the position and alignment of dowel bars at contraction and expansion joints shall be checked by measurements relative to the side forms or guide wires.

602.11.7.2 When the slab has been constructed, the position and alignment of dowel bars and any filler board shall be measured after carefully exposing them in the plastic concrete across the whole width of the slab. When the joint is an expansion joint, the top of the filler board shall be exposed sufficiently in the plastic concrete to permit measurement of any lateral or vertical displacement of the board. During the course of normal working, these measurements shall be carried out in the pavement section at the end of days work by extending slab length by 2 m. After sawing the transverse joint groove, the extended 2 m slab shall be removed carefully soon after concrete has set to expose dowels over half the length. These dowels can be tested for tolerances. This joint shall be treated as construction joint. The position of dowel bars in any type of transverse joint ie, contraction, construction or expansion can alternatively be tested by suitable device like MIT SCAN with the permission of the

602.11.7.3 If the position and alignment of the bars in a single joint in the slab is unsatisfactory then the next two joints shall be inspected. If only one joint of the three is defective, the rate of checking shall be increased to one joint per day until the Engineer is satisfied that compliance is being achieved.

602.11.7.4 After the dowel bars have been examined, the remainder of the concrete shall be removed over a width of 500 mm on each side of the line of the joint and reinstated to the satisfaction of the Engineer. The dowels shall be inserted on both sides of the 1 m wide slab by drilling holes and grouting with epoxy mortar. Plastic sheath as per Clause 602.6.5.5 shall be provided on dowels on one of the joints. The joint groove shall be widened and sealed as per Clause 602.10.

602.11.8 Inspection of Tie Bars

To check the position of the tie bars, one metre length 0.5 m on either side of the longitudinal joint shall be opened when the concrete is green (within 20 to 30 minutes of its laying). The pit shall be refilled with the fresh concrete of same mix after checking.

602.12 Measurement of Texture Depth – Sand Patch Method

602.12.1 The following Apparatus shall be used:

- i) A cylindrical container of 25 ml internal capacity;
- ii) A flat wooden disc 64 mm diameter with a hard rubber disc, 1.5 mm thick, next to one face, the reverse face being provided with a handle;
- iii) Dry natural sand with a rounded particle shape passing a 300 micron IS sieve and retained on a 150 micron IS sieve.

602.12.2 Method

The surface to be measured shall be dried, any extraneous mortar and loose material removed and the surface swept clean using a wire brush both at right angles and parallel to the carriageway. The cylindrical container shall be filled with the sand, tapping the base 3 times on the surface to ensure compaction, and striking off the sand level with the top of the cylinder. The sand shall be poured into a heap on the surface to be treated. The sand shall be spread over the surface, working the disc with its face kept flat in a circular motion so that the sand is spread into a circular patch with the surface depressions filled with sand to the level of peaks.

602.12.3 The diameter of the patch shall be measured to the nearest 5 mm. The texture depth of concrete surface shall be calculated from $31000/(D \times D)$ mm where D is the diameter of the patch in mm.

602.12.4 Measurement of Texture Depth - Tining

602.12.4.1 The following apparatus shall be used :

- i) Tire Tread Depth Gauge
A stainless steel tire tread depth gauge with graduations with least count of 1.0 mm. The gauge end may be modified to measure depth of tine texture.
- ii) A stainless steel caliper to measure spacing of tines. If necessary the caliper may be modified to measure the spacing and width of tine texture. The gauge shall be used after making necessary calibration.
- iii) Wire brush
- iv) Corborundum stone
- v) Steel straight edge to remove snots etc. sticking to the surface. The straight edge may be of 6 x 25 x 300 mm size.

602.12.4.2 Test Section

A unit of testing shall be 75 m per lane. If the length of construction is less than 75 m it shall be taken as one unit.

602.12.4.3 Test Procedure

In each 75 m section, along the diagonal line, 10 points shall be selected for making checks of depth, width and spacing of tine grooves. The surface where tests are to be conducted shall be cleared carefully with a wire brush or a steel straight edge or using a corborundum plate to remove any upward projection of concrete. When the base plate of the gauge is in contact with the concrete surface, the gauge shall be pressed to the bottom of groove and the depth shall be measured and recorded at this location. At the same location, the spacing of tines shall be measured to verify whether the pattern recommended in Clause 602.9.11.1 is complied or not.

The average of depth and width at 10 locations shall be calculated and recorded to the nearest 1 mm. The spacing of spectrum measured at 10 locations shall be recorded separately.

602.12.5 602.12.5 The average depth shall be 3 to 4 mm. When the depth is less than 2.5 mm and in excess of 4.5 mm, the Contractor shall stop concreting till he corrects his tine brush or replaces it. The sensors associated with work shall be again calibrated to achieve the required texture. The textured groove less than 2.5 mm shall be re-grooved using concrete saw at the cost of Contractor. Variation in texture width in the range of $3+1$ mm and $3 - 0.5$ mm will be acceptable. If the variation of width is in excess of this range, the Contractor shall stop work and correct the brush and technique. When the spacing of spectrum is not satisfactory, the Contractor shall replace the entire brush.

602.13 Opening to Traffic

No vehicular traffic shall be allowed to ply on the finished surface of a concrete pavement within a period of 28 days of its construction and until the joints are permanently sealed and cured. The road may be opened to regular traffic after completion of the curing period of 28 days and after sealing of joints is completed

including the construction of shoulder, with the written permission of the Engineer.

602.14 Acceptance Criteria in Quality and Distress

- i) **Tolerances for Surface Regularity, Level, Thickness and Strength:** The tolerances for surface regularity, level, thickness and strength shall conform to the requirements given in Clause 903.5. Control of quality of materials and works shall be exercised by the Engineer in accordance with Section 900.
- ii) **Tolerances in Distress :** The acceptance criteria with regard to the types of distresses in rigid pavement shall be as per IRC:SP-83. "Guidelines for Maintenance, Repair and Rehabilitation of Cement Concrete Pavements". The cracks (of severity rating not more than 2) which may appear during construction or before completion of Defect Liability Period shall be acceptable with suggested treatments as given in IRC:SP-83.

Cement Concrete Pavement slabs having cracks of severity rating more than 2 i.e. cracks of width more than 0.5 mm for single discrete cracks, multiple and transverse cracks and cracks of width more than 3 mm in case of longitudinal cracks and of depth more than half of the concrete pavement slabs, shall be removed and replaced as per IRC:SP-83.

602.15 Measurements for Payment

602.15.1 Cement Concrete pavement shall be measured as a finished work in cubic metres of concrete placed based on the net plan area and thickness as measured in accordance with Clause 602.15.2.

602.15.2 The finished thickness of concrete for payment on volume basis shall be computed in the manner described in Clause 113.3 with the following modifications:

- i) The levels shall be taken before and after construction at grid points 5 m centre to centre longitudinally in straight as well as at curves.
- ii) A day's work is considered as a 'lot' for calculating the average thickness of the slab. In calculating the average thickness, individual measurements which are in excess of the specified thickness by more than 10 mm shall be considered as the specified thickness plus 10 mm.

602.15.3 Individual areas deficient by more than 10 mm shall be verified by the Engineer by ordering core cutting and if in his opinion the deficient areas warrant removal, they shall be removed and replaced with concrete of the thickness shown on the plans.

602.16 Rate

602.16.1 The Contract unit rate for the construction of the cement concrete pavement shall be payment in full for carrying out the operations required for the different items of the work as per these Specifications including full compensation for all labour, tools, plant, equipment, providing all materials i.e. aggregates, dowel bars, tie bars, PVC membrane, cement, stabilizers (lime, cements or any other stabilizers approved by the Engineer), storing, mixing, transportation, placing, compacting, finishing, curing, testing, all royalties, fees, rents where necessary, all leads and lifts and incidentals to complete the work as per Specifications.

The unit rate shall all include the full costs of construction, expansion, contraction and longitudinal joints including joint filler, sealant, primer, debonding strip and all

other operations for completing the work. The construction and testing of trial length shall be included in the contract unit rate for the pavement and shall not be paid separately.

- 602.16.2** Where the average thickness for the lot is deficient by the extent shown in Table 600-6, payment for cement concrete pavement shall be made at a price determined by adjusting the contract unit price as per Table 600-6.

Table 600-6 : Payment Adjustment for Deficiency in Thickness

Deficiency in the Average Thickness of Day's Work	Percent of Contract Unit Price Payable
Up to 5 mm	100
6-10 mm	87

- 602.16.3** No additional payment shall be made for the extra thickness of the slab than shown on the drawings.

Item No 25.

Providing and fixing pre-cast Rubber Dye / steel Dye inter locking concrete block 60mm thick with grade of concrete M300 pneumatic compressed / vibrated mechanically and as per approved design Confirming to IS 15658 : 2006 including 35 mm Sand layer for levelling and filling the joint with sand in proper line and level as per guidelines of IRC : SP 63-2018 etc. Complete.

General

This work shall consist of providing and laying **precast Rubber dye / steel dye inter locking concrete block 60 mm thick with grade of concrete M-300 pneumatic compressed / vibrated mechanically and as per approved design confirming to IS 15658 : 2006 including 35 mm thick layer** of sand of the shape and dimensions shown on the drawings and conforming to these specifications or as approved by the Engineer in charge.

1. MATERIAL

Water shall conform to M-1. Cement shall conform to M-3.

1. Precast Rubber dye / steel dye inter locking concrete block

Precast Rubber dye / steel dye inter locking concrete block shall be of approved size brand and make as approved by Engineer in charge.

- 1.1** The size shape and design of **precast Rubber dye / steel dye inter locking concrete block** shall generally be as per manufacturers product or as directed by the Engineer in charge and Architect.
- 1.2** The **precast Rubber dye / steel dye inter locking concrete block** shall satisfy the tests as regards compress strength transverse strength resistance to wear and water absorption.
- 1.3** The colour size shape and design of the **precast Rubber dye / steel dye inter locking concrete block** shall be directed by Engineer or Architect.
- 1.4** The **precast rubber dye / steel dye inter locking concrete block** shall be of best quality as approved by the Engineer In charge. They shall be flat and true to shape. They shall be free from cracks, crazing spots, chipped edges and corners. The glazing shall be of uniform shade.

2. SAND

- 2.1** Sand shall be natural sand, clean well graded, hard strong durable and gritty particular free from immures amounts of dust, clay, kankar modules.
- 2.2** For masonry works sand shall confirm to the requirements of IS: 2116.
- 2.3** For plain and reinforced cement concrete (PCC and RCC) or pre stressed concrete (PSC) works fine aggregates shall consist of clean, hard strong and durable prices of crushed stone, crushed gravel or suitable combination of natural sand crushed stone or gravel, They shall not contain dust lumps soft or flaky materials mica or other deleterious materials in such quantities as to reduce the strength and durability of concrete, or to attack the embedded steel. Motorized sand washing machines should be used to remove impurities from sand. Fine aggregate having positive alkali-silica reaction shall not be used. All fine aggregates shall conform to IS L 383 and tests for conformity shall be carried out as per IS : 2386 (Part I to VIII) The contractor shall submit to the Engineer in charge the entire information indicated in Appendix A of IS : 383. The fineness modulus

of fine aggregate shall neither be less than 2.00 nor greater than 3.5.

2.4 Sand fine aggregates for structural concrete shall conform to the following grading requirements as shown in the table below.

2.5 Fine Sand: The fineness module shall not exceed 1.0 the sieve analysis of fine sand be as under:

IS. Sieve Designation	% by wt. passing		
	Zone I	Zone II	Zone III
10 mm	100	100	100
4.75 mm	90-100	90-100	90-100
2.36 mm	60-95	75-100	85-100
1.18 mm	30-70	55-90	75-100
600 MC	15-34	35-59	60-79
300 MC	5-20	8-30	12-40
150 MC	0-10	0-10	0-10

☞ **Coarse Sand:** The fineness modules of coarse sand shall not be less than 2.5 and shall not exceed 3.0. The sieve analysis of coarse sand be as under:

Item No 26.

Scarifying gravelled macadam or bitumen macadam surface 6 cm to 10 cm.depth including stacking useful materials on road side and disposing off remaining stuff.

1. The layer of the existing layer metalling / bituminous layer shall excavated for all depth as directed by Engineer-in-charge and shall be screened on site of work. Stacking of 75% of metal obtained from screening shall be done by filling in the standard steel boxes of 2m x 1.5 m x 0.5 mt. size which shall be supplied by department if available on rent, otherwise contractor shall make his own arrangements. No deductions for voids shall be made from the gross measurements. Where any doubt exist as to whether the quantity of stacks of metal in any hectometer is not confirming with cubical content of the standard pharas (2m x 15 mt. x 0.5 mt.) shall be got corrected by the contractor if so ordered by the Engineer-in-charge for which no extra payment shall be claimed by the contractor. If the quantity of metal in -any stack in a particular hectometer is found to be less then the standard measurements viz. 1.5 cmt. the entire collection in the hectometre shall be paid on the basis of the quantity so found. Regular stacks shall be done by the contractor on a tairiy level ground. Stacking of the metal shall be done in a manner as directed by the Engineer-in-charge.
2. The remaining material except 75% of metal obtained from screening process shall be used in embankment with all lead and lift. It shall be directly deposited at the required location in specified layers. No handling or conveyance charges shall be paid if the materials is temporarily deposited else where and subsequently convey to site of deposition. The sequence of operations should be arranged properly. Material not required for any use whatsoever may be disposed off by the contractor at his own cost in manner approved by the Engineer-in-charge. The material utilised in the embankment will be deducted from the net quantity of earthwork in embankment arrived at within the chainage measured.
3. The payment shall be made on **Sq.mt.** basis, the contractor shall maintain all stacks in regular and proper size till the whole materials shall not be measured and finally accepted by the department. The spreading of materials shall not be allowed till the materials are fully stacked and completed kilometer wise.
4. The rate includes the cost of scarifying macadam, screening, depositing, conveyance with all lead and lift, filling the boxes including all labour, tools, equipments and all other incidental expenses.

Item No 27.

Providing laying and spreading granular materials available from existing crust and adding fresh machine crushed material in required proportion so as to have mix material gradation of GSB grade I/II/III, mixing in place with rotavator and grading with mortar grader at OMC and compacted with vibratory roller to achieve desired density etc. complete.

401.0 GRANULAR SUB-BASE**401.1 Scope**

This work shall consist of laying and compacting well-graded material on prepared subgrade in accordance with the requirements of these Specifications. The material shall be laid in one or more layers as sub-base or lower sub-base and upper sub-base (termed as sub-base hereinafter) as necessary according to lines, grades and cross-sections shown on the drawings or as directed by the Engineer.

401.2 Materials

- 401.2.1** The material to be used for the work shall be natural sand, crushed gravel, crushed stone, crushed slag, or combination thereof depending upon the grading required. Use of materials like brick metal, Kankar and crushed concrete shall be permitted in the lower sub-base. The material shall be free from organic or other deleterious constituents and shall conform to the gradings given in Table 400-1 and physical requirements given in Table 400-2. Gradings III and IV shall preferably be used in lower sub-base. Gradings V and VI shall be used as a sub-base-cum-drainage layer. The grading to be adopted for a project shall be as specified in the Contract. Where the sub-base is laid in two layers as upper sub-base and lower sub-base, the thickness of each layer shall not be less than 150 mm.
- 401.2.2** If the water absorption of the aggregates determined as per IS:2386 (Part 3) is greater than 2 percent, the aggregates shall be tested for Wet Aggregate Impact Value (AIV) (IS:5640). Soft aggregates like Kankar, brick ballast and laterite shall also be tested for Wet AIV (IS:5640).

Table-400-1- Grading for Granular Sub-base materials ::

Sieve Designation	Percent by Weight Passing the IS Sieve					
	Grading I	Grading II	Grading III	Grading IV	Grading V	Grading VI
75.00mm	100	--	--	--	100	--
53.00mm	80-100	100	100	100	80-100	100
26.5mm	55-90	70-100	55-75	50-80	55-90	75-100
9.50mm	35-65	50-80	--	--	35-65	55-75
4.75mm	25-55	40-65	10-30	15-35	25-50	30-55
2.36mm	20-40	30-50	--	--	10-20	10-25
0.85mm	--	--	--	--	2-10	--
0.425mm	10-15	10-15	--	--	0-5	0-8
0.075mm	<5	<5	<5	<5	--	0-3

Table 400-2-Physical Requirements for Materials for Granular sub-base

Aggregate Impact Value (AIV)	IS-2396 (Part-4-) or I.S. 5640	40% Maximum
Liquid Limits	IS-2720 (Part-5-)	Maximum 25
Plasticity Index	IS-2720 (Part-5-)	Maximum 06
CBR at 98% dry density (at IS2720-Part-8-)	IS-2720 (Part-5-)	Minimum 30 unless otherwise specified in the contract

401.3 Construction Operations ::

401.3.1. Preparation of subgrade : Immediately prior to the laying of sub-base, the subgrade already finished to Clause 301 or 305 as applicable shall be prepared by removing all vegetation and other extraneous material, lightly sprinkled with water if necessary and rolled with two passes of 80 -100 kN smooth wheeled roller.

401.4.2. Spreading and compacting :

The sub-base material of grading specified in the Contract and water shall be mixed mechanically by suitable equipment with provisions for controlled addition of water and mechanical mixing. So as to ensure homogenous and uniform mix. The required water content shall be determined in accordance with IS 2720 (Part 8) The mix shall be spread on the prepared subgrade with the help of a motor grader of adequate capacity, its blade having hydraulic controlled suitable for initial adjustment and for maintaining the required slope and grade during the operation or other means as approved by the Engineer.

Moisture content of the mix shall be checked in accordance with IS-2720 (part 2) and suitably adjusted so that at the time of compaction it is from 1 to 2 percent below the optimum moisture content.

Immediately after spreading the mix, rolling shall be done by an approved roller. If the thickness of the compacted layer does not exceed 100 mm, a smooth wheeled roller of 80 to 100 kN weight may be used. For a compacted single layer, up to 200 mm the compaction shall be done with the help of a vibratory roller of minimum 80 to 100 kN static weight capable of achieving the required compaction. Rolling shall commence at the lower edge and proceed towards the upper edge longitudinally for portions having unidirectional cross fall or on super-elevation. For carriageway having cross fall on both sides, rolling shall commence at the edges and progress towards the crown.

Each pass of the roller shall uniformly overlap not less than one-third of the track made in the preceding pass. During rolling, the grade and cross fall (camber) shall be checked and any high spots or depressions which become apparent, corrected by removing or adding fresh material. The speed of the roller shall not exceed 5 km per hour.

Rolling shall be continued till the density achieved is at least 98% of the maximum dry density for the material determined as per IS 2720 (Part-8-). The surface of any layer of materials on completion of compaction shall be well closed, free from movement under compaction equipment and from compaction planes, ridges, cracks or loose materials. All loose segregated or otherwise defective area shall be made good to the full thickness of layer and re-compacted.

401.4 Surface Finish and Quality Control of Work

The surface finish of construction shall conform to the requirements of Clause 902. Control on the quality of materials and works shall be exercised by the Engineer in accordance with Section 900.

401.5 Arrangements for Traffic

During the period of construction, arrangement of traffic shall be maintained in accordance with Clause 112.

401.6 Measurements for Payment

Granular sub-base shall be measured as finished work in position in cubic metres.

The protection of edges of granular sub-base extended over the full formation as shown in the drawing shall be considered incidental to the work of providing granular sub-base and as such no extra payment shall be made for the same.

401.7 Rate

The Contract unit rate for granular sub-base shall be payment in full for carrying out the required operations including full compensation for :

- (i)** Malting arrangements for traffic to Clause 112 except for initial treatment to verges, shoulders and construction of diversions;
- (ii)** Supplying all materials to be incorporated in the work including all royalties, fees, rents where necessary and all leads and lifts;
- (iii)** All labour, tools, equipment and incidentals to complete the work to the Specifications;
- (iv)** Carrying out the work in part widths of road where directed; and
- (v)** Carrying out the required test for quality control.

401.8 Measurements for payment ::

Granular sub-base shall be measured as finished work in provision in Cubic meter. The protection of edges of granular sub-base extended over the full formation as shown in the drawing shall be considered incidental to the work of providing granular sub-base and as such no Extra Payment shall be made for the same.

- (vi) The payment shall be made on Cubic meter basis with a average area method.**

Item No 28.

Providing and laying 20mm thick Mix Seal Surface with tack coat @ 2.0 kg/10 sqm using B.T. chips as per M.O.R.T. & H. gradation type A and specification with VG-30 for mixing @ 51.00 Kg / M.T. i.e. 5.1 % of total weight of mix using including heating and mixing the aggregate and asphalt in continuous of drum mix plant and hot laid process spreading the same by paver finisher and consolidation with roller as per M.O.R.T. & H. specification to achieve desire density, including providing all materials equipments, tools and plants, fire wood, oil, kerosene, labour charges etc.

512.1. Scope

512.1.1 This work shall consist of the preparation, laying and compaction of a close graded premix surfacing material of 20 mm thickness composed of graded aggregates premixed with a bituminous binder on a previously prepared surface in accordance with the requirements of these Specifications, to serve as a wearing course.

512.1.2. Close graded premix surfacing shall be of Type A or Type B as specified in the Contract

512.2. Materials

512.2.1. Binder : The binder shall be bitumen of a suitable viscosity grade VG-30 as specified in the Contract, or as directed by the Engineer, and satisfying the requirements of IS: 73.

Viscosity Grade (VG) Bitumen Specification as per IS 73 : 2006

Characteristics	VG - 10	VG-20	VG-30	VG-40
Absolute Viscosity 60°C, poises, min	800	1600	2400	3200
Kinematics Viscosity 135°C CSI, min	250	300	350	400
Flash point, C, min	220	220	220	220
Solubility in trichloroethylene, % min	99.0	99.0	99.0	99.0
Penetration at 25°C	80-100	60-80	50-70	40-60
Softening point, C min	40	45	47	50
Test on residue from thin film oven test / RTFOT:				
(A) Viscosity ration at 60°C, max	4.0	4.0	4.0	4.0
(B) Ductility at 25°C, cm, min after thin film over test	75	50	40	25

512.2.2 Coarse aggregates : 504.2.2.1. The aggregates shall consist of crushed stone, crushed gravel/shingle or other stones. They shall be clean, strong, durable, of fairly cubical shape and free from disintegrated pieces, organic or other deleterious matter and adherent coating. If crushed shingle/gravel is used, not less than 90 per cent by weight of the gravel/shingle pieces retained on 4.75 mm sieve shall have at least two fractured faces. The aggregates shall preferably be hydrophobic and of low porosity. If hydrophilic aggregates are to be used, the bitumen shall preferably be treated with anti-stripping agents of approved quality in suitable dose as per Appendix-5. The aggregates shall satisfy the physical requirements set forth in Table 500-3.

TABLE 500-3. PHYSICAL REQUIREMENTS OF AGGREGATES FOR BITUMINOUS MACADAM

Sr. No.	Test	Test Method	Requirement
1	Log Angeles Abrasion Value*	IS 2386 (Part-4)	40 percent Maximum
2	Aggregates Impact Value*	IS 2486 (Part-4)	30 percent Maximum

3	Flakiness and Elongation	IS 2386 (Part-1)	30 percent Maximum
4	Coating and Stripping of Bitumen Aggregate mixtures.	I.S. 6241	Minimum retained coating 95 per cent.
5	5 Soundness (1) Loss with Sodium Sulphate 5 cycles. (2) Loss with Sodium Magnesium 5 cycles.	IS 2386 (Part-V)	12 percent Maximum 18 percent Maximum
6	Water Absorption	IS 2386 (Part-3)	1 percent Maximum.

*** Aggregates may satisfy requirements for either of the two tests.**

Note : If crushed slag is used, Clause 404.2.3 shall apply.

512.2.3 Fine aggregates : The fine aggregates shall consist of crushed rock quarry sands, natural gravel / sand or a mixture of both. These shall be clean, hard, durable, un-coated, mineral particles, dry and free from injurious, soft or flaky particles and organic or deleterious

512.2.4 Aggregate gradation.: The coarse and fine aggregates shall be so graded or combined as to conform to one or the other grading shown in Table 500-26, as specified in the contract.

TABLE 500-26. AGGREGATE GRADATION

IS Sieve Designation (mm)	Cumulative percent by weight of Total aggregate passing	
	Type A	Type B
13.2 mm	--	100
11.2 mm	100	88 - 100
5.6 mm	52 - 88	31 - 52
2.8 mm	14 - 38	5 - 27
0.090mm	0 - 5	0 - 5

512.2.5. Proportioning of materials: The total quantity of aggregates used for Type A or B close-graded premix surfacing shall be 0.27 cubic metre per 10 square metre area. The quantity of binder used for premixing in terms of straight-run bitumen shall be 22.0 kg and 19.40 kg per 10 Square metre area for Type A and Type B surfacing respectively.

512.3. Construction Operations

501.5.1. Weather and seasonal limitations: Laying shall be suspended while free standing water is present on the surface to be covered or during rain, fog and dust storms. After rain, the bituminous surface, prime or tack coat, be blown off with a high pressure air jet to remove excess moisture or the surface left to dry before laying shall start Laying of bituminous mixtures shall not be carried out when the air temperature at the surface on which it is to be laid is below 100C or when the wind speed at any temperature exceeds 40 km/h at 2m height unless specifically approved by the Engineer.

501.5.2. Cleaning of surface: The surface on which the bituminous work is to be laid shall be cleaned of all loose and extraneous matter by means of a mechanical broom or any other approved equipment / method as specified in the contract. The use of a high pressure air jet from a compressor to remove dust or loose matter shall be available fall time on the site, unless otherwise specified in the Contract.

501.5.3. Spreading: Except in areas where a mechanical paver cannot access, bituminous materials shall be spread, leveled and tamped by an approved self-propelled paving machine. As soon as possible after arrival at site, the materials shall be supplied continuously to the paver and laid without delay.

The rate of delivery of material to the paver shall be regulated to enable the paver to operate continuously. The travel rate of the paver and its of operations, shall be adjusted to ensure an even and uniform flow of bituminous material across the screed, free from dragging, tearing and segregation of the material. In areas with restricted space where a mechanical paver cannot be used, the material shall be spread, raked and levelled with suitable hand tools by experienced staff, and compacted to the satisfaction of the Engineer.

The minimum thickness of material laid in each paver pass shall be in accordance with the minimum values given in the relevant parts of these Specifications. When laying binder course or wearing course approaching an expansion joint of a structure, machine laying shall stop 300mm short of the joint. The remainder of the pavement up to the joint and the corresponding area beyond it shall be laid by hand, and the joint or joint cavity shall be kept clear of surfacing material.

Bituminous material with a temperature greater than 1450C shall not be laid or deposited on bridge deck waterproofing systems, unless precautions against heat damage have been approved by the Engineer.

Hand placing of pre-mixed bituminous materials shall only be permitted in the following circumstances:

- (i) For laying regulating courses of irregular shape and varying thickness.
- (ii) In confined spaces where it is impracticable for a paver to operate.
- (iii) For footways.
- (iv) At the approaches to expansion joints at bridges, viaducts or other structures.
- (v) For laying mastic asphalt in accordance with Clause 515.
- (vi) For filling of potholes.
- (vii) Where directed by the Engineer.

Manual spreading of pre-mixed wearing course material or the addition of such material by hand spreading to the paved area, for adjustment of level, shall only be permitted in the following circumstances:

- (i) At the edges of the layers of material and at gullies and manholes.
- (ii) At the approaches to expansion joints at bridges, viaducts or other structures.
- (iii) As directed by the Engineer.

501.5.4. Cleanliness and overlaying: Bituminous material shall be kept clean and uncontaminated. The only traffic permitted to run on bituminous material to be overlaid shall be that engaged in laying and compacting the next course or, where a binder course is to be sealed or surface dressed, that engaged on such surface treatment. Should any bituminous material become contaminated the Contractor shall make it good to the satisfaction of the Engineer, in compliance with Clause 501.8.

Binder course material shall not remain uncovered by either the wearing course or surface treatment, whichever is specified in the Contract, for more than three consecutive days after being laid. The Engineer may extend this period, by the minimum amount of time necessary, because of weather conditions or for any other reason. If the surface of the base course is subjected to traffic, or not covered within three days, a tack coat shall be applied, as directed by the Engineer.

Traffic may be allowed after completion of the final rolling when the mix has cooled down to the surrounding temperature. Excessive traffic speeds should not be permitted.

512.7. Measurements for Payment

Close graded premix surfacing, Type A or B shall be measured as finished work, for the area specified to be covered, in square metres at a specified thickness. The area will be the net area covered, and all allowances for wastage and cutting of joints shall be deemed to be included in the rate.

The measurement shall be all measures for finished work on weight base in Metric Tonne.

512.8. Rate

The contract unit rate for close graded premix surfacing, Type A or B shall be payment in full for carrying out the required operations including full compensation for all components listed in Clause 501.8.8.2. (i) to (xi).

501.8.8. Rate for premixed bituminous material: The contract unit rate for premixed 2. bituminous material shall be payment in full for carrying out the required operations including full compensation for, but not necessarily limited to:

- (i) Making arrangements for traffic to Clause 112 except for initial ant to verge. shoulders and construction of diversions;
- (ii) Preparation of the surface to receive the material.
- (iii) Providing all materials to be incorporated in the work including arrangement for stock yards, all royalties, fees, rents where necessary and all leads and lift.
- (iv) Mixing, transporting, laying and compacting the mix, as specified.
- (v) All labour, tools, equipment, plant including installation of drum mix plant power supply units and all machinery, incidental to complete the work to these Specifications;
- (vi) Carrying out the work in part widths of the road where directed;
- (vii) Carrying out all tests for control of quality and
- (viii) The rate shall cover the provision of bitumen at the rate specified in the contract, with the provision that the variation in actual percentage of bitumen used will be assessed and payment will be adjusted accordingly.
- (ix) The rates for premixed material are to include for all wastage in cutting of joints etc.
- (x) The rates are to include for all necessary testing, mix design, transporting and testing of samples, and cores. If there is not a project specific laboratory, the Contractor must arrange to carry out all necessary testing at an outside Laboratory, approved by the Engineer, and all costs incurred are deemed to be included in the rate quoted for the
- (xi) The cost of all plant and laying trials as specified to prove the mixing and laying methods is deemed to be included in the Contractor's rates for the material.

Item No 29.

Providing & laying seal coat with B.T. agg. as specified using agg. at the rate of 0.18 cu.mt/10Sq.Mt.and bitumen for mixing agg. at the rate of 4.50% i.e. 45.00 kg/M.T. of total mix for binder and including heating & mixing in hot / drum mix plant & transporting & spreading the same by paver finisher & consolidation with vibratory roller incl. necessary firewood, oil, lubricants, labour charges etc. using contractor's own drum mix plant, machineries & equipment, tools etc. complete in accordance with the requirement of specification.

511 SEAL COAT**511.1 Scope**

This work shall consist of the application of a seal coat for sealing the voids in a bituminous surface laid to the specified levels, grade and cross fall (camber).

Seal coat shall be of either of the two types specified below:

- A) Liquid seal coat comprising of an application of a layer of bituminous binder followed by a cover of stone chips.
- B) Premixed seal coat comprising of a thin application of fine aggregate premixed with bituminous binder.

511.2 Materials**511.2.1 Binder**

The requirements of Clauses 510.1.2.1 and 510.2.2.1 shall apply.

The quantity of bitumen per 10 square metres, shall be 9.8 kg for Type A, and 6.8 kg for Type B seal coat. Where bituminous emulsion is used as a binder, the quantities for Type A and Type B seal coats shall be 15 kg and 10.5 kg respectively.

511.2.2 Stone Chips for Type A Seal Coat

The stone chips shall consist of angular fragments of clean, hard, tough and durable rock of uniform quality throughout. They shall be free of soft or disintegrated stone, organic or other deleterious matter. Stone chips shall be of 6.7 mm size defined as 100 percent passing through 11.2 mm sieve and retained on 2.36 mm sieve. The quantity used for spreading shall be 0.09 cubic metre per 10 square metre area. The chips shall satisfy the quality requirements given in Table 500-8 except that the upper limit for water absorption value shall be 1 percent.

511.2.3 Aggregate for Type B Seal Coat

The aggregate shall be sand or grit and shall consist of clean, hard, durable, uncoated dry particles, and shall be free from dust, soft or flaky/elongated material, organic matter or other deleterious substances. The aggregate shall pass 2.36 mm sieve and be retained on 180 micron sieve. The quantity used for premixing shall be 0.06 cum per 10 sqm area.

511.3 Construction Operations**511.3.1 Weather and Seasonal Limitations**

The requirements of Clause 501.5.1 shall apply.

511.3.2 Preparation of Surface

The seal coat shall be applied immediately after laying the bituminous course which is required to be sealed. Before application of seal coat materials, the surface shall be cleaned free of any dust or other extraneous matter.

511.3.3 Construction of Type A Seal Coat

The construction operations shall be the same as described in Clause 509.3.3 to 509.3.5.

511.3.4 Construction Type B Seal Coat

511.3.4.1 Using Paving Bitumen

The construction operations shall be the same as in Clause 510.1.3.

511.3.4.2 Using Emulsion

The construction operations shall be the same as in Clause 510.2.4.

511.4 Opening to Traffic

In the case of Type B seal coat, traffic may be allowed soon after final rolling when the premixed material has cooled down to the surrounding temperature. In the case of Type A seal coat, traffic shall not be permitted to run on any newly sealed area until the following day.

In special circumstances, however, the Engineer may open the road to traffic immediately after rolling, but in such cases traffic shall be rigorously limited to 20 km per hour until the following day.

511.5 Surface Finish and Quality Control Work

The surface of construction shall conform to the requirements of Clause 902.

For control on the quality of materials and the works carried out, the relevant provisions of **Section 900** shall apply.

511.6 Arrangements for Traffic

During the period of construction, arrangements for traffic shall be made in accordance with the provisions of Clause 112

511.7 Measurement for Payment

Seal coat, Type A or B shall be measured as finished work, over the area specified to be covered, in square metres at the thickness specified in the Contract.

511.8 Rate

The contract unit rate for seal coat Type A or B shall be payment in full for carrying out the required operations including full compensation for all components listed in Clause 501.8.8.2.

Item No 30.

Road marking with hot applied thermoplastic paint with reflectorising glass beads on bitumen surface providing and laying a hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads @ 250 gms per sqm area, thickness of 2.5 mm is excluding of surface applied glass beads as per IRC 35 :2015 . The Finished surface to be level uniform and free from streaks and holes. Zebra patta/bump patta lane/center line/edge line/cut patta. The white colour marking should provide luminance coefficient on cement road shall be min 130 mcd/m²/lux and asphalt road shall be min 100 mcd/m²/lux during the service life during the day time. The marking should meet the performance criteria for night time reflectivity wet reflectivity and skid resistance as mentioned in the section 15 of IRC 35-2015 Warranty for the Retro reflectivity should be two years

803.4.1. General:

- (i) The work under this section consists of marking traffic stripes using a thermoplastic compound meeting the requirements specified here in.
- (ii) The thermoplastic compound shall be screened /extruded on to the pavement surface in a molten state by suitable machine capable of controlled preparation and laying with surface application of glass beads at a specific rate. Upon cooling to ambient pavement temperature, it shall produce an adherent pavement marking of specified thickness and width and capable of resisting deformation by traffic.
- (iii) The color of the compound shall be white or yellow (IS color No. 356) as specified in the drawings or as directed by the Engineer.
- (iv) Where the compound is to be applied to cement concrete pavement, a scaling primer is recommended by the manufacturer, shall be applied to the pavement in advance of placing of the stripes to ensure proper bonding of the compound. On new concrete surface any laitance and/or curing compound shall be removed before the markings are

803.4.2. Thermoplastic Material

803.4.2.1. General: The thermoplastic material shall be homogeneously composed of aggregate, pigment, resins and glass reflectorising beads.

803.4.2.2. Requirements (1) Composition: The pigment, beads, and aggregate shall be uniformly dispersed in the resin. The material shall be free from all skins, dirt and foreign objects and shall comply with requirements indicated in Table 800 3.

TABLE 900 3 PROPORTIONS OF CONSTITUENTS OF MARKING MATERIAL

(Percentage by weight)

Component	White	Yellow
Binder	18.0 min.	18.0 min.
Glass Beads	30 - 40	30 - 40
Titanium Dioxide	10.0 Min.	-----
Calcium Carbonate and Inert		
Fillers	42.0 Max.	See Note
Yellow Pigments	-----	

Note: Amount of yellow pigment calcium carbonate and inert fillers shall be at the option of the manufacturer, provided all other requirements of this Specification are met.

(II) Properties: The properties of thermoplastic material, when tested in accordance with ASTM D36/BS 3262 (Paint 1), shall be as below:

(a) Luminance:

White: Daylight luminance at 45 degrees 65 per cent min. as per AASHTO M 249

Yellow: Daylight luminance at 45 degrees 45 per cent min. as per AASHTO M 249

(b) Drying time: When applied at a temperature specified by the manufacturer and to the required thickness, the material shall set to be open to traffic in not more than 15 minutes.

(c) Skid resistance: not less than 45 as per BS 6044.

(d) Cracking resistance at low temperature: The material shall show no cracks on application to concrete blocks.

(e) Softening point: 102.5 + 9.50 C as per AASTM D 36.

(f) Flow resistance: Not more than 25 per cent as per AASHTO M 249.

(g) Yellowness Index (for white thermoplastic paint): not more than 0.12 as per AASHTO M 249

(III) Storage life: The material shall meet the requirements of these Specifications for a period of one year. The thermoplastic material must also melt uniformly with no evidence of skins or unmelted particles for the one year storage period. Any material not meeting the above requirements shall be replaced by the manufacturer/

(IV) Reflectorisation: Shall be achieved by incorporation of beads. The grading and other properties of the beads shall be as specified in Clause 803.4.3.

(V) Marking: Each container of the thermoplastic material shall be clearly and indelibly marked with the following information:

1. The name, trade mark or other means of identification of manufacturer, 2. Batch number, 3. Date of manufacture, 4. Color (white or yellow) & 5. Maximum application temperature and maximum safe heating temperature.

(VI) Sampling and testing: The thermoplastic material shall be sampled and tested in accordance with the appropriate ASTM/BS method. The Contractor shall furnish to the Employer a copy of certified test reports from the manufacturers of the thermoplastic material showing results of all tests specified herein and shall certify that the material meets all requirements of this Specification.

803.4.3. Reflectorising glass beads

803.4.3.1. General: This Specification covers two types of glass beads to be used for the production of reflectorised pavement markings.

Type I beads are those which are a constituent of the basic thermoplastic compound vide Table 800 3 and Type 2 beads are those which are to be sprayed on the surface vide Clause 803.6.3.

803.4.3.2. The glass beads shall be transparent, colourless and free from milkiness, dark particles and excessive air inclusions.

803.4.3.3. Specific requirements

A. Gradation: The glass beads shall meet the gradation requirements for the two types as given in Table 800 4.

TABLE 800 4 GRADATION REQUIREMENTS FOR GLASS BEAD

Sieve size	Percent retained	
	Type I	Type 2
1.18mm	0 to 3	-
850 micron	5 to 20	0 to 5
600 micron	-	5 to 20
425 micron	65 to 95	-
300 micron	-	30 to 75
180 micron	0 to 10	10 to 30
Below 180Micron		00 to 15

B Roundness : The glass beads shall have a minimum of 70 percent true spires.

C Refractive index : The glass beads shall have a minimum refractive index of 1.50.

D Free flowing properties : The glass beads shall be free of hard lumps and clusters and shall dispense readily under any conditions suitable for paints striping. They shall pass the free flow test.

803.4.3.4 Test Methods

The specific requirements shall be tested with the following methods:

- i. Free-flow test: Spread 100 grams of beads evenly in a 100 mm diameter glass dish. Place the dish in a 250 mm inside diameter dessicator which is filled within 25 mm of the top of a dessicator plate with sulphuric acid water solution (specific gravity 1.10). Cover the dessicator and let it stand for 4 hours at 20°C to 29°C. Remove sample from dessicator, transfer beads to a pan and inspect for lumps or clusters. Then pour beads into a clean, dry glass funnel having a 100 mm stem and 6 mm orifice. If necessary, initiate flow by lightly tapping the funnel. The glass spheres shall be free of lumps and clusters and shall flow freely through the funnel.
- ii. The requirements of gradation, roundness and refractive index of glass beads and the amount of glass beads in the compound shall be tested as per BS:6088 and BS:3262 (Part
- iii. The Contractor shall furnish to the Engineer a copy of certified test reports from the manufacturer of glass beads obtained from a reputed laboratory showing results of all tests specified herein and shall certify that the material meets all requirements of these Specifications However, if so required, these tests may be carried out as directed by the

803.4.4 Application Properties of Thermoplastic Material

803.4.4.1 The thermoplastic material shall readily get screeded/extruded at temperatures specified by the manufacturers for respective method of application to produce a line of specified thickness which shall be continuous and uniform in shape having clear and

803.4.4.2 The material upon heating to application temperatures shall not exude fumes which are toxic, obnoxious or injurious to persons or property.

803.5 Preparation

- i. The material shall be melted in accordance with the manufacturer's instructions in a heater with a mechanical stirrer to give a smooth consistency to the thermoplastic material to avoid local overheating. The temperature of the mass shall be within the range specified by the manufacturer, and shall on no account be allowed to exceed the maximum temperature stated by the manufacturer. The molten material should be used

as expeditiously as possible and for thermoplastic material which has natural binders or is otherwise sensitive to prolonged heating, the material shall not be maintained in a molten condition for more than 4 hours.

- ii. After transfer to the laying equipment, the material shall be maintained within the temperature range specified by the manufacturer for achieving the desired consistency

803.4.5 Preparation

- i. The material shall be melted in accordance with the manufacturer's instructions in a heater with a mechanical stirrer to give a smooth consistency to the thermoplastic material to avoid local overheating. The temperature of the mass shall be within the range specified by the manufacturer, and shall on no account be allowed to exceed the maximum temperature stated by the manufacturer. The molten material should be used

803.6 Reflectorised Paint

Reflectorised paint, if used, shall conform to the Specification by the manufacturers and approved by the Engineer. Reflectorising glass beads for reflectorising paints where used shall conform to the requirements of Clause 803.4.2.

803.7 Application

803.7.1 Marking shall be done by machine. For locations where painting cannot be done by machine, approved manual methods shall be used with prior approval of the Engineer. The Contractor shall maintain control over traffic while painting operations are in progress so as to cause minimum inconvenience to traffic compatible with protecting the workmen.

803.7.2 Where the compound is to be applied to cement concrete pavement, a sealing primer as recommended by the manufacturer, shall be applied to the pavement in advance of placing of the stripes to ensure proper bonding of the compound. On new concrete surface any laitance and/or curing compound shall be removed before the markings are applied.

803.7.3 The thermoplastic material shall be applied hot either by screeding or extrusion process. After transfer to the laying apparatus, the material shall be laid at a temperature within the range specified by the manufacturer for the particular method of laying being used. The paint shall be applied using a screed or extrusion machine.

803.7.4 The pavement temperature shall not be less than 10°C during application. All surfaces to be marked shall be thoroughly cleaned of all dust, dirt, grease, oil and all other foreign matter before application of the paint.

The material, when formed into traffic stripes, must be readily renewable by placing an overlay of new material directly over an old line. Such new material shall so bond itself to the old line that no splitting or separation takes place.

Thermoplastic paint shall be applied in intermittent or continuous lines of uniform thickness of at least 2.5 mm unless specified otherwise. Where arrows or letters are to be provided, thermoplastic compound may be hand-sprayed. In addition to the beads included in the material, a further quantity of glass beads of Type 2, conforming to the above noted Specification shall be sprayed uniformly into a mono-layer on to the hot paint line in quick succession of the paint spraying operation. The glass beads shall be applied at the rate of 250 grams per square metre area.

803.7.5 The minimum thickness specified is exclusive of surface applied glass beads. The method of thickness measurement shall be in accordance with Appendices B and C of BS:3262 (Part 3).

803.7.6 The markings shall be done to accuracy within the tolerances given below:

- i. Width of lines and other markings shall not deviate from the specified width by more than 5 percent.
- ii. The position of lines, letters, figures, arrows and other markings shall not deviate from the position specified by more than 20 mm
- iii. The alignment of any edge of a longitudinal line shall not deviate from the specified alignment by more than 10 mm in 15 m.
- iv. The length of segment of broken longitudinal lines shall not deviate from the specified length by more than 150 mm.

In broken lines, the length of segment and the gap between segments shall be as indicated on the drawings; if these lengths are altered by the Engineer, the ratio of the lengths of the Painted sections shall remain the same.

803.7.7 Properties of Finished Road Markings

The finished lines shall be free from ruggedness on sides and ends and be parallel to the general alignment of the carriageway. The upper surface of the lines shall be level, uniform and free from streaks.

- a. The stripe shall not be slippery when wet.
- b. The marking shall not lift from the pavement in freezing weather.
- c. After application and proper drying, the stripe shall show no appreciable deformation or discoloration under traffic and under road temperatures upto 60°C.
- d. The marking shall not deteriorate by contact with sodium chloride calcium chloride or oil dripping from traffic.
- e. The stripe or marking shall maintain its original dimensions and position. Cold ductility of the material shall be such as to permit normal movement with the road surface without chopping or cracking.
- f. The colour of yellow marking shall conform to IS Colour No. 356 as given in IS:164

803.7.8 Measurements for Payment

803.7.8.1 The painted markings shall be measured in sq. metres of actual area marked (excluding the gaps, if any).

803.7.8.2 In respect of markings like directional arrows and lettering, etc., the measurement shall be by numbers.

803.7.9 Rate

The Contract unit rate for road markings shall be payment in full compensation for furnishing all labour, materials, tools, equipment, including all incidental costs necessary for carrying out the work at the site conforming to these Specifications complete as per the approved drawing(s) or as directed by the Engineer and all other incidental costs necessary to complete the work.

1.7 SPECIAL TERMS AND CONDITIONS FOR THERMOPLAST PAINT WORK:

1. Agency should carry out the such type of work by only of thermoplastic paint laying machine (power driven only) with temperature controller and automatic mixing arrangement of glass beads in required proportion.
2. After completion of the laying of thermoplastic paint work, four years guarantee for durability and reflectivity as per M.O.R.T.H. specification for road and bridge works clause 803 should be given by the bidder in the writing.
3. Guarantee security deposit shall be retained @ 10% of the cost of the item of thermoplast paint from the R.A. bills, which will be released after expiry of guarantee period.
4. Agency who carry out the such type of work shall have an experience of carrying out similar type of work.
5. Test certificates as per M.O.R.T.H. specification for road and bridge works clause 803.3.2.2 (vi) should be furnished of reputed laboratory before.

Item No 31.

Cats eye/Road stud/RPM : supplying Raised pavement marker made of polycarbonate and ABS moulded body and reflective panels with micro prismatic lens (No glass lens) capable of providing total internal reflection of the light entering the lens face and shall support a load of 13635 kgs. tested in accordance to ASTM D 4280 type H and complying to specifications of category A of MORTH circular No RW/NH/33023/10-97-DO III Dt 11.06.1997. The height width and length shall not exceed 20 mm, 130 mm and 130 mm and with minimum reflective area of 13 sqcm on each side and the slope to the base shall be 35 +/- 5 degree. The body of the marker should have finger grip for easy and accurate placement and application with epoxy/bituminous adhesive as recommended by the manufacturer of the marker. The color of the marker should be as per the IRC 35-2015 and as directed by Engineer in charge.

1.0 General

The colour, configuration, size and location of **Molded Twin Shanks Raised Pavement Markers** for highways other than Expressways shall be in accordance with the Code of Practice for Road Signs, IRC:35-2015 or as shown on the drawings or as directed by the Engineer.

The Molded Twin Shanks Raised Pavement Markers shall be reflectorised as shown on the drawings or as directed by the Engineer. It shall be of retro-reflectorised type and made of polycarbonate and ABS moulded body and reflective panels with micro prismatic lens capable of providing total internal reflection of the light entering the lens face and shall support a load of 13635 kgs. tested in accordance to ASTM D 4280 Type H and complying to Specifications of Category A of MORTH Circular No RW/NH/33023/10-97 – DO III Dt. 11.06.1997.

In general, cautionary and mandatory signs shall be fabricated through process of screen printing. In regard to informatory signs with inscriptions, either the message could be printed over the reflective sheeting, or cut letters of non-reflective black sheeting used for the purpose which must be bonded well on the base sheeting as directed by the Engineer.

1.2 Materials :

The various materials and fabrication of the **Molded Twin Shanks Raised Pavement Markers** shall conform to the following requirements.

The adhesive materials shall be of standard quality and it shall be high resistance quality against heavy moving vehicles.

The materials shall be used for the body of the **Molded Twin Shanks Raised Pavement Markers** is of high density PVC materials.

The dimensions and size of the Molded Twin Shanks Raised Pavement Markers shall be as per IS standard. The retro-reflective sheeting used on the Molded Twin Shanks Raised Pavement Markers shall consist of the white or coloured sheeting having a smooth outer surface which has the property of retro reflection over its entire surface. It shall be weather resistant and show colour fastness. It shall be new and unused and shall show no evidence of cracking, scaling, pitting, blistering, edge lifting or curling and shall have negligible shrinkage or expansion. A certificate of having tested the sheeting for these properties in an unprotected outdoor exposure facing the sun for two years and its having passed these tests shall be obtained from a reputed laboratory, by the manufacturer of the sheeting. The reflective sheeting shall be either of Engineering Grade material with enclosed lens or of High Intensity Grade with encapsulated lens. The type of the sheeting to be used would depend upon the type, functional hierarchy and importance of the road.

High intensity grade sheetings : This sheeting shall be of encapsulated lens type consisting of spherical glass lens, elements adhered to a synthetic resin and encapsulated by a flexible,

transparent water-proof plastic having a smooth surface. The retro-reflective surface after cleaning with soap and water and in dry condition shall have the minimum co-efficient of retro-reflection determined in accordance with ASTM D 4280 Type H).

TABLE 800.1
ACCEPTABLE MINIMUM CO-EFFICIENT OF RETRO-REFLECTION FOR HIGH
INTENSITY GRADE SHEETING

[CANDEL AS PER LUX PER SQUARE METRE]

Observation (in degree)	Entrance angle (in degree)	White	Yellow	Orange	Green / Red	Blue
0.2	-4	250	170	100	45	20
0.2	+30	150	100	60	25	10
0.5	-4	95	62	30	15	7.5
0.5	+30	65	45	25	10	5

When totally wet, the sheeting shall not show less than 90 percent of the values of retro reflective indicated in Table 800-1. At the end of 7 years, the sheeting shall retain at least 75 percent of its original retro-reflectance.

Engineer grade sheetings : This sheeting shall be of enclosed lens type consisting of micro prismatic lens elements embedded beneath the surface of a smooth, flexible, transparent, water proof plastic, resulting in a non-exposed lens optical reflecting system. The retro-reflective surface after cleaning with soap and water and in dry condition shall have the minimum co-efficient of retro-reflection determined in accordance with ASTM D 4280 Type H) as indicated in Table 800.2.

TABLE 800.2
ACCEPTABLE MINIMUM CO-EFFICIENT OF
RETRO-REFLECTION FOR HIGH INTENSITY GRADE SHEETING

[CANDEL AS PER LUX PER SQUARE METRE]

Observation (in degree)	Entrance angle (in degree)	White	Yellow	Orange	Green	Red	Blue
0.2	-4	70	50	25	9.0	14.5	4.0
0.2	+30	30	22	7.0	3.5	6.0	1.7
0.5	-4	30	25	13.5	4.5	7.5	2
0.5	+30	15	13	4.0	2.2	3.0	0.8

When totally wet, the sheeting shall not show less than 90 percent of the values of retro reflective indicated in Table 800-2. At the end of 5 years, the sheeting shall retain at least 50 percent of its original retro-reflectance.

- 1.3** Processed and applied in accordance with recommended procedures, the reflective material shall be weather resistant and, following cleaning, show no appreciable discolouration, cracking, blistering or dimensional change and shall not have less than 50 percent of the specified minimum reflective intensity values (Table 800-1 and 800-2) when subjected to accelerated weathering for 1000 hours, using type E or EH Weatherometer (AASHTO Designation M 268).

1.4 INSTALLATION:

The **Molded Twin Shanks Raised Pavement Markers** shall be installed directly on road surface, after cleaning completely by removing all dust and other foreign materials from the surface of the road.

1.5 MEASUREMENT FOR PAYMENT :

The measurement of **Molded Twin Shanks Raised Pavement Markers** shall be in numbers, these shall be measured in No.

1.6 RATE :

The Contract unit rate shall be payment in full for the cost of making **Molded Twin Shanks Raised Pavement Markers** including all materials, installing it at the site and incidentals to complete the work in accordance with the specifications.

Item No 32.**Cautionary Warning Sign**

Cautionary Warning Sign :-Providing and fixing sign boards made out of 2mm aluminium sheet / 4mm ACP (Aluminum composite Panel); size 90 x 90 x 90 cms. equilateral triangle as per design of IRC-67-2012. Pre treated with phospheting process & acid etching; coated with one coat of epoxy primer and two coats of best quality epoxy paint ;reflectorised with Micro Prismatic Grade retro reflective sheeting of Type-11 as per ASTM D-4956 and latest M.O.S.T.Specifications; 3.6mtr long stand post of 75 x 75 x 6mm / 65NB Circular MS Pipe as required and frame fabricated from suitable size iron angle of 35 x 35 x 3mm; painted with best quality epoxy coatings in black and white bends. The details of symbol for each board shall be as per the instruction of engineer in charge. The fixing at site shall be in 1:2:4 CC block of size 45 x 45 x 60 Cms. for each leg including excavation, curing etc. complete under the supervision of engineer in charge. A warranty for 10 years for the Retro reflective sheeting from original manufacturer & a certified copy of 3 year outdoor exposure test report from third party test lab for the product offered shall be submitted by contractor. (A) Class-C Type-11 Retro Reflective sheeting

(A) Class-C Type-11 Retro Reflective sheeting

A warranty for 7 years for the Retro reflective sheeting from original manufacturer & a certified copy of 3 year outdoor exposure test report from third party test lab for the product offered shall be submitted by contractor. (A) Class-C Type-11 Retro Reflective sheeting .

An amount equivalent to 10% of the Item amount shall be kept in Deposit for 10 years and shall be released on completion of 10 years after certified date of completion.

The Cautionary Warning Sign boards shall be made out of 2mm thick aluminium sheet/4mm thick ACP using phospheting process and one coat of epoxy primer and two coats of best quality epoxy paint. The fixing shall be done in C.C. 1:2:4 blocks of

The board shall be of Class - (A) Class-C Type-11 Retro Reflective sheeting .

1. SCOPE :

The work shall consist of providing and fixing in C.C. 1:2:4 (size of block 45 x 45 x 60 cm.) the road sign boards as per specification as under as directed by Engineer – in – charge.

2. MATERIALS :

The boards shall be made from 4mm. aluminum sheet. The sheet shall be of good quality approved by Engineer - in - charge. Stand post and frames should be made of M.S. angle of 75 x 75 x 6 mm size. Epoxy paint and epoxy primer shall be approved quality and shade as approved by Engineer – in – charge shall be encapsulated lens type. **The board shall be prepared 90x30 cms. rectangular .**

3. TRAFFIC SHINS HAVING RETRO REFLECTIVE SHEETING :**4. GENERAL REQUIREMENTS :**

The retro-reflective sheeting used on the sign shall consist of white or coloured sheeting having a smooth outer surface which has the property of retroreflective over its entire surface. It shall be weather resistance and show colour fastness. It shall be new and unused and shall show no evidence of cracking scaling pitting, blistering, edge lifting or curling and shall have negligible shrinkage or expansion. A certificate of having tested the sheeting for these properties in an unprotected outdoor exposure facing the sun for two

years and its having passed these tests shall be obtained from a reputed laboratory by the manufacture of the sheeting. The reflective sheeting shall be either of Engineering Grade material with enclosed lens or of high intensity grade with encapsulated lens/ micro prismatic type. The type of sheeting to be used would depend upon the type functional hierarchy and importance of the road.

5. High Intensity grade sheeting

The board shall be of Class-(A) Class-C Type-11 Retro Reflective sheeting.

The sheeting shall be of enclosed lens type consisting of microscope lens elements embedded beneath the surface of a smooth transparent, water-proof plastic resulting in a non exposed lens optical reflecting system. The retro-reflective surface after cleaning with soap and water and in dry condition shall have the minimum coefficient of retro reflection (determined in accordance with ASTM standard E-810) (As indicated in Table 800 – 2)

Table 800 - 2
ACCEPTABLE MINIMUM COEFFICIENT OF RETRO REFLECTION FOR
ENGINEERING GRADE SHEETING (CANDAL AS PER LUX PER SQUARE METER)

Observation angle	Entrance angle	White	Yellow	Orange	Green	Red	Blue
0.2°	-4	70.0	50.0	2.5	9.0	14.5	4.0
0.2°	30	30.0	22.0	7.0	3.5	6.0	1.7
0.5°	-4	30.0	25.0	13.5	4.5	7.5	2.0
0.5°	30	15.0	13.0	4.0	2.2	3.0	0.8

When totally wet, the sheeting shall not show less than 90% of the values, of retro-reflective indicated in Table 800 – 2 at the end of 5 years, the sheeting shall retain at least 50% of its original retro-reflective.

Message (legends, letters, numerals etc.) and borders shall either be screen printed or of cut – outs screen printing shall be processed and finished with materials and in a manner specified by the sheeting manufacturer. Cut outs shall be of materials as specified by the sheeting manufacturer and shall be bounded with the sheeting in manner specified by the manufacturer.

For screen printed transparent coloured areas on white sheeting the coefficient of retro-reflective shall not be less than 50% (fifty) of the value of corresponding colour in table 800.1 (a), 800.1(b) and 800.2 as applicable. Cut out and borders, wherever used shall be made out of retro-reflective sheeting (as per clause 801.3.2 of 801.3.3 as applicable) except those in black which shall be of non – reflective sheeting.

6. COLOUR :

Unless otherwise specified, the general colour scheme shall be as stipulated in IS 5 colour or ready mixed paints.

Blue	IS	Colour No. 166 French Blue.
Red	IS	Colour No. 537 Single Red.
Green	IS	Colour No. 284 Indian Green
Orange	IS	Colour No. 591 Deep Orange.

The colours shall be durable and uniform in acceptable hue when viewed in day light or under normal headlights at night.

7. Adhesives

The sheeting shall either have a pressure sensitive adhesive of the aggressive tack type requiring no heat, solvent or other preparation for adhesion to a smooth clear surface or a tack free adhesive activated by heat, applied in a heat vacuum applicator in a manner recommended by the sheeting manufacture. The sheeting shall be protected by an easily removable liner (removable by peeling without soaking in water or other solvent) and shall be suitable for the type of materials of the base plate used for the sign. The adhesive shall form a durable bond to smooth corrosion and weather resistant surface of the base plate such that it shall not be possible to remove the sheeting from the sign base in one place by use of sharp instrument. In case of pressure sensitive adhesive sheeting the sheeting shall be applied in accordance with the manufacturer's specification. Sheeting with adhesive requiring use of solvents or other preparations for adhesive shall be applied strictly in accordance with the manufacturer's instructions.

11. Refurbishment

Where existing signs are specified for refurbishment, the sheeting shall have a semi-rigid aluminium backing pre-coated with aggressive tack type pressure sensitive adhesive. The adhesive shall be suitable for the type of materials used for the sign and should thoroughly bond with that material.

Alternatively, the aluminium blank shall be recycled to a finished condition and new sheeting's put on in an approved manner.

12. Fabrication

Surface to be refabricated shall be effectively prepared to receive the retro-reflective sheeting. The aluminium sheeting shall be degreased either by acid or hot alkaline etching and all scale/ dust removed to obtain a smooth plain surface before the application of retro-reflective glue sheeting. If the surface is rough, approved surface primer may be used. After cleaning, metal shall not be handled except by suitable device or clean canvas gloves between all cleaning and preparation operation and application of reflective sheeting primer. There shall be no opportunity for metal to come in contact with grease, oil or other contaminants prior to the application of retro-reflective sheeting.

- 12.0.2** Complete sheets or the materials shall be used on the sign except where it is unavoidable, at splices, sheeting with pressure sensitive adhesives shall be overlapped not less than 5mm sheeting with heat activated adhesives may be spliced with an overlap not less than 5 mm or butted with a gap not exceeding 0.75mm where screen printing with transparent colours is proposed, only butt joining shall be used. The materials shall cover the sign surface evenly and shall be free from twists, cracks and folds. Cut outs to produce legends and borders shall be bonded with the sheeting in the manner specified by the manufacturer

13. WARRANTY AND DURABILITY:

For each lot of sheeting's procured the contractor shall obtain from the manufacturer a 10 years warranty for satisfactory field performance including stipulated retro-reflective of the sheeting of high intensity grade and 10 years warranty for the Engineering Grade and submit the same to the Engineer. In addition, a 10 years and five years warranty for satisfactory in field performance of the finished sign with retro-reflective sheeting of high intensity grade and engineering grade respectively, inclusive of the screen printing or cut

out letter/legends and their ponding to the retro-reflective sheeting shall be obtained from the contractor/supplier and passed on the Engineer. The contractors/Supplier shall also furnish a certification that the signs and materials supplied against the assigned work meeting all the stipulated requirements and carry the stipulated warranty. All signs shall be dated during fabrication with indelible markings to indicate the start of warranty. The warranty shall also cover the replacement obligation by the sheeting manufacturer as well as contractor for replacement/repair/restoration of the retro-reflective efficiency.

14. Installation

- 14.0.1** Sign posts, their foundations and sign mountings shall be so constructed as to hold these in a proper and permanent position against the normal storm wind loads or displacement by vandalism. Normally signs with an area upto 0.9 sqm. Shall be mounted on a single post and for greater area two or more supports shall be provided. Sign supports may be of mild steel reinforced concrete or galvanized iron (G.I.) posts end(s) shall be firmly fixed to the ground by means of properly designed foundation. The work of foundation shall conform to relevant specifications as specified.
- 14.0.2** All components of signs and supports other than the reflective portion and G.I. posts shall be thoroughly descaled, cleaned, primed, with two coats of epoxy paint. Any part of mild steel (M.S) post below ground shall be painted with three coat of red lead paint.
- 14.0.3** The signs shall be fixed to the posts by welding in the case of steel posts and by bolts and washers of suitable size in the case of reinforced concrete or G.I. posts. After the nuts have been tightened the tails of the bolts shall be furred over with a hammer to prevent

15. MEASUREMENT FOR PAYMENT

The measurement for standard cautionary, mandatory and information signs shall be in number of different types of sign supplied and fixed. Direction and place identification signs, also shall be measured in numbers of different type of sign supplied and fixed.

- 16.** The contract unit rate shall be payment in full for the cost making the road sign including all materials, installing it at the site and incidentals to complete the work in accordance with the specifications.

17. Unit rate for payment of this item shall be per 1-No. basis

SPECIAL TERMS AND CONDITIONS OF CONTRACT FOR SIGN BOARDS

1. Warranty certificate for seven years for respective grades of signs from the sheeting manufacturer should be attached with the bid.
2. A certificate of authorization from the sheeting manufacturer shall be submitted with the
3. The responsibility for handling, upkeep and safety of the boards lies with the contractor until the completion of work and final payment are released.
4. The contract is valid for three months from the date of work order. The required quantity has to be supplied and fixed as and when intimated by the Division.
5. The measurement for payment will be done only after fulfilling condition up to the satisfaction of Executive Engineer. The 100% quantity of supply and fixing will be checked by Deputy Executive Engineer and at least 10% quantity of supply and fixing will be checked by the Executive Engineer to ensure quality and workmanship, before passing. The contractor will have to ensure how he is going to arrange repair or replacement of defective boards after intimation from the Division.

Item No 33.

Direction sign (Junction board)

Direction (Junction) Sign :-Providing and fixing sign boards made out of 2mm aluminium sheet / 4mm ACP (Aluminum composite Panel); size 244x122 cms. rectangular as per design of IRC-67-2012. Pre treated with phospheting process & acid etching; coated with one coat of epoxy primer and two coats of best quality epoxy paint ;reflectorised with Micro Prismatic Grade retro reflectivesheeting of Type-11 as per ASTM D-4956 and latest M.O.S.T.Specifications; 4.0mtr long (2 Nos.) stand post of 75 x 75 x 6mm / 65NB Circular MS Pipe as required and frame fabricated from suitable size iron angle of 50 x 50 x 5mm; painted with bestquality epoxy coatings in black and white bends. The details of symbol foreach board shall be as per theinstruction of engineer in charge. The fixing at site shall be in 1:2:4 CC blockof size 45 x 45 x 60 Cms. for each leg.including excavation, curing etc.complete under the supervision of engineer in charge. A warranty for 10 years for the Retro reflective sheeting from original manufacturer & a certified copy of 3 year (A) Class-C Type-11 Retro Reflective sheeting

A warranty for 7 years for the Retro reflective sheeting from original manufacturer & a certified copy of 3 year outdoor exposure test report from third party test lab for the product offered shall be submitted by contractor. (A) Class-C Type-11 Retro Reflective sheeting .

An amount equivalent to 10% of the Item amount shall be kept in Deposit for 10 years and shall be released on completion of 10 years after certified date of completion.

This item shall be carried out for Direction sign (Junction board) Sign boards as per Detailed Specification of Item No. 32 as above except the size of the board shall be 244x122 cms Rectangle as per Design and shall be fixed on C.C. Block of 45x45x60cm.s as above.

Item No 34.

Village name Sign

Village Name Sign :-Providing and fixing sign boards made out of 2mm aluminium sheet / 4mm ACP (Aluminum composite Panel); size 90x60 cms. rectangular as per design of IRC-67-2012. Pre treated with phospheting process & acid etching; coated with one coat of epoxy primer and two coats of best quality epoxy paint ;reflectorised with Micro Prismatic Grade retro reflectivesheeting of Type-11 as per ASTM D- 4956 and latest M.O.S.T.Specifications; 3.3mtr long stand post of 75 x 75 x 6mm / 65NB Circular MS Pipe as required and frame fabricated from suitable size iron angle of 35 x 35 x 3mm; painted with bestquality epoxy coatings in black and white bends. The details of symbol or inscription/letters / numerals for each board shall be as per the instruction of engineer in charge. The fixing at site shall be in 1:2:4 CC blockof size 45 x 45 x 60 Cms. for each leg.including excavation, curing etc.complete under the supervision of engineer in charge. A warranty for 10 years for the Retro reflective sheeting from original manufacturer & a certified copy of 3 year (A) Class-C Type-11 Retro Reflective sheeting

A warranty for 7 years for the Retro reflective sheeting from original manufacturer & a certified copy of 3 year outdoor exposure test report from third party test lab for the product offered shall be submitted by contractor. (A) Class-C Type-11 Retro Reflective sheeting .

An amount equivalent to 10% of the Item amount shall be kept in Deposit for 10 years and shall be released on completion of 10 years after certified date of completion.

<p>This item shall be carried out for Village name Sign Sign boards as per Detailed Specification of Item No. 32 as above except the size of the board shall be 90 x 60 cms. rectangle as per Design and shall be fixed on C.C. Block of 45x45x60cm.s as above.</p>
--

Item No 35.**Hazard Marker**

Hazard Marker Sign :-Providing and fixing sign boards made out of 1.5mm aluminium sheet / 3mm ACP (Aluminum composite Panel); size 90x30 cms. rectangular as per design of IRC-67-2012. Pre treated with phospheting process & acid etching; coated with one coat of epoxy primer and two coats of best quality epoxy paint ;reflectorised with Micro Prismatic Grade retro reflectivesheeting of Type-11 as per ASTM D- 4956 and latest M.O.S.T.Specifications; 1.8mtr long stand post of 75 x 75 x 6mm / 65NB Circular MS Pipe as required and frame fabricated from suitable size iron angle of 35 x 35 x 3mm; painted with bestquality epoxy coatings in black and white bends. The details of symbol foreach board shall be as per theinstruction of engineer in charge. The fixing at site shall be in 1:2:4 CC blockof size 45 x 45 x 60 Cms. for each leg.including excavation, curing etc.complete under the supervision of engineer in charge. A warranty for 10 years for the Retro reflective sheeting from original manufacturer & a certified copy of 3 year (A) Class-C Type-11 Retro Reflective sheeting

A warranty for 7 years for the Retro reflective sheeting from original manufacturer & a certified copy of 3 year outdoor exposure test report from third party test lab for the product offered shall be submitted by contractor. (A) Class-C Type-11 Retro Reflective sheeting .

An amount equivalent to 10% of the Item amount shall be kept in Deposit for 10 years and shall be released on completion of 10 years after certified date of completion.

<p>This item shall be carried out for Hazard Marker Sign boards as per Detailed Specification of Item No. 32 as above except the size of the board shall be 90 x 30 cms. rectangle as per Design and shall be fixed on C.C. Block of 45x45x60cm.s as above.</p>
--

Item No 36.**Chevron Sign**

Chevron sign :-Providing and fixing sign boards made out of 1.5mm aluminium sheet / 3mm ACP (Aluminum composite Panel); size 60x50 cm as per design of IRC-67- 2012. Pre treated with phospheting process & acid etching; coated with one coat of epoxy primer and two coats of best quality epoxy paint ;reflectorised with Micro Prismatic Grade retro reflectivesheeting of Type- 11 as per ASTM D-4956 and latest M.O.S.T.Specifications; 3.3 mtr long stand post of 75 x 75 x 6mm / 65NB Circular MS Pipe as required and frame fabricated from suitable size iron angle of 50 x 50 x 5mm; painted with bestquality epoxy coatings in black and white bends. the details of symbol or inscription / numerals for each board shall be as per the instruction of engineer in charge.The fixing at site shall be in 1:2:4 CC blockof size 45 x 45 x 60 Cms. for each leg.including excavation, curing etc.complete under the supervision of engineer in charge. A warranty for 10 years for the Retro reflective sheeting from originaa manufacturer & a certified copy of 3 year outdoor exposure test report from third party test lab for the product offered shall be submitted by contractor. (A) Class-C Type-11 Retro Reflective sheeting

(A) Class-C Type-11 Retro Reflective sheeting.

A warranty for 7 years for the Retro reflective sheeting from original manufacturer & a certified copy of 3 year outdoor exposure test report from third party test lab for the product offered shall be submitted by contractor. (A) Class-C Type-11 Retro Reflective sheeting. .

An amount equivalent to 10% of the Item amount shall be kept in Deposit for 10 years and shall be released on completion of 10 years after certified date of completion.

<p>This item shall be carried out for Chevron Sign Sign boards as per Detailed Specification of Item No. 32 as above except the size of the board shall be 90 x 60 cms. Rectangle as per Design and shall be fixed on C.C. Block of 45x45x60cm.s as above.</p>

Item No 37.

Providing and fixing 5th Km. stone of precast C.C. 1:2:4 including necessary reinforcement as per I.R.C. type design fixing in C.C. 1:4:8 including painting and lettering etc. complete S.H.

1. This item shall be carried as per Item of Ordinary Kilometer stone shall be of approved quality and shall be casted with precast 1:2:4 R. C. C. grade or as specified in the item. as per I.R.C. 8 (Type design for highway kilometre stones).The detailed specification for C.C. 1:2:4 shall be followed during casting of the Kilometer stones at site or at workshop of the contractor. The precast stones shall be brought to the site without any damage at any side. If such damaged stones shall be found same shall be replaced by the contractor at his own cost.
2. The size, manner of fixing, painting and lettering of 5th K.M. stone shall conform specifications as per I.R.C. 8 (Type design for Highway kilometre stories). The fixing of K.M. stone shall be carried out in ordinary Cement concrete 1:4:8 of grade specified in the item using crushed metal of requiredsize.. The measurement for **payment shall be made per No. of 5th K.M. stone fixed** in position.
3. The stones so fixed on to site shall be painted and lettered with white and black enamel paint and top of the stone shall be painted with Green reflective colour or as directed by the Engineer-in-charge in TWO coats.
4. Unit rate for kilometre stone includes the cost of all materials, labour, tools. fixing, finishing curing lettering and painting as directed by the Engineer in charge.
5. **Unit rate for payment of this item shall be per 1-No. of stones supplied fixed and Painting and Lettering as per I.R.C. type design or as directed with all lead and lift.**

Item No 38.

Providing and fixing ordinary kilometer stone of precast C.C. 1:2:4 including necessary reinforcement as per I.R.C. type design fixing in C.C. 1:4:8 including painting and lettering etc.

1. The Ordinary Kilometer stone shall be of approved quality and shall of Hard stone of approved quality The Km. Stones shall be brought to the site without any damage at any side. If such damaged stones shall be found same shall be replaced by the contractor at his own cost.
2. The size, manner of fixing, painting and lettering of K.M. stone shall conform specifications as per I.R.C. 8 (Type design for Highway kilometre stories). The fixing of K.M. stone shall be carried out in ordinary Cement concrete 1:4:8 of grade specified in the item using crushed metal of required size.. The measurement for **payment shall be made per No. of K.M. stone fixed** in position.
3. The stones so fixed on to site shall be painted and lettered with white and black enamel paint and top of the stone shall be painted with Green reflective colour or as directed by the Engineer-in-charge.
4. Unit rate for kilometre stone includes the cost of all materials, labour, tools. fixing, finishing curing lettering and painting with enamel paint (TWO Coats) as directed by the Engineer in charge.
5. **Unit rate for payment of this item shall be per 1-No. of stones supplied fixed and Painting and Lettering as per I.R.C. type design or as directed with all lead and lift.**

Item No 39.

Providing and fixing hectometer as per I.R.C. type design including painting lettering etc. complete fixing in C.C. 1:5:10.

The work shall be carried out as per the item of ordinary kilometre stone except that the size of Hectometre stone shall be smaller than that of ordinary kilometre stone as per I.R.C. 26 (Type design for 200 metre stones). The Hectometer stones shall be of Hard stone of approved quality as per I.R.C. type and Design. and its fixing shall be in C.C. 1:5:10

Fixing in C. C. 1:5:10:- 3. The Hectometer Stones shall be fixed in Cement Concrete 1:5:10 by making necessary excavation as directed. First necessary excavation shall be carried out as per size of Hectometer Stones and then stone shall be fixed to the said excavated place. It shall be watered and rammed after fixing so that same can be fixed to proper strength.

The stones so fixed on to site shall be painted and lettered with approved brand oil paint of the stone as directed by the Engineer-in-charge

The measurement for payment as well as the operations included in the unit rate shall be supply of H.M. Stone, fixing the same in C.C. 1:5:10 including painting, lettering etc. complete.

Unit rate for payment of this item shall be per 1-No. of stones supplied fixed and painting and lettering (Two coats) the Hecto Meter stones as per I.R.C. type Design or as directed with all lead and lift.

Item No 40.

Regulatory / Mandatory Sign

Regulatory / Mandatory Sign :-Providing and fixing sign boards made out of 2mm aluminium sheet / 4mm ACP (Aluminum composite Panel); size 60 cms Dia Circle as per design of IRC-67-2012. Pre treated with phospheting process & acid etching; coated with one coat of epoxy primer and two coats of best quality epoxy paint ;reflectorised with Micro Prismatic Grade retro reflectivesheeting of Type-11 as per ASTM D- 4956 and latest M.O.S.T.Specifications; 3.6mtr long stand post of 75 x 75 x 6mm / 65NB Circular MS Pipe as required and frame fabricated from suitable size iron angle of 35 x 35 x 3mm; painted with bestquality epoxy coatings in black and white bends. The details of symbol foreach board shall be as per theinstruction of engineer in charge. The fixing at site shall be in 1:2:4 CC blockof size 45 x 45 x 60 Cms. for each leg.including excavation, curing etc.complete under the supervision of engineer in charge. A warranty for 10 (A) Class-C Type-11 Retro Reflective sheeting

A warranty for 7 years for the Retro reflective sheeting from original manufacturer & a certified copy of 3 year outdoor exposure test report from third party test lab for the product offered shall be submitted by contractor. (A) Class-C Type-11 Retro Reflective sheeting .

An amount equivalent to 10% of the Item amount shall be kept in Deposit for 10 years and shall be released on completion of 10 years after certified date of completion.

<p>This item shall be carried out for Regulatory / Mandatory Sign Sign boards as per Detailed Specification of Item No. 32 as above except the size of the board shall be 60 cms Dia Circle as per Design and shall be fixed on C.C. Block of 45x45x60cm.s as above.</p>

Item No 41.**Stop Signs**

STOP Sign :-Providing and fixing sign boards made out of 2mm aluminium sheet / 4mm ACP (Aluminum composite Panel); size 90 cms Octagone as per design of IRC-67-2012. Pre treated with phospheting process & acid etching; coated with one coat of epoxy primer and two coats of best quality epoxy paint ;reflectorised with Micro Prismatic Grade retro reflectivesheeting of Type-11 as per ASTM D-4956 and latest M.O.S.T.Specifications; 3.6mtr long stand post of 75 x 75 x 6mm / 65NB Circular MS Pipe as required and frame fabricated from suitable size iron angle of 35 x 35 x 3mm; painted with bestquality epoxy coatings in black and white bends. The details of symbol foreach board shall be as per theinstruction of engineer in charge. The fixing at site shall be in 1:2:4 CC blockof size 45 x 45 x 60 Cms. for each leg.including excavation, curing etc.complete under the supervision of engineer in charge. A warranty for 10 years for the Retro reflective (A) Engineer Grade(VR)

A warranty for 7 years for the Retro reflective sheeting from original manufacturer & a certified copy of 3 year outdoor exposure test report from third party test lab for the product offered shall be submitted by contractor. (A) Engineer Grade(VR) .

An amount equivalent to 10% of the Item amount shall be kept in Deposit for 10 years and shall be released on completion of 10 years after certified date of completion.

<p>This item shall be carried out for Stop Signs Sign boards as per Detailed Specification of Item No. 32 as above except the size of the board shall be 90 x 90 mm rectangal as per Design and shall be fixed on C.C. Block of 45x45x60cm.s as above.</p>

Item No 42.

Providing and laying of raised profile edge line marking (audible warning) with hot applied thermoplastic road marking compound 2mm thick base coat layer above that ribs profile of 6 mm thick (Total 8 mm thick) at the distance of 500 mm between two ribs including reflectorizing glass beads @ 250 gm/ sq.mt area. The minimum and maximum width of raised profile should be 150 mm. The thickness of 8 mm profile should be exclusive of surface applied glass beads. The finished surface to be levelled, uniform and free from streaks and holes, to be applied on edge lines.

The work shall be executed as per specification of Item No. 30 except the work is for providing and laying of raised profile edge line marking (audible warning) with hot applied thermoplastic road marking compound 2mm thick base coat layer above that ribs profile of 6 mm thick (Total 8 mm thick) at the distance of 500 mm between two ribs including reflectorizing glass beads @ 250 gm/ sq.mt area.

The minimum and maximum width of raised profile should be 150 mm. The thickness of 8 mm profile should be exclusive of surface applied glass beads. The finished surface to be levelled, uniform and free from streaks and holes, to be applied on edge lines.

Item No 44.

Tree Guard sign :-Providing & fixing sign board made out of 2mm aluminium sheet / 3mm ACP (Aluminum composite Panel) , size 30cms diameter circle, pretreated with phosphating process and acid etching, painted with one coat of epoxy primer and two coats of best quality epoxy paint reflectorised with retro reflective sheeting as per latest M.O.S.T. specifications. A warranty for 10 years for the Retro reflective sheeting from original manufacturer & a certified copy of 3 year outdoor exposure test report from third party test lab for the product offered shall be submitted by contractor. (A) Class-C Type-11 Retro Reflective sheeting

(A) Class-C Type-11 Retro Reflective sheeting

A warranty for 7 years for the Retro reflective sheeting from original manufacturer & a certified copy of 3 year outdoor exposure test report from third party test lab for the product offered shall be submitted by contractor. (A) Class-C Type-11 Retro Reflective sheeting .

An amount equivalent to 10% of the Item amount shall be kept in Deposit for 10 years and shall be released on completion of 10 years after certified date of completion.

<p>This item shall be carried out for Sign boards as per Detailed Specification of Item No. 32 as above except the size of the board shall be 30cms dia circle as per Design and shall be fixed on C.C. Block of 45x45x60cm.s as above.</p>
--

Item No 43.**Facility Informatory Sign**

Facility Informatory Sign :-Providing and fixing sign boards made out of 2mm aluminium sheet / 4mm ACP (Aluminum composite Panel); size 80 x 60 cms rectangular as per design of IRC-67-2012. Pre treated with phospheting process & acid etching; coated with one coat of epoxy primer and two coats of best quality epoxy paint ;reflectorised with Micro Prismatic Grade retro reflectivesheeting of Type-11 as per ASTM D-4956 and latest M.O.S.T.Specifications; 3.6mtr long stand post of 75 x 75 x 6mm / 65NB Circular MS Pipe as required and frame fabricated from suitable size iron angle of 35 x 35 x 3mm; painted with bestquality epoxy coatings in black and white bends. The details of symbol foreach board shall be as per theinstruction of engineer in charge. The fixing at site shall be in 1:2:4 CC blockof size 45 x 45 x 60 Cms. for each leg.including excavation, curing etc.complete under the supervision of engineer in charge. A warranty for 10 (A) Class-C Type-11 Retro Reflective sheeting

A warranty for 7 years for the Retro reflective sheeting from original manufacturer & a certified copy of 3 year outdoor exposure test report from third party test lab for the product offered shall be submitted by contractor. (A) Class-C Type-11 Retro Reflective sheeting .

An amount equivalent to 10% of the Item amount shall be kept in Deposit for 10 years and shall be released on completion of 10 years after certified date of completion.

<p>This item shall be carried out for Facility Informatory Sign Sign boards as per Detailed Specification of Item No. 32 as above except the size of the board shall be 80 x 60 cm Rectangular as per Design and shall be fixed on C.C. Block of 45x45x60cm.s as above.</p>
--

Item No 45.

Give way Sign

Give Way Sign :-Providing and fixing sign boards made out of 2mm aluminium sheet / 4mm ACP (Aluminum composite Panel); size 90 x 90 x 90 cms. equilateral triangle as per design of IRC-67-2012. Pre treated with phospheting process & acid etching; coated with one coat of epoxy primer and two coats of best quality epoxy paint ;reflectorised with Micro Prismatic Grade retro reflectivesheeting of Type-11 as per ASTM D-4956 and latest M.O.S.T.Specifications; 3.6mtr long stand post of 75 x 75 x 6mm / 65NB Circular MS Pipe as required and frame fabricated from suitable size iron angle of 35 x 35 x 3mm; painted with bestquality epoxy coatings in black and white bends. The details of symbol foreach board shall be as per theinstruction of engineer in charge. The fixing at site shall be in 1:2:4 CC blockof size 45 x 45 x 60 Cms. for each leg.including excavation, curing etc.complete under the supervision of engineer in charge. A warranty for 10 years for the Retro reflective sheeting from original manufacturer & a certified copy of 3 year outdoor exposure test report from third party test lab for the product offered shall be submitted by contractor. (A) Class-C Type-11 Retro Reflective sheeting

(A) Class-C Type-11 Retro Reflective sheeting

A warranty for 7 years for the Retro reflective sheeting from original manufacturer & a certified copy of 3 year outdoor exposure test report from third party test lab for the product offered shall be submitted by contractor. (A) Class-C Type-11 Retro Reflective sheeting .

An amount equivalent to 10% of the Item amount shall be kept in Deposit for 10 years and shall be released on completion of 10 years after certified date of completion.

<p>This item shall be carried out for Give way Sign Sign boards as per Detailed Specification of Item No. 32 as above except the size of the board shall be 90 x 90 x 90 cms. equilateral Triangular as per Design and shall be fixed on C.C. Block of 45x45x60cm.s as above.</p>
--

Item No 46.**Route Marker Sign**

Route Marker sign :-Providing and fixing sign boards made out of 2.0 mm aluminium sheet / 4 mm ACP (Aluminum composite Panel); size 60x45 cm rectangular plus 30x25cm additional plate as per design of IRC-67-2012. Pre treated with phospheting process & acid etching; coated with one coat of epoxy primer and two coats of best quality epoxy paint ;reflectorised with Micro Prismatic Grade retro reflectivesheeting of Type- 11 as per ASTM D-4956 and latest M.O.S.T.Specifications; 3.6 mtr long stand post of 75 x 75 x 6mm / 65NB Circular MS Pipe as required and frame fabricated from suitable size iron angle of 35x 35 x 3mm; painted with bestquality epoxy coatings in black and white bends. the details of symbol or inscription / numerals for each board shall be as per the instruction of engineer in charge.The fixing at site shall be in 1:2:4 CC blockof size 45 x 45 x 60 Cms. for each leg.including excavation, curing etc.complete under the supervision of engineer in charge. A warranty for 10 years for the Retro reflective sheeting from original manufacturer & a certified copy of 3 year outdoor exposure test report from third party test lab for the product offered shall be submitted by contractor. (A) Class-C Type-11 Retro Reflective sheeting -
(B) Class-B Type-4 Retro Reflective sheeting

A warranty for 7 years for the Retro reflective sheeting from original manufacturer & a certified copy of 3 year outdoor exposure test report from third party test lab for the product offered shall be submitted by contractor. (B) Class-B Type-4 Retro Reflective sheeting .

An amount equivalent to 10% of the Item amount shall be kept in Deposit for 10 years and shall be released on completion of 10 years after certified date of completion.

This item shall be carried out for Route Marker Sign Sign boards as per Detailed Specification of Item No. 32 as above except the size of the board shall be 30 x 25 cms. Rectangle as per Design and shall be fixed on C.C. Block of 45x45x60cm.s as above.

Item No 47.

Distance Informatory / Destination Sign

Distance Informatory / Destination Sign :-Providing and fixing sign boards made out of 2mm aluminium sheet / 4mm ACP (Aluminum composite Panel); size 180x120 cms. rectangular as per design of IRC-67-2012. Pre treated with phosphating process & acid etching; coated with one coat of epoxy primer and two coats of best quality epoxy paint ;reflectorised with Micro Prismatic Grade retro reflectivesheeting of Type-11 as per ASTM D-4956 and latest M.O.S.T.Specifications; 4.0mtr long (2 Nos.) stand post of 75 x 75 x 6mm / 65NB Circular MS Pipe as required and frame fabricated from suitable size iron angle of 50 x 50 x 5mm; painted with bestquality epoxy coatings in black and white bends. The details of symbol foreach board shall be as per theinstruction of engineer in charge. The fixing at site shall be in 1:2:4 CC blockof size 45 x 45 x 60 Cms. for each leg.including excavation, curing etc.complete under the supervision of engineer in charge. A warranty for 10 years for the Retro reflective sheeting from original manufacturer & a certified copy of 3 year outdoor exposure test report from third party test lab for the product offered shall be submitted by contractor. (A) Class-C Type-11 Retro Reflective sheeting

(B) Class-B Type-4 Retro Reflective sheeting

A warranty for 7 years for the Retro reflective sheeting from original manufacturer & a certified copy of 3 year outdoor exposure test report from third party test lab for the product offered shall be submitted by contractor. (B) Class-B Type-4 Retro Reflective sheeting .

An amount equivalent to 10% of the Item amount shall be kept in Deposit for 10 years and shall be released on completion of 10 years after certified date of completion.

<p>This item shall be carried out for Distance Informatory / Destination Sign Sign boards as per Detailed Specification of Item No. 32 as above except the size of the board shall be 180x120 cms Rectangle as per Design and shall be fixed on C.C. Block of 45x45x60cm.s as above.</p>

Item No 48.**Diversion Ahead Sign**

Diversion Ahead Sign :-Providing and fixing sign boards made out of 2mm aluminium sheet / 4mm ACP (Aluminum composite Panel); size 180x60 cms. rectangular as per design of IRC-67-2012. Pre treated with phospheting process & acid etching; coated with one coat of epoxy primer and two coats of best quality epoxy paint ; reflectorised with High Intensity Prismatic Grade retro reflectivesheeting of Type-4 as per ASTM D-4956 and latest M.O.S.T.Specifications; 3.1 mtr long stand post (2 Nos.) of Iron Angle 50 x 50 x 5mm / 50NB Circular MS Pipe as required and frame fabricated from suitable size iron angle of 35 x 35 x 3mm; painted with bestquality epoxy coatings in black and white bends. The details of symbol for each board shall be as per the instruction of engineer in charge. The fixing at site shall be in 1:2:4 CC blockof size 45 x 45 x 60 Cms. for each leg including excavation, curing etc.complete under the supervision of engineer in charge. A warranty for 7 years for the Retro reflective sheeting from original manufacturer & a certified copy of 3 year outdoor exposure test report from third party test lab for the product offered shall be submitted by contractor. (B) Class-B Type-4 Retro Reflective sheeting

(B) Class-B Type-4 Retro Reflective sheeting

A warranty for 7 years for the Retro reflective sheeting from original manufacturer & a certified copy of 3 year outdoor exposure test report from third party test lab for the product offered shall be submitted by contractor. (B) Class-B Type-4 Retro Reflective sheeting .

An amount equivalent to 10% of the Item amount shall be kept in Deposit for 10 years and shall be released on completion of 10 years after certified date of completion.

<p>This item shall be carried out for Diversion Ahead Sign Sign boards as per Detailed Specification of Item No. 32 as above except the size of the board shall be 180 x 60 cms. Rectangle as per Design and shall be fixed on C.C. Block of 45x45x60cm.s as above.</p>
--

Item No 49.**Men at Work Sign**

Men at work (Heavy) sign :-Providing and fixing sign boards made out of 2mm aluminium sheet / 4mm ACP (Aluminum composite Panel); size 120cm x 90cm as per design of IRC-67-2012. Pre treated with phospheting process & acid etching; coated with one coat of epoxy primer and two coats of best quality epoxy paint ; reflectorised with High Intensity Prismatic Grade retro reflective sheeting of Type-4 as per ASTM D-4956 and latest M.O.S.T.Specifications; 3.6 mtr long stand post (2 Nos.) of Iron Angle 75 x 75 x 6mm / 65NB Circular MS Pipe as required and frame fabricated from suitable size iron angle of 50x50x5mm; painted with best quality epoxy coatings in black and white bends. the details of symbol or inscription / numerals for each board shall be as per the instruction of engineer in charge. The fixing at site shall be in 1:2:4 CC block of size 45 x 45 x 60 Cms. for each leg including excavation, curing etc.complete under the supervision of engineer in charge. A warranty for 7 years for the Retro reflective sheeting from original manufacturer & a certified copy of 3 year outdoor exposure test report from third party test lab for the product offered shall be submitted by contractor. (B) Class-B Type-4 Retro Reflective sheeting

(B) Class-B Type-4 Retro Reflective sheeting

A warranty for 7 years for the Retro reflective sheeting from original manufacturer & a certified copy of 3 year outdoor exposure test report from third party test lab for the product offered shall be submitted by contractor. (B) Class-B Type-4 Retro Reflective sheeting .

An amount equivalent to 10% of the Item amount shall be kept in Deposit for 10 years and shall be released on completion of 10 years after certified date of completion.

<p>This item shall be carried out for Men at Work Sign Sign boards as per Detailed Specification of Item No. 32 as above except the size of the board shall be 60 x60 x 60 cms. equilateral Triangular as per Design and shall be fixed on C.C. Block of 45x45x60cm.s as above.</p>
--

Item No 50.

Portable Barricade in Construction Zone (Installation of a steel portable barricade with horizontal rail 300 mm wide, 2.5 m in length fitted on a 'A' frame made with 45 x 45 x 5 mm angle iron section, 1.5 m in height, horizontal rail painted (2 coats) with yellow and white stripes, 150 mm in width at an angle of 45°, 'A' frame painted with 2 coats of yellow paint, complete as per IRC:SP:55-2001)

1. Work shall be carried out as per standard practice, drawings and as directed by Engineer in charge. Allowing for movement of traffic as per drawing and directed by Engineer as per site requirements.
2. Excavations for open foundations as well as for pile cap at some locations are to be carried out on existing roads, where the traffic is of mixed character viz. slow and freight traffic including pedestrian, cyclists etc. for enclosing and confining the area of the actual construction, a module of 1.8m height M.S. CGI / CRC plates fixed on MS Channel /Angle posts shall be provided to cover area of working.
3. The rate covers all labour and supply of required material viz. GI/CRC sheets, M S post angle (45 x 45 x 5mm) / Channels, at site, erecting including digging hole in pavement structure and fixing MS posts in the existing ground by any stable and fixed devices, painting, providing road sign boards with blinkers as may be directed by the Engineer-in charge.
4. The rate shall be paid on the basis of no. or as may be required height of enclosure used.
5. Contractor shall have to carry out frequent cleaning, washing & painting of portable barricade as instructed by Engineer in charge.
6. Payment for this item shall be made only when the barricading is made as per drawing & specification of tender documents. If barricading is not as per tender provision then no payment shall be made.

The mode of payment shall be in per No. basis

Item No 51.

Standard Delineator: Providing and fixing Standard Metal Delineator consisting of minimum retro reflective unit exposed area of 330 cm² white color, full cube corner micro prismatic non-metallic retro reflective sheeting on each side conforming with IRC 67-2012 and meeting the coefficient of retro reflection values as per ASTM D 4956 Type XI table specification. The delineator shall be painted with powder coat of minimum 401 microns thickness, on top of which retro reflective sheeting shall be pasted on both sides. The structure shall be manufactured in roll forming process and shall have height not less than 800 mm above the ground, width not less than 100 mm and shall extend not more than 300 mm below the ground while being installed, height of sheeting should be minimum 150 mm whereas width of sheeting should not be less than 75 mm (should be placed every alternative 15cm), The front and the back faces of the delineator should be curved with a radius of not more than 200 mm and with delta angle (or central angle of curve) lying between 20 and 30, to increase the visibility of delineator for vehicles moving in continuous curves. The delineator shall have grooves across the length to make the reflective sheets vandal-proof. The delineator is meant for application on gaps in median, traffic islands, dangerous bends, roundabouts, narrow bridge etc. or as desired by site engineer.

1.0 General

The colour, configuration, size and location of **standard metal delineator** for highways other than Expressways shall be in accordance with the Code of Practice for Road Signs, IRC:67-2012 or as shown on the drawings or as directed by the Engineer.

The **standard metal delineator** shall be protective grill reflectorised as shown on the drawings or as directed by the Engineer. It shall be of retro-reflectorised type and made of encapsulated lens type reflective sheeting vide Clause 801.3, fixed over retro reflective sheeting as per these specifications.

In general, cautionary and mandatory signs shall be fabricated through process of screen printing. In regard to informatory signs with inscriptions, either the message could be printed over the reflective sheeting, or cut letters of non-reflective black sheeting used for the purpose which must be bonded well on the base sheeting as directed by the Engineer.

1.2 Materials :

The various materials and fabrication of the standard metal delineator shall conform to the following requirements.

The adhesive materials shall be of standard quality and it shall be high resistance quality against heavy moving vehicles.

The materials shall be used for the body of the **standard metal delineator** is of high density PVC materials.

The dimensions and size of the **standard metal delineator** shall be as per IS standard. The retro-reflective sheeting used on the **standard metal delineator** shall consist of the white or coloured sheeting having a smooth outer surface which has the property of retro reflection over its entire surface. It shall be weather resistant and show colour fastness. It shall be new and unused and shall show no evidence of cracking, scaling, pitting, blistering, edge lifting or curling and shall have negligible shrinkage or expansion. A certificate of having tested the sheeting for these properties in an unprotected outdoor exposure facing the sun for two years and its having passed these tests shall be obtained from a reputed laboratory, by the manufacturer of the sheeting. The reflective sheeting shall be either of Engineering Grade material with enclosed lens or of High Intensity Grade with encapsulated lens. The type of the sheeting to be used would depend upon the

hierarchy and importance of the road.

High intensity grade sheetings : This sheeting shall be of encapsulated lens type consisting of spherical glass lens, elements adhered to a synthetic resin and encapsulated by a flexible, transparent water-proof plastic having a smooth surface. The retro-reflective surface after cleaning with soap and water and in dry condition shall have the minimum co-efficient of retro-reflection determined in accordance with ASTM Standard E:810).

TABLE 800.1
ACCEPTABLE MINIMUM CO-EFFICIENT OF RETRO-REFLECTION FOR HIGH
INTENSITY GRADE SHEETING

[CANDEL AS PER LUX PER SQUARE METRE]

Observation (in degree)	Entrance angle (in degree)	White	Yellow	Orange	Green / Red	Blue
0.2	-4	250	170	100	45	20
0.2	+30	150	100	60	25	10
0.5	-4	95	62	30	15	7.5
0.5	+30	65	45	25	10	5

When totally wet, the sheeting shall not show less than 90 percent of the values of retro reflective indicated in Table 800-1. At the end of 7 years, the sheeting shall retain at least 75 percent of its original retro-reflectance.

1.3 Processed and applied in accordance with recommended procedures, the reflective material shall be weather resistant and, following cleaning, show no appreciable discolouration, cracking, blistering or dimensional change and shall not have less than 50 percent of the specified minimum reflective intensity values (Table 100.1) when subjected to accelerated weathering for 1000 hours, using type E or EH Weatherometer (AASHTO Designation M 268).

1.4 INSTALLATION:

The **standard metal delineator** shall be installed directly on road surface, after cleaning completely by removing all dust and other foreign materials from the surface of the road.

1.5 MEASUREMENT FOR PAYMENT :

The measurement of **standard metal delineator** shall be in numbers, these shall be measured in **No.**

1.6 RATE :

The Contract unit rate shall be payment in full for the cost of making **Molded Twin Shanks Raised Pavement Markers** including all materials, installing it at the site and incidentals to complete the work in accordance with the specifications.

Item No 52.

Type - A, "W" : Metal Beam Crash Barrier (Providing and erecting a "W" metal beam crash barrier comprising of 3 mm thick corrugated sheet metal beam rail, 70 cm above road/ground level, fixed on ISMC series channel vertical post, 150 x 75 x 5 mm spaced 2 m centre to centre, 1.8 m high, 1.1 m below ground/road level, all steel parts and fitments to be galvanised by hot dip process, all fittings to conform to IS:1367 and IS:1364, metal beam rail to be fixed on the vertical post with a spacer of

810. METAL BEAM CRASH BARRIERS

810.1. General

810.1.1. This work shall consist of furnishing and erection of metal beam crash barrier of dimensions and at locations as shown on the drawing (s) or as directed by the Engineer.

810.1.2. Metal beam crash barrier shall generally be located on approaches to bridge structures, at locations where the embankment height is more than 3 metres and at horizontal curves and location as specified by Engineer in charge.

810.2. Materials

810.2.1. Metal beam rail shall be corrugated sheet steel beams of the class, type, section and thickness indicated on the plans. Railing posts shall be made of steel of the section, weight and length as shown on the plans. All complete steel rail elements, terminal sections, posts, bolts, nuts, hardware and other steel fittings shall be galvanized. All elements of the railing shall be free from abrasions, rough or sharp edges and shall not be kinked, twisted or bent.

810.2.2. Steel beam elements and terminal sections shall be galvanized (zinc coated, 0.55 kg per square metre, minimum single spot) unless otherwise specified. The galvanizing on all other steel parts shall conform to the relevant IS Specifications. All fittings (bolts, nuts, washers) shall conform to the IS : 1367 and IS : 1364. All galvanizing shall be done after fabrication.

810.2.3. Concrete for bedding and anchor assembly shall conform to section 1700 of these Specifications.

810.3. Construction Operations

810.3.1. The line and grade of railing shall be true to that shown on the plans. The railing shall be carefully adjusted prior to fixing in place, to ensure proper matching at abutting joints and correct alignment and camber throughout their length. Holes for field connections shall be drilled with the railing in place in the structure at proper grade and alignment.

810.3.2. Unless otherwise specified on the drawing, railing steel posts shall be given one shop coat of paint (primer) and three coats of paint on structural steel after erection, if the sections are not galvanised. Any part of assembly below ground shall be painted with three coats of red lead paint.

810.3.3. Splices and end connections shall be of the type and designs or shown on the plans and shall be of such strength as to develop full design strength of the rail elements.

810.4. Installation of Posts

810.4.1. Holes shall be dug or drilled to the depth indicated on the plans or posts may be driven by approved methods and equipment, provided these are erected in proper position and are free from distortion and burring or any other damage.

- 810.4.2.** All post holes that are dug or drilled shall be of such size as will permit proper setting of the posts and allow sufficient room for back filling and tapping.
- 810.4.3.** Holes shall be back filled with selected earth or stable materials in layers not exceeding 100 mm thickness and each layer shall be thoroughly tamped and rammed. When back filling and tamping are completed, the posts or anchors shall be held securely in place.
- 810.4.4.** Post holes that are drilled in rock and holes for anchor posts shall be back filled with concrete.
- 810.4.5.** Posts for metal beam guardrails on bridges shall be bolted to the structure as detailed on the plans. The anchor bolts shall be set to proper location and elevation with templates and carefully checked.

810.5. Erection

- 810.5.1.** All guardrail anchors shall be set and attachments made and placed as indicated on the plans or as directed by the Engineer.
- 810.5.2.** All bolts or clips used for fastening the guardrail or fittings to the posts shall be drawn up tightly. Each bolt shall have sufficient length to extend at least 6 mm through and beyond the full nut, except where such extensions might interfere with or endanger traffic in which case the bolts shall be cut off flush with the nut.
- 810.5.3.** All railings shall be erected, drawn and adjusted so that a length of 3 metre. The railing barrier shall be erected true to line and grade.

810.6. Tolerance

- 810.6.1.** The posts shall be vertical with a tolerance not exceeding 6 mm in a length of 3 metre. The railing barrier shall be erected true to line and grade.

810.7. Measurements for Payment

- 810.7.1.** Metal beam railing barriers will be measured by **linear metre** of completed length as per plans and accepted in place. Terminals/anchors of various types shall be paid for by numbers.
- 810.7.2.** No measurement for payment shall be made for projections or anchors beyond the end posts except as noted above. Furnishing and placing anchor bolts and/or devices for guard rail posts on bridges shall be considered incidental to the construction and the costs thereof shall be included in the price for other items of construction.
- 810.7.3.** No measurement for payment will be made for excavation or back filling performed in connection with this construction.

810.8. Rate

The Contract unit rate shall include full compensation for furnishing of labour, materials, tools, equipments and incidental costs necessary for doing all work involved in constructing the metal beam railing barrier complete in place in all respects as per these Specifications.

Item No 53.

Sign board per Square Meter :-Providing and fixing sign boards made out of 2mm aluminium sheet / 4mm ACP (Aluminum composite Panel); size 1meter x1 meter as per design of IRC-67-2012. Pre treated with phosphating process & acid etching; coated with one coat of epoxy primer and two coats of best quality epoxy paint ;reflectorised with Micro Prismatic Grade retro reflective sheeting of Type-11 as per ASTM D-4956 and latest M.O.S.T.Specifications; 4 mtr long stand post (2 Nos.) of 75 x 75 x 6mm / 65NB Circular MS Pipe as required and frame fabricated from suitable size iron angle of 50 x 50 x 5mm; painted with best quality epoxy coatings in black and white bands. the details of symbol or inscription / numerals for each board shall be as per the instruction of engineer in charge.The fixing at site shall be in 1:2:4 CC block of size 45 x 45 x 60 Cms. for each leg.including excavation, curing etc.complete under the supervision of engineer in charge. A warranty for 10 years for the Retro reflective sheeting from original manufacturer & a certified copy of 3 year outdoor exposure test report from third party test lab for the product offered shall be submitted by contractor. (A) Class-C Type-11 Retro Reflective sheeting

(B) Class-B Type-4 Retro Reflective sheeting

A warranty for 7 years for the Retro reflective sheeting from original manufacturer & a certified copy of 3 year outdoor exposure test report from third party test lab for the product offered shall be submitted by contractor. (B) Class-B Type-4 Retro Reflective sheeting .

An amount equivalent to 10% of the Item amount shall be kept in Deposit for 10 years and shall be released on completion of 10 years after certified date of completion.

<p>This item shall be carried out for Sign boards as per Detailed Specification of Item No. 32 as above except the size of the board shall be 1 x 1 ms. equilateral Triangular as per Design and shall be fixed on C.C. Block of 45x45x60cm.s as above.</p>
--

Item No 54.

Providing & laying rubble stone pitching 22.5 cm thick including preparing the surface and providing panelwall for pitching 3.0 x 3.0 m of cement concrete 1:2:4 including pointing on pitching in CM 1:3 including curing, cost of all materials and labour.

1.0 Rubble stone pitching

- 1.1** The work shall consist of covering the slopes of high banks, training works and road embankment with rubble, over a layer of murrum bedding with **panel wall for pitching 3.0 x 3.0 mt. of cement concrete 1:2:4 including pointing on pitching in C.M. 1:3 as**
- 1.2** Rubble subject to marked deterioration by water or weather will not be accepted. The rubble shall be sound hard, durable and fairly regular in shape and its thickness in any one direction shall not be less than the thickness of pitching as specified in the item and thickness of the rubble at any place shall not be less by 15% of the thickness specified. The largest rubbles procurable shall be supplied on site. The sizes of spalls shall be minimum 25 mm and shall be suitable to fill the voids in the pitching. Thickness of the pitching shall be as specified in the pitching item. (G.C. No. SSR/ 2080 IB 547/28/C Dated 6th March
- 1.3** Before laying the pitching the sides of banks shall be trimmed to the required slopes and profiles put up by means of line and pegs at intervals of 3 meters to ensure regular straight work and uniform slope throughout. Depressions shall be filled and thoroughly compacted.
- 1.4** Murrum for bedding shall be laid over the prepared base and suitably compacted to a thickness 150 mm. Quality of murrum will be as per its relevant specifications.
- 1.5** The rubble pitching shall commence in a trench below the toe of the slope. Rubble shall be placed by derrick or by hand to the required length, thickness and depth conforming to the drawings. Rubbles shall be set normal to the slope and placed so that the largest dimension is perpendicular to the face of the slope, unless such dimensions are greater than the specified thickness of pitching. The largest rubbles shall be placed in the bottom courses and used as headers for subsequent courses. When full depth of pitching can be formed with single rubble, the rubble shall be laid breaking joints and all interstices between adjacent rubbles shall be filled in with spalls of the proper size and wedged in with hammers to ensure tight packing. Pitching shall be done in panels of 3.0 M x 3.0 M with a **45 cm. wide and 22.5 cm. deep** band all around.

2.0 Stone Masonry

- 2.1** Panel wall for pitching **3.0 x 3.0 mt. of cement concrete 1:2:4** or as per guidelines of Engineer in charge in case of irregular dimensions.
- 2.2** Necessary curing shall be carried out.

3.0 Cement pointing

- 3.1** For a surface which is to be subsequently jointed, the joints shall be squarely raked out to a depth of 15 mm. while the mortar is still green. The raked joints shall be well brushed to remove dust and loose particles and the surface shall be thoroughly washed with water, cleaned and wetted.
- 3.2** Cement and sand shall be mixed in proportions as specified in the spec. Cement and sand shall be proportioned by volume after making due allowance for bulking. The required quantity of water shall then be added and the mortar mixed to produce workable

- 3.3** The mixing shall be done intimately by hand mixing. The operation shall be carried out on a clean watertight platform and cement and sand shall be first mixed dry in the required proportion to obtain a uniform colour and then the mortar shall be mixed for at least two minutes after addition of water. In case of cement mortar, that has stiffened because of evaporation of water, the same shall be re-tempered by adding water as frequently as needed to restore the requisite consistency but this re-tempering shall be permitted only with thirty minutes from the time of addition of water at the time of initial mixing.
- 3.4** For pointing, the mortar shall be filled and pressed into the raked out joints before giving the required finish. The pointing shall then be finished to proper type given on the drawings. If type of pointing after the mortar has been filled and pressed into the joints and finished off level with the edge of the bricks, it shall while still green ruled along the centre with a half round tool of such width as may be specified by the Engineer-in-charge. The superfluous mortar shall then be cut off from the edges of the lines and the surface of masonry shall also be cleaned of all mortar.
- 3.5** Curing shall be started as soon as the mortar used for finishing has hardened sufficiently not to be damaged when watered. It shall be kept wet for a period of at least 7 days. During this period shall be suitably protected from all damages.
- 3.6** Stage scaffolding shall be approved for the work. This shall be independent of the
- 3.7** Payment shall be made on **Square Meter** basis of the finished work. If directed by the Engineer-in charge for measurement the materials may have to be stacked at site before laying and nothing extra will be paid to the Contractor for this stacking. Preparation of base for laying bedding shall be deemed incidental to the work.
- 3.8** The rate shall include the cost preparing the base, putting to the profiles, providing, laying and compacting the murrum bedding and rubble pitching of dry rubble, **making panels of 3.00 x 3.00m of cement concrete 1:2:4 including pointing on pitching in C.M. 1:3 including curing, cost of all materials and labour as directed** as per embankment slopes to specified thickness, lines curves, slopes and levels and all labour and material as well as tools and plant required of the work.

Item No 55.

Providing and laying in position C.C 1;2:4 water chute as directed including with all necessary excavation curing incl all material labour etc complete

The water chutes is to be constructed as per detail drawing. The water chutes shall be constructed to the line and grade. The dimension of water chutes is as per drawing.

The necessary excavation shall be carried out as per instruction and drawing. The excavation shall be carried out as per specification of Item No. 15 and for cement concrete work the specification of Item No. 18 shall be followed except that the grade of concrete shall be 1:2:4.

All the corner in the finished work shall be true sharp and clean. The entire work shall be carried out as per the instruction of Engineer-in-charge.

The water chutes shall be measure in Running meter. The rate of water chutes is includes with the cost of labour, materials, tools plants from work, required for doing the work.

The payment shall be made on **Running meter** basis.

Item No 56.

Wall painting two coats with plastic emulsion paint of approved brand and manufacturer on wall surfaces to give an even shade including thoroughly brushing the surface to remove all dirt, dust, mortar drops and other foreign matter.

General

This work shall consist of painting the walls with **weather proof exterior emulsion paint on wall surfaces** of the shape and dimensions shown on the drawings and conforming to these specifications or as approved by the Engineer in charge.

MATERIALS**1.0 Exterior Emulsion Paint**

Exterior emulsion paint shall be of specified colour as approved by Engineer in charge the ready mixed exterior emulsion paint shall not be allowed, If however ready mix emulsion paint of specified shade or tint is not available white ready mixed paint with approved Steiner will be allowed in such case the contractor shall ensure that the shade of the paint so allowed shall be uniform exterior emulsion paint shall meet with the following general

1. Exterior emulsion paint shall not show excessive setting in freshly opened full can and shall easily be redepressed with a paddle to a smooth homogeneous state. The exterior emulsion paint shall show no curding, livering cracking or colour separation and shall be free from lumps and skins.
2. The exterior emulsion paint as received shall brush easily possess good leveling properties and show no running or sagging tendencies.
3. The exterior emulsion paint shall not skin within 48 hours in a three quarters filled closed container
4. The exterior emulsion paint shall dry to a smooth uniform finish free from roughness grit unevenness and other imperfections
5. Ready mix exterior emulsion paint if allowed for specified shade, shall be used exactly as received from the manufacturers and generally according to their instruction and without any admixtures whatsoever.

2.0 WORKMAN SHIP**2.1 Scaffolding :**

Where scaffolding is required, it shall be erected in such a way that as far as possible no part of scaffolding shall rest against the surface to be distempered. A properly secured strong and well tied suspended platform (joola) may be used for distempering. Where ladders are used, pieces of old gunny bags.

3.0 Application coat :

The weather proof **exterior emulsion paint on wall surfaces** shall be diluted with water or any other prescribed thinner in a manner recommended by the manufacturer only. Sufficient quantity of distemper required for a day's work shall be prepared.

- 3.1** For undecorated surfaces, after the primer coat is dried for at least 48 hours, the surface shall be lightly sand papered to make it smooth for receiving the exterior emulsion paint, taking care not to rub out the priming coat. All loose particles shall be dusted off after rubbing. Minimum two coats of the exterior emulsion paint shall be applied with brushes in horizontal strokes followed immediately by vertical strokes which together shall constitute

one coat. The subsequent coats shall be applied after a time interval of at least 24 hours between consecutive coats to permit proper drying of the preceding coat. The finished surface shall be even and uniform without patches, brush marks, distemper drops etc.

- 3.2** Sufficient quantity of the weather proof **exterior emulsion paint** shall be mixed to finish one room at a time.

4.0 MODE OF MEASUREMENT & PAYMENT :

- 4.1** The unit rate wall painting with weather proof **exterior emulsion paint** shall include the cost of all materials, tools and plant required for mixing, cleaning brushing sand papering & painting with all required specials and Lapi compound, finishing as per direction of the Engineer-in-charge, and all other incidental expenses for producing pipe line work of specified diameter to complete the structure or its components as shown on the drawings and according to these specifications. They shall also include the cost of making, fixing and removing of all scaffolding and forms required for the work.
- 4.2** The rate of wall painting with weather proof **exterior emulsion paint** shall include the cost of all labour, materials tools and plant scaffolding and all incidental expenses as described herein above.
- 4.3** The wall painting with weather proof **exterior emulsion paint** shall be measured for its length and height limiting dimensions to those specified on plan or as directed. The rate shall be for a unit of one square meter.
- 4.4** The payment will be made on **square meter** basis of the finished work.

Item No 67.

Providing and laying rubble for apron (each stone weighting not less than 40Kg.) including and packing and filing in the interestices with quarry-spalls.

67. The work shall consist of laying boulders directly on the prepared surface for protection against scour.
68. The rubble stones used in foundation shall be sound, hard, durable & fairly regularly in shape. Stone subject to marked deterioration by water or weather shall not be used. The thickness and shape of rubble shall be as indicated on the drawings or as directed by the Engineer-in-charge. The surface on which the rubble is to be laid shall be levelled and prepared for the length and width as shown on the drawings. The size of stone shall be as large as possible & weight shall be as specified in the item but in no case any fragment shall weight less than 40 Kg. The specific gravity of stone shall be as high as possible and it shall not be less than 2.50. To ensure regular and orderly disposition of the full intended quantity of stone in the foundation, template cross walls in dry masonry shall be built about a metre wide and to the full weight of the specified thickness of the apron at intervals of 30 metres and all along the length and width of the apron. Within these walls, the stone then shall be hand packed.
69. Payment shall be made on Cu.m. basis of chata. The materials shall have to be stacked at site before laying. Preparation of base for laying bedding shall be deemed incidental to the work nothing shall deducted for voids.
70. The rate shall include cost of materials, labour & tools to complete the job.
71. Payment shall be made on Cu.m. basis.