

Name of work:- Renovation and Repair to Geological office at 4/7 in MS Bldg at Rajkot (Pro. Aluminium section, false ceiling, colour work, furniture and misc. civil work)(Deposit work)

Statement of laboratory test to be carried out during execution of work as per Govt. in (R&B) Dept. Sachivalaya Gandhinagar No. S.R.R./1083/Q.C./5415/DT.20-2-1993.

MATERIAL TEST SCHEDULE

Tender item	Description of item in brief	Material to be tested	Test Qty	Name of laboratory Test	Frequency	Total no. of Test	Remark
Teak wood	Teak wood	Teak wood	Sqmt	1. Anatomy test 2. Density test 4. Moisture Content test 5. Weight hardness colour	1 Sample per Lot	As frequency	per As per required while execution

Note : The above material shall be supplied by the Contractor at his own cost to the Government Laboratory (G. E.R.I.) as per Schedule mentioned above directed by the Engineer-in-charge 1.00% (One percent) of the estimated cost after deducting the controlled material as per “Schedule “A” of this agreement shall be deducted from the bills of the contractor as per Government Instruction all testing charges shall be paid by the Department.

**Deputy Executive Engineer
City (Building) Sub Division
Rajkot**

**Executive Engineer
City (R&B) Division
Rajkot**