

Name of work :- SR to office of (R&B) Circle-1 & Primary inquiry office (CLF-9 Campus) at Rajkot (Pro. Chair, Sofa , Partition and Misc Minor civil Work) (JobNo.City/Raj/SR/NR/26-27/36)

Specification Index

Sr. No.	Description	Vol. No.	Page No.	Para No.	Remarks
1	2	3	4	5	6
1	Providing and placing Wooden VISITOR CHAIR (HOF -orient arm wooden chair / Equivalent Make) of Wooden frame structure of approved shape using high density U foam covering good quality of tapestry cloth on seat back as per requirement and the job as per design /drawing and shall get approved from engineer in charge	II		As per seprate specification attached	
2	Providing and placing Wooden VISITOR CHAIR (HOF-Epic beige PU / Equivalent Make) of Wooden frame structure of approved shape using high density U foam covering good quality of tapestry cloth on seat back as per requirement and the job as per design /drawing and shall get approved from engineer in charge	II		As per seprate specification attached	

1	2	3	4	5	6
3	Providing and placing Centre Wooden (HOF-227 A / Equivalent Make) Ractangular Table With round edge 12mm thick transperent table top glass as per requirement and the job as per design /drawing and shall get approved from engineer in charge	II		As per seprate specification attached	
4	Providing and supplying THREE seater OFFICE SOFA with Premium Fabric material and wood polish (HOF VERO-3 series / Equivalent Make) etc comp as per requirement and the job as per design /drawing and shall get approved from engineer in charge	II		As per seprate specification attached	
5	Providing and supplying TWO seater OFFICE SOFA with Premium Fabric material and wood polish (HOF VERO - 2 series / Equivalent Make) etc comp as per requirement and the job as per design /drawing and shall get approved from engineer in charge	II		As per seprate specification attached	
6	Providing and placing Centre Wooden (HOF / Equivalent Make) Round Table With 12mm thick transperent table top glass as per requirement and the job as per design /drawing and shall get approved from engineer in charge	II		As per seprate specification attached	

1	2	3	4	5	6
7	Providing and placing Centre Wooden (HOF-307 A / Equivalent Make) Round Coffee Table with 12mm thick transparent table top glass as per requirement and the job as per design /drawing and shall get approved from engineer in charge	II		As per seprate specification attached	
8	Providing and supplying (HOF Ventis / Equivalent Make) Make REVOLVING premium Executive Revolving Chair (HIGH BACK) including Aluminum Alloy Base with knee tilt synchro mechanism with Adjustable Armrests, single position back lock, seat and back, made from high density U -foam, arms, S.S. pipe with PU pad etc comp as per requirement and the job as per design /drawing and shall get approved from engineer in charge	II		As per seprate specification attached	
9	Providing and placing Wooden Glider (HOF M68+M68 P1 Rocking Chair / Equivalent Make) of Wooden frame structure of approved shape using high density U foam covering good quality of tapestry cloth on seat back as per requirement and the job as per design /drawing and shall get approved from engineer in charge	II		As per seprate specification attached	

1	2	3	4	5	6
10	Providing and fixing Wooden tiles flooring using 8 MM thick Wooden tiles of Std. company including fixing with necessary solution for all floors.	II		As per seprate specification attached	
11	Providing supplying and laying wooden partition with one side 12 mm thick marine water proof plywood and other side 8 mm thick marine water proof plywood with framing of 50 x 37.50 mm thick alluminium pipe with 600 mm distance horizontal and vertical both way with 1 mm premium lamination sheet with require all labour, material and fixture etc. complete	II		As per seprate specification attached	
12	Providing and supplying Office Rectangular Metal (Powder coated) Cupboard (Godrej/ Equivalent Make) 1980mm Height X 900mm width and 2 door, 4 shelves with necessary stainless steel fitting and hinges, with key Lock etc comp design approved by Engineer-in-charge.	II		As per seprate specification attached	

1	2	3	4	5	6
13	Providing and fixing wall paper of premium quality acrylic coated two to three layers material, pretreated, non woven, washable and strippable, PVC base material including fixing the wall paper with glue as directed by Engineer-in-charge.	II		As per seprate specification attached	
14	Providing and fixing BOX type cupboard of size 450mm depth with using 18mm thick plywood in outer frame, shutter and shelves with both side laminated with 1mm thick decorative laminate sheet with necessary hardware materials like S.S. hinges handles and other fixture and fastening etc. complete or as directed.	II		As per seprate specification attached	
15	Providing and Fixing table top premium quality acrylic coated two to three layers material, pretreated, non woven, washable and strippable, PVC base material including fixing On table as design by Engineer - in - charge.	II		As per seprate specification attached	
16	Providing and placing Wooden Foot rest (42.5L x 12.5W x 29.5H CM) with Wooden frame structure as per requirement and the job as per design /drawing and shall get approved from engineer in charge	II		As per seprate specification attached	

1	2	3	4	5	6
17	Providing and supplying Two Seater Sleeper, 53.5" W 83" L Convertible Sofa Bed Couch Futon Couches with Premium Fabric material etc comp as per requirement and the job as per design /drawing and shall get approved from engineer in charge	II		As per seprate specification attached	
18	Providing and supplying of 12mm thick clear glass of table top and with polishing edge as design by Engineer - in - charge.	II		As per seprate specification attached	
19	Providing, Supplying and Fixing in Position Roller Blind as per instruction of Engineer-in-Charge. The Fabric shall be Woven using either Polyester or Fibre Glass Materials. The selection of Fabric Category i.e. Privacy / Black Out or Sheer Shade shall be done by EIC.	II		As per seprate specification attached	

1	2	3	4	5	6
20	Providing and Fixing Prepainted galvanized coated steel roof sheet semi corrugated (JSW) in salted colour having 0.50 MM thick & 6.00 MM thick insulation layer including fixing with SDS Screw to structural steel etc. complete as per instruction (Jindal or Eq. Made) of Engineer in Charge (Structural Sheet Shall be Paid Separately)	II		As per seprate specification attached	
21	Dismantaling of sheet roofing including ridges, Hips, Valleys, Gutters etc. stacking of serviceable materilas and disposal of unserviceable materials with all lead and lift.(i) G.I.sheet roofing.	I	149	20.27(ii)	
22	Providing and laying cement concrete 1:3:6 (1-Cement : 3- coarse sand : 6- Crushed stone aggregates 40 mmnominal size) and curing complete excluding cost of formwork in (A) Foundation and Plinth	I	38	5.3.2(A)	

1	2	3	4	5	6
23	Dismantling tiled of stone floors laid in mortar including stacking of serviceable materials and disposal of unserviceable materials with all lead and lift.	I	148	20.23	The dismantling work shall be carried out for all type of tiled or stone floor laid in mortar with due care that adjoining structure or man power may not be effected even if such accident happens it will be total liability of the contractor. The useful materials shall be the property of the contractor and a Fix amount as per Schedule-B shall be deducted from the First R.A. bill payable to the contractor
24	Steel work, riveted in built up sections framed work including cutting, hoisting, fixing in position and applying a priming coat of red lead paint. (A) In beams and joists, channels angles Tees, flats, with connecting plates or angle cleats as in main and cross beams. Hip and jack rafters, purlins conneted to common rafters and the like.	I	80	11.4(A)	Strucural Design shall preparad from recognized structural engineer from contrtractor's own cost. Before using got approved from Engineer-in-charge. Rate shall include complete item of work.
25	Providing and laying polished Kota stone slab flooring over 20mm (Average) thick base of cement mortar 1:6 (1-cement : 6-coarse sand) or L.M. 1.1.5 (1-Lime putty :1.5 - coarse sand) laid over and jointed with grey cement slurry mixed with pigment to match the shade of slab including rubbing and polishing etc. complete. (A) 25mm thick	I	98-99	14.43(A)	

1	2	3	4	5	6
---	---	---	---	---	---

26 Providing and fixing rolling shutters of approved make made of 80 mm wide M.S. laths inter-locked together through their entire length and jointed together at the ends by end locks mounted on specially designed pipe shaft with bracket plates, guide channels and arrangements for inside and outside locking with push-pull operation including the cost of hood cover and spring etc. complete.(A)
Shutters having width below 3.5 M.

27 Providing and fixing 19MM thick commercial plywood shutter using teak wood beading 1-MM thick lamination sheet as approved by Engineer-in-Charge. On front side including oil paint to C.B. shutter back side shutter beading and frame of door, necessary fixture and fastening and including finishing of the existing wall surface with colour touching matching with all labour and material etc. complete.

II

**As per seprate
specification attached**

**Deputy Executive Engineer
City (Building) Sub Division
Rajkot**

**Executive Engineer
City (R & B) Division
Rajkot**