

Name of Work:- Construction of fabrication shed for DCF Bunglow at Porbandar of Barda Sanctuary Range, Forest Division Porbandar

:: SCHEDULE B ::

Quantity	Unit	Item no.	Items of work	Total Rate	Amount
			Item No. 1		
4226.18	Kg	1	Providing and fixing fabricated structure of galvanised iron hollow pipe, angle, flat etc including cutting, binding, welding, bolting, hoisting etc complete as directed by engineer incharge	137.05	579197.96
			Item No. 2		
120.75	Sqm	2	Painting two coats and priming coat on new steel and other metal surface with enamel paint, brushing, interior to give an even shade including cleaning the surface an even shade including cleaning the surface of all dirt, dust and other foreign matter.	134.73	16268.64
			Item No. 3		
301.87	Sqm	3	Providing and fixing 3mm thick fiber glass or stone cloated Asphalt Shingles of size 200 x 1200 mm of any colour, shape and textured (Quality and design of Material to be approved by architect or person incharge and necessary certificate or testing results has to be provided) comprising 18 mm thick cement sheet and membrane to be fixed before Shingles to be fitted with necessary addhesive, chemicals, screws etc in true line and level including ridges complete as directed by person incharge.	2671.45	806430.61
				Total Rs.	1401897.21
				Say Rs.	1401897.21

