

Kaalol Nagar Palika, Kaalol

Name of Work: :Bid Documents for Construction work of Paver Block at Various Location at Kaalol Nagarpalika Under SJMSVY 2025-26 3rd Attempt

SCHEDULE - "B1"

Name of Work :Construction of Paver Block at Kasba vistar ma Sakilbhai na ghar thi Rajakbhai na ghar sudhi at Kaalol Nagarpalika Panchmahal

Item No.	Item	Total Qty.	Rate	Per	Amount
1	Box Cutting the road surface to Proper Slops and camber for making a base for road work including removing the excavated stuff and disposing on the road side slopes as directed up to 2 Km.lead				
		40.80	104.20	Cum	4251.36
2	Providing and laying cement concrete 1:4:8 (1-Cement : 4-coarse sand : 8- hand broken stone aggregates 40 mm nominal size) and curing complete excluding cost of formwork in (A) Foundation and Plinth				
		20.40	2721.47	Cum	55517.99
3	Providing and fixing pre-cast Rubber Dye / steel Dye inter locking concrete block 60mm thick with grade of concrete M300 pneumatic compressed / vibrated mechanically and as per approved design Confirming to IS 15658 : 2006 including 35 mm Sand layer for levelling and filling the joint with sand in proper line and level as per guidlines of IRC : SP 63-2018 etc. Complete.				
		204.00	686.90	Cum	140127.60
4	Providing and fixing pre-cast concrete kerb stone of gray cement based concrete block 30cm length,30cm height and 15cm thick of M200 grade concret as per approved design and including excavation for fixing in proper line and level,filling the joint with C:M 1:3 (1cement:3fine sand) etc complete.				
		110.00	383.38	Rmt	42171.80
5	Providing cement vata (10cm. x 10 cm. size) quarter round in cement mortar 1:1 including neat cement finishing, watering etc. complete.				
		55.00	23.68	Rmt	1302.40
	Total				243371.15
	Add 18% GST Charge				43806.81
	Total Amount				287177.95
	Add 3% Contingency				8615.34
	Add 1% QC Charge				2871.78
	Total				298665.07
	Say				298670.00