

Kaalol Nagar Palika, Kaalol

Name of Work: :Bid Documents for Construction work of Paver Block at Various Location at Kaalol Nagarpaqlika Under SJMSVY 2025-26 3rd Attempt

SCHEDULE - "B3"

Name of Work : Construction of Paver Block at Near Mahakali Mandir Gokarpura at Kaalol Nagarpalika Panchmahal.

Item No.	Item	Total Qty.	Rate	Per	Amount
1	Box Cutting the road surface to Proper Slops and camber for making a base for road work including removing the excavated stuff and disposing on the road side slopes as directed up to 2 Km.lead				
		34.00	104.20	Cum	3542.80
2	Providing and laying cement concrete 1:4:8 (1-Cement : 4-coarse sand : 8- hand broken stone aggregates 40 mm nominal size) and curing complete excluding cost of formwork in (A) Foundation and Plinth				
		17.00	2721.47	Cum	46264.99
3	Providing and fixing pre-cast Rubber Dye / steel Dye inter locking concrete block 60mm thick with grade of concrete M300 pnumatic compressed / vibrated mechanically and as per approved design Confirming to IS 15658 : 2006 including 35 mm Sand layer for levelling and filling the joint with sand in proper line and level as per guidlines of IRC : SP 63-2018 etc. Complete.				
		170.00	686.90	Cum	116773.00
4	Providing cement vata (10cm. x 10 cm. size) quarter round in cement mortar 1:1 including neat cement finishing, watering etc. complete.				
		78.00	23.68	Rmt	1847.04
				Total	168427.83
				Add 18% GST Charge	30317.01
				Total Amount	198744.84
				Add 2% Contingency	3974.90
				Add 1% QC Charge	1987.45
				Total	204707.19
				Say	204710.00