

BILL OF QUANTITY

Name of work:	Modification of Rodh River(Vahelo) For Clearance Water Way of Bavla Taluka from Ch. 0/000 Km to 48.00 Km under Sanand Irrigation Sub Division, Sanand.				
Item NO.	DESCRIPTION	QTY.	UNIT	RATE in Figures (Excluding GST)	AMOUNT
1-a	Jungle clearance of specified category and bushes for canal / dam work as directed with disposing materials etc. complete. (Excluding tree of girth above 0.50 mt) (ByMachinery) (By long reach hydraulic excavator) (a) Light Dense	57.39	Ha.	14493.00	831753.27
1-c	Jungle clearance of specified category and bushes for canal / dam work as directed with disposing materials etc. complete. (Excluding tree of girth above 0.50 mt) (ByMachinery) (By long reach hydraulic excavator) (c) Heavy Dense	161.39	Ha.	35200.00	5680928.00
2	Clearing the silt from the drain bed by digging the same to the required bed level and gradient including depositing the excavated earth regularly in spoil bank for utilizing the same preparing the bank safer breaking clods as and where directed for lead upto 50 m. and all lifts. FOR MAIN,LATERAL & SUB-LATERAL DRAINS.(BYMACHINERY)(By Long Reach Hyd Excavator)	381390.69	Cmt.	153.00	58352775.57
3	Earth work in embankment from borrow pits in all sorts of soil and soft murrum or other suitable strata as directed including breaking the clods and dressing to the design sections including cutting the proud section with lead as under and all lift including site clearing etc. complete. For all canal capacity (c) 200 to 1000 Mt.	14600.00	Cmt.	85.00	1241000.00
4	Excavation for C.O.T. work as per design in all sorts of soil & over burden including hard murrum incl. sorting,stacking and depositing materials with lead upto 1KM. and all lifts etc.comp.including dewatering	143625.00	Cmt.	91.00	13069875.00
	Total				79176331.84
In words Seven crores Ninety one Lakh Seventy six Thousands Three hundred Thirty one Rupees and Eighty four paisa Only					

I/We am/are willing to carry out the work at..... % above/below percent(Should be written in figures and words) of the

Estimated amount put to tender

Deduct.....% below

Net

In words

Estimated amount put to tender

Add.....% Above

Net

In words

1	The Contractor shall exhibit a board with detailed specification and details of work as directed by the Engineer-In-Charge for which no extra payment shall be made.
2	The labour cess will be deducted as per prevailing rules i.e. 1% of the work done.
3	GST and Income tax TDS will be deducted at a source while making payments of bills
4	In all R.C.C. Items in Rate Analysis Standard Cement Consumption has been taken as per Govt. G.R.: PRC-10/2017 Cement Consumption/16/C Date:11/05/2017 as stated in S.O.R. therefore in R.C.C. items where there is a change as per actual mix design the cost of difference of cement consumption have been deducted from the rate of original item at the rate of input rate mentioned in all the tender.