

**Name of Work : S.R. to New Seva Sadan-1 (PWD) Office, Dist. Bharuch (Repairs to Outer Plaster Work, Colour Work, Plumbing Work, Flooring Work).**

### **BILL OF QUANTITIES**

**Memorandum showing item of works to be carried out.**

It. No.	Item of Work	Qty.	Unit	Rate in Figures	Total Amount
1	2	3	4	5	6
1	Removing and scraping of old deteriorated plaster of any thickness from wall / R.C.C member including stacking of serviceable material and disposal of unserviceable from site of work with all lead and lift.	722.00	Sqm	18.94	13674.68
2	Dismantling tiled of stone floors laid in mortar including stacking of serviceable materials and disposal of unserviceable materials with all lead and lift.	317.00	Sqm	46.77	14826.09
3	20mm thick sand faced cement plaster on walls upto height 10 metre above ground level consisting of 12mm thick backing coat of CM. 1:3 (1-cement : 3-sand) and 8mm thick finishing coat of CM. 1:1 (1 cement: 1-sand) etc. complete extra for scaffolding.	722.00	Sqm	331.79	239552.38
4	Applying two coats of (white cement based) or (acrylic lappy (putty) or equivalent and two coats of primer of approved brand and manufacture on new wall surface to give an even shade including thoroughly brushing the surface free from mortar dropping and other foreign matter and sand papered smooth for All floor.	722.00	Sqm	40.59	29305.98
5	Finishing wall with Weather proof exterior acrylic emulsion paint With one coat of primer on wall surface to give an required shape even shade after thoroughly brushing the surface to remove all dirt, and remains of loose powdered materials etc complete for All floor.	722.00	Sqm	114.53	82690.66
6	P & L 24" x 24" vitrified 8 mm thick tile flooring over 20 mm average) base of cement mortar 1:6 ( 1 cement: 6 coarse sand) on new surface or fixing on existing flooring by adhesive material including dismantling of existing flooring and jointed with color cement slurry including finished with flush pointing & cleaning the surface etc.	10.08	Sqm	916.27	9236.00

It. No.	Item of Work	Qty.	Unit	Rate in Figures	Total Amount
1	2	3	4	5	6
7	Providing and laying BITUMAT SYNROOF HI-BUILD, an elastomeric, premium quality acrylic coating on terrace in two layers total of avg. 1 mm th. waterproofing membrane finished which consist coat of SYNROOF primer and middle layer of 80 GSM geotextile with ultra violet resistance and working up to any height with the 5 ears of guaranty against New Construction and 3 years for Old buildings for any leakage etc. complete as per detail specification and as directed by Engineer In Charge.	292.00	Sqm	333.30	97323.60
			<b>TOTAL Rs.</b>		<b>486609.39</b>

**i.e.Rs. Four lakh eighty six thousand six hundred nine and paise thirty nine only.**

I/We am/are willing to carry out the work @ \_\_\_\_\_ % above/below percent  
(Should be written in figures and words) of the estimated rate mentioned above. Amount of my /our tender works out as under.

Estimated amount put to tender	Estimated amount put to tender
Deduct.....% below	Add.....% Above
Net Rs. _____	Total Rs. _____
In words _____	In words _____

**Note :-**

1. The Contractor shall exhibit a board with detailed specification and details of work as directed by the Engineer-In-Charge for which no extra payment shall be made.
2. The labour cess will be deducted as per prevailing rules i.e. 1% of the work done.
3. GST and Income tax TDS will be deducted at a source while making payments of bills.
4. In all R.C.C. Items in Rate Analysis Standard Cement Consumption has been taken as per Govt. G.R.: PRC-10/2017 Cement Consumption/16/C, Date:11/05/2017 as stated in S.O.R. therefore in R.C.C. items where there is a change as per actual mix design the cost of difference of cement consumption have been deducted from the rate of original item at the rate of input rate mentioned in all the tender.

**Above all items of "Schedule-B" with Item Description, Unit, Rate & Amount have verified by me and found order.**

Deputy Executive Engineer  
City (R & B) Sub Division  
Bharuch

Sr. Divisional Account Officer  
Bharuch (R & B) Division  
Bharuch

Executive Engineer  
Bharuch (R & B) Division,  
Bharuch