

Name of work :- C.R to Lalpur Bypass Road Km 0/0 to 3/8 (Providing MSS Patta in selected stretches)

SPECIFICATION INDEX

Item No. as per Sch. 'B'	Description of Item in brief.	Volume No.	Page No. of General Technical Specification	Specification It. No.	Remarks.
1	2	3	4	5	7
1	Providing and laying 20 mm thick average for patchwork Mix seal surface using stone chips @66% by weight, gradation as per MORTH specification and using bitumin VG 30 grade at rate not less then 50.90KG/MT on BT surface using stone chips as per MORTH specification including heating the asphalt and aggregates by hot mix plant and spreading the same bt paver finisher including consolidation wit vibratory roller and providing, operating plant machineries, equipments, tools, plants, oil, fire wood, kerosene and all labour charges etc. complete. upto all lead.	As per Attached Specification			
2	Providing and laying 50mm thick B.M. With BT Aggregate VG-30 grade bitumen for Tack coat @ 2.50 kg/10 sqm using crushed stone aggregate 0.66 cum/ MT as per MORTH&H Specification & VG-30 grade bitumen for mixing @34.00 Kg/1 MT i.e. 3.4% of by weight of total mix incl. heating and mixing by drum mix plant and spreading the same with paver finisher consolidation with vibratory roller including cost of fuel, hire charges, all necessary equipments, tools and plant, fire wood, oil, kerosene labour changes etc complete.(Using contractor's own Machinery) upto all lead.	As per Attached Specification			

1	2	3	4	5	7
3	Providing & laying 37.5 mm Thick B.U.S.G (Manually) Patch work on road site using Bitumin for tack coat at the rate of 2.5Kg/10sqm. on Existing Road surface & with spreading stone aggregate at the rate of 0.50Cum./10 sqm. with dry rolling and spraying bitumin over it and spraying bitumin over it at the rate of 15 kg/10sqm layer. and then spreading over it stone aggregate at the rate of 0.13cum/10 Sqmt of key aggregate on top in accordance with the requirement of specification incl. cost of stone aggregate bitumin consolidation with vibratory roller necessary firrwood labour charges machineris equipment tools etc. complete.upto all lead.	As per Attached Specification			
4	Providing and laying compacted WBM of grading II B.T.M.C. Metal including spreading watering and consolidation by vibratory roller etc. complete.	As per Attached Specification			

Deputy Executive Engineer
Jamjodhpur. (R&B) Sub-Division
Jamnagar.

Executive Engineer
Jamnagar (R&B) Division
Jamnagar.

