

Name of work :- C.R. to Rajkot Kalawad Road SH-25 K.M. 26/0 to 48/7
(Providing MSS Paver Patta work Bet. K.M. 26/0 to 38/0)

SPECIFICATION INDEX

Item No. as per Sch. 'B'	Description of Item in brief.	Volume No.	Page No. of General Technical Specification	Specification It. No.	Remarks.
1	2	3	4	5	7
1	Providing and laying 20mm thick average for patch work Mix seal surface using stone chips @ 66% by weight, gradation as per MORTH specification and using bitumin VG-30 grade for tack coat 2.50Kg/10Sqm and for mixing rate not less than 50.90Kg/MT on BT surface using stone chips as per MORTH specification including heating the asphalt and aggregate by hot mix plant and spreading the same by paver finisher including consolidation with vibratory roller and providing, operating plant machineries, equipments, tools, plants, oil, fire wood, kerosene and all labour charges etc. complete.	As per Attached Separately			

Deputy Executive Engineer
Jamnagar (R&B) Sub-Division
Jamnagar.

Executive Engineer
Jamnagar (R&B) Division
Jamnagar.

