

**Name of Work :- S.R to New Court Building at Godhra, Dist - Panchmahal
(Water Proofing of Terrace)**

BILL OF QUANTITIES

Memorandum showing item of works to be carried out.

It. No.	Item of Work	Qty.	Unit	Rate in Figures	Total Amount
1	2	3	4	5	6
1	Dismantling tiled of stone floors laid in mortar including stacking of serviceable materilas and disposal of unserviceable materials with all lead and lift.	1272.50	Smt.	46.77	59518.77
2	Providing and laying broken china mosaic flooring for terrace using 12 mm to 20 mm broken pieces of glazed tiles to be laid over cement mortar 1:3 to plain or slope and to be tempered to bring mortar creme out upto surface using white cement including rounding off junctions and extending them upto 15 cm along the wall,clearing with water and oxalic acid etc. over cement concrete flooring 1:2:4 (1-cement : 2-coarse sand : 4-graded stone aggregate 20mm nominal size) laid in one layer (A)Average 40mm thick. (more than 10 ton) etc. complete & Finishing with floating coat of neat cement slurry.	1390.00	Sqmt.	1078.65	1499323.50
			TOTAL Rs.		1558842.27

Rs. Fifteen lakh fifty eight thousand eight hundred forty two and twenty seven Paise Only.

1558842.27

I/We am/are willing to carry out the work @ _____ % above/below percent (Should be written in figures and words) of the estimated rate mentioned above. Amount of my /our tender works out as under.

Estimated amount put to tender	Estimated amount put to tender
Deduct.....% below	Add.....% Above
Net Rs. _____	Total Rs. _____
In words _____	In words _____

Note :-

- The Contractor shall exhibit a board with detailed specification and details of work as directed by the Engineer-In-Charge for which no extra payment shall be made.
- The labour cess will be deducted as per prevailing rules i.e. 1% of the work done.
- GST and Income tax TDS will be deducted at a source while making payments of bills.
- In all R.C.C. Items in Rate Analysis Standard Cement Consumption has been taken as per Govt. G.R.: PRC-10/2017 Cement Consumption/16/C, Date:11/05/2017 as stated in S.O.R. therefore in R.C.C. items where there is a change as per actual mix design the cost of difference of cement consumption have been deducted from the rate of original item at the rate of input rate mentioned in all the tender.
- The Contractor will have to submit the mix design for different grades of cement concrete at his own cost before execution as directed and to be approved from the Engineer in charge.**

Above all items of "Schedule-B" with Item Description, Unit, Rate & Amount have verified by me and found order.

Executive Engineer
Godhra (R & B) Division,
Godhra