

## SCHEDULE - D

PAYMENT SCHEDULE		
BREAK UP FOR INTERIM PAYMENTS FOR UG SUMP		
a.	On approval of designs	2 % of Quoted rate
b.	On completion of excavation and base slab	18 % of Quoted rate
c.	On completion of vertical wall and braces	20 % of Quoted rate
d.	Full supporting structures including column, ring beam and completion of top slab / dome	15 % of Quoted rate
e.	Plastering inside & outside with epoxy etc. complete	10 % of Quoted rate
f.	Procurement and fixing of inlet, outlet, washout, overflow pipes, valves, specials, chambers, lighting arrester conductor and specials at site	15 % of Quoted rate
g.	Water level indicator, painting of letters, M.S ladder pipes, railing and all miscellaneous items such as exterior proof emulsion paint in three coats etc (Completed with all respect including water tightness test)	10 % of Quoted rate
H.	On hydraulic testing	10 % of Quoted rate

Executive Engineer  
P. H. Works Division,  
Junagadh

Deputy Executive Engineer  
P. H. S. Sub Division,  
Manavadar