

M & R to Padra Regional Water Supply Scheme					
Taluka - Padra			Districit - Vadodara		
Estimate for Demolition of Existing 04 Nos of RCC ESR @ Different SHW under old padra RWSS Along with 03 Nos of Pump rooms and 02 Nos of Staff quarters at Different SHW under padra RWSS.					
S C H E D U L E - B					
Quantity	Unit	Particulars	Rate	Per	Amount
1	2	3	4	5	6
		Item No.1 :-			
		Demolition and dismantling of the existing RCC Elevated Storage Reservoir (ESR), located at Different SHW of old Padra RWSS. The scope includes the complete dismantling of the RCC structure, including walls, slabs, beams, columns, foundation and other related components. All serviceable materials such as steel reinforcement bars, stairs, C.I. pipes, C.I. specials (tees, bends, sluice valves), G.I. pipe railings, and C.I. manhole frames and covers must be taken away by the contractor at no extra cost for the conveyance of the demolished scrap (inclu. crushed concrete). The demolition has to be done mechanically (with machineries) & in the order from top towards bottom of the ESR safely, using machineries such as Concrete Crushers, etc. After demolition, the contractor must ensure that the site is cleaned, all debris removed and the gound is levelled, leaving the site in a clean and safe condition as per the Engineer-in-charge's instructions. The rates for this work shall include the cost of all serviceable materials and scrap value of reusable items. The contractor must comply with all relevant permits, safety measures, and local regulations. The entire work, from demolition to site cleanup, must be completed with due diligence, ensuring no debris is left and the site is left in an acceptable condition, as specified by the Engineer-in-charge.			
1.00	Job	RCC ESR (2.70 LL * 17 Mtr Ht) at Abhor Sub Head Work	-295802.59	Job	-295802.59
1.00	Job	RCC ESR (1.00 LL * 7 Mtr Ht) at Kotna Sub Head Work	-38347.57	Job	-38347.57
1.00	Job	RCC ESR (10.00 LL * 15 Mtr Ht) at Muval Sub Head Work	-539028.99	Job	-539028.99
1.00	Job	RCC ESR (1.5 LL * 10 Mtr Ht) at Sarsavni Sub Head Work	-46243.67	Job	-46243.67
		Item No.2 :-			
		Demolition and dismantling of the existing Staff quarters and Pump house, located at Different SHW of old Padra RWSS. The scope includes the complete dismantling of the RCC structure, including walls, slabs, beams, columns, and other related components. All serviceable materials such as steel reinforcement bars, stairs, C.I. pipes, C.I. specials (tees, bends, sluice valves), G.I. pipe railings, and C.I. manhole frames and covers must be taken away by the contractor at no extra cost for the conveyance of the demolished scrap (inclu. crushed concrete). The demolition has to be done mechanically (with machineries) & in the order from top towards bottom of the structure safely, using machineries such as Concrete Crushers, etc. After demolition, the contractor must ensure that the site is cleaned, all debris removed and the gound is levelled, leaving the site in a clean and safe condition as per the Engineer-in-charge's instructions. The rates for this work shall include the cost of all serviceable materials and scrap value of reusable items. The contractor must comply with all relevant permits, safety measures, and local regulations. The entire work, from demolition to site cleanup, must be completed with due diligence, ensuring no debris is left and the site is left in an acceptable condition, as			
1.00	Job	02 Nos of Staff quarters at Chapad SHW, 02 Nos of Pump House at Sarsavni SHW and a Pump House at Kotna SHW Under PADRA RWSS	85038.80	Job	85038.80
			Total	Rs.	-834384.02

Note:

The bidder shall be required to pay GST directly to the GST department as per applicable government norms.

In negative amount tenders, the bidder quoting the highest final payable amount to the department shall be considered as L1.

Here:

Negative amount (–) indicates payment to the department by the bidder.

GST is calculated on the absolute value of the final quoted amount.

This example is for clarification only and actual payable amount will depend on the actual tendered value and bidder's quoted rate.

Special Condition:

All bidders shall compulsorily submit a "Bahendari" (Affidavit) on ₹300 non-judicial stamp paper as per the prescribed format attached with the tender.

Failure to submit this affidavit along with the bid shall result in the bid being excluded from the evaluation process.

Note: Approximate quantities and amount for the work shown in the Schedule - B.

I /We am/are willing to carry out the work at _____% above/below _____
percent (should be written in figures and words) above / below the tendered. The rate
mentioned above, amount of my/our tender work as under.

*Estimated amount put

*Estimated amount put

to tender Rs.[-834384.02]_____ **to tender Rs.[-834384.02]**_____

Deduct _____ % below

Add _____ % above

Rs._____ Rs._____

Net Rs._____ Total Rs._____

In words: _____ In words: _____

(Please strike out which is not applicable)

Special Information

Say Tender Amount	Quoted Percentage	Amount to be deposited to Department
-100.00	(Above)+10%	-90
-100.00	(Below)-10%	-110

Signature of Contractor

Deputy Executive Engineer
Public Health Sani. Sub Division
Gujarat. W. S. & S. Board
Karjan