

## Kaalol Nagar Palika, Kaalol

Name of Work: :Bid Documents for Providing Supplying and Laying Precast U Drain with Cover at Various Location for Kaalol nagarpalika. Under SJMSVY 2025-26 3rd Attempt

### SCHEDULE - "B4"

**Name of Work : Providing Supplying and Laying Precast U Drain with Cover at Teen Batti Char Rasta thi Kalal Zampa Part 2 Sudhi for Kaalol nagarpalika.**

Item No.	Item	Total Qty.	Rate	Per	Amount
1	Excavation for foundation upto 1.5 m depth including sorting out and stacking of useful materials and disposing off the excavated stuff upto 50 Meter lead.(A) Loose or soft soil				
		257.00	117.08	Cum	30089.56
2	Providing and laying rubble for apron (each stone weighting not less than 40Kg.) including and packing and filing in the interestices with quarry-spalls.				
		62.00	1010.60	Cum	62657.20
3	Providing and laying cement concrete 1:3:6 (1- Cement : 3- coarse sand : 6- hand broken stone aggregates 40 mmnominal size) and curing complete excluding cost of formwork in (A) Foundation and Plinth				
		46.50	2980.90	Cum	138611.85
4	Providing Supplying and Fixing Precast RCC U Drain with Cover 300 x 300 mm Section M 250 Approximate 415 kg Including necessary all work required and as directed by Engineer In Charge.				
		430.00	3658.73	Cum	1573253.90
5	Providing Supplying and Fixing Precast Chamber 300 x 300 mm Section M 250 Approximate 415 kg Including necessary all work required and as directed by Engineer In Charge.				
		18.00	1320.58	Rmt	23770.44
6	Filling available excavated earth (excluding rock) in trenches. plinth, sides of foundations etc. in layers not exceeding 20 cm. in depth consolidating each disposed layer by ramming and watering.				
		61.90	130.39	Cumt	8071.14
				<b>Total</b>	<b>1836454.09</b>
				<b>Add 18% GST Charge</b>	<b>330561.74</b>
				<b>Add 2% Contingency</b>	<b>36729.08</b>
				<b>Add 1% QC Charge</b>	<b>18364.54</b>
				<b>Total</b>	<b>2222109.45</b>
				<b>Say</b>	<b>2222110.00</b>