

**Name of work : C.R./F.D.I.R. to various roads under Ankleshwar (R&B) Sub Division  
(Hansot Section) (Supplying of Road Materials including spreading and rolling) Tal.  
Hansot, Dist. Bharuch.**

### **BILL OF QUANTITIES**

**Memorandum showing item of works to be carried out.**

It. No.	Item of Work	Qty.	Unit	Rate in Figures	Total Amount
1	2	3	4	5	6
1	Supplying, Spreading and Consolidate with 8 - 10 tonne capacity roller to Machine Crushed metal of 40 mm to 63 mm in size on road side including filling measure boxes etc. complete.	397.00	Cum	1275.63	506425.11
2	Supplying, Spreading and Consolidate with 8 - 10 tonne capacity roller to Machine Crushed metal of 25 mm to 40 mm in size on road side including filling measure boxes etc. complete.	318.00	Cum	1241.29	394730.22
3	Supplying, Spreading and Consolidate with 8 - 10 tonne capacity roller to Stone Dust of approved quality on road side including filling measure boxes etc. complete.	350.00	Cum	1024.14	358449.00
			<b>TOTAL Rs.</b>		<b>1259604.33</b>

**i.e. Rs. Twelve lakh fifty nine thousand six hundred four and paise thirty three only.**

I/We am/are willing to carry out the work @ \_\_\_\_\_ % above/below percent  
(Should be written in figures and words) of the estimated rate mentioned above. Amount of  
my /our tender works out as under.

Estimated amount put to tender	Estimated amount put to tender
Deduct.....% below	Add.....% Above
Net Rs. _____	Total Rs. _____
In words _____	In words _____

**Note :-**

- The Contractor shall exhibit a board with detailed specification and details of work as directed by the Engineer-In-Charge for which no extra payment shall be made.
- The labour cess will be deducted as per prevailing rules i.e. 1% of the work done.
- GST and Income tax TDS will be deducted at a source while making payments of bills.
- In all R.C.C. Items in Rate Analysis Standard Cement Consumption has been taken as per Govt. G.R.: PRC-10/2017 Cement Consumption/16/C, Date:11/05/2017 as stated in S.O.R. therefore in R.C.C. items where there is a change as per actual mix design the cost of difference of cement consumption have been deducted from the rate of original item at the rate of input rate mentioned in all the tender.
- 1% testing charges should be paid by the contractor.

**Above all items of "Schedule-B" with Item Description, Unit, Rate & Amount have verified by me  
and found order.**

Deputy Executive Engineer  
Ank (R & B) Sub Division  
Ankleshwar

Sr. Divisional Account Officer  
Bharuch (R & B) Division  
Bharuch

Executive Engineer Bharuch  
(R & B) Division,  
Bharuch