

Name of Work :Demolition of Existing RCC ESR from Various area at Viramgam Nagarpalika, Viramgam .					
SCHEDULE - B					
Memorandum showing items works to be carried out :					
હાથ ધરવાના કામની બાબતો દર્શાવતી યાદી					
Item No. બાબત	QuantitiesE stimated Qty.	Item Of Work કામ ની બાબત	Tendered Rate In Figure Rs. Ps	Unit	Total Amount according to estimated
1	2	3	4	6	7
1		Demolition and dismantling of the existing RCC Elevated Storage Reservoir (ESR). The scope includes the complete dismantling of the RCC structure, including walls, slabs, beams, columns, foundation and other related components. All serviceable materials such as steel reinforcement bars, stairs, C.I. pipes, C.I. specials (tees, bends, sluice valves), G.I. pipe railings, and C.I. manhole frames and covers must be taken away by the contractor at no extra cost for the conveyance of the demolished scrap (inclu. crushed concrete). The demolition has to be done mechanically (with machineries) & in the order from top towards bottom of the ESR safely, using machineries such as Jaw Crushers, Concrete Crushers, etc. After demolition, the contractor must ensure that the site is cleaned, all debris removed and the ground is levelled, leaving the site in a clean and safe condition as per the Engineer-in-charge's instructions. The rates for this work shall include the cost of all serviceable materials and scrap value of reusable items. The contractor must comply with all relevant permits, safety measures, and local regulations. The entire work, from demolition to site cleanup, must be completed with due diligence, ensuring no debris is left and the site is left in an acceptable condition, as specified by the Engineer-in-charge.			
1A	1.00	Gandhi Hospital Water Works 6.00 Lakh Liter capacity & 18 Meter Height.	0.00	Job	0.00
1B	1.00	Adamiya Tekari Water Works 1.00 Lakh Liter Capacity & 12 Meter Height.	0.00	Job	0.00
1C	1.00	Dispensary Water Works 3.00 Lakh Liter Capacity & 18 Meter Height.	0.00	Job	0.00

ID	1.00	IOC (482) Water Works 6.00 Lakh Liter Capacity & 18 Meter Height .	0.00	Job	0.00
TOTAL AMOUNT					0.00
SAY AMOUNT					0.00

Estimated amount

Put to tender Rs ...

Deduct% below Rs.....

Total Rs.....

In words

(*Please strike out whichever is not applicable).

Note : 1 All work shall be carried out as per Public Works Department Handbook and other specifications of Division or as directed.

નોંધ-૧ બધું જ કામ બાંધકામ વિભાગની પુસ્તિકા અને ડિવીઝનની બીજી ખાસ વિગત મુજબ અથવા સૂચના પ્રમાણે કરી આપવાનું રહેશે.

Note : 2 All the columns is Schedule should be filled in ink and the total of the entries in the last column should be struck by the contractor under this signature.

નોંધ : ૨ અનુસૂચિમાં બધા ખાનાની વિગતો સહીથી ભરવી અને છેલ્લા ખાનાની નોંધોનો સરવાળો કરી કોન્ટ્રાક્ટરે પોતાની સહી કરવી.

Note : 3 Rates quoted include clearance of site (prior commencement of work and at its close) in all respects and hold good for work under all conditions, site, moisture, weather etc.

નોંધ-૩ : ટાંકેલા દરમાં, સ્થળની (કામના આરંભે અને પૂરૂ થાય તે વખતે)દરેક રીતે સાફસૂફી કરવાનો સમાવેશ થાય છે, અને તે દર તમામ પરિસ્થિતિ, સ્થળ, ભેજ, હવામાન વગેરે હેઠળ કામ અમલમાં રહેશે.

Note : 4 To be continued on additional sheets, if found necessary.

નોંધ-૪ : જરૂર જણાય વધારાના કાગળો જોડી ચાલું રાખવું.

Estimated amount

Put to tender Rs...

Add.....% above Rs.....

Total Rs.....

In words

Chief Officer
Viramgam Nagarpalika
Viramgam