

SCHEDULE-A

Name of Work : Annual Rate Contract for Temporary Electrical installations ,Decorative Roshni,DG Set and A.C, Machines for Ahmedabad electrical Division No-1, Ahmedabad (Year 2026-27)						
Sr. No.	Item No.	Item	Qty.	Unit	Amount	Place
1	1	NIL	NIL	NIL	NIL	NIL
t	t					
o	o					
1	1	NIL	NIL	NIL	NIL	NIL
3	3					
3	3					

Contractor's signature

Deputy Executive Engineer
Ahmedabad Electrical Sub-Division
R&B Deptt., Ahmedabad.

SCHEDULE - B							
Name of Work : Annual Rate Contract for Temporary Electrical installations ,Decorative Roshni,DG Set and A.C, Machines for Ahmedabad electrical Division No-1, Ahmedabad (Year 2026-27)							
ITEM NO.	QTY	UNIT	ITEM NAME	PER	RATE IN FIGURE	RATE IN WORDS	AMOUNT
1			Hire charges for providing erecting temp LED light 10 mm bulbs approved high glow with complete wiring with auto changer reverse and after good use dismantling.				
	1	1st Day /RMT	(A) Strip Light. (Minimum 38 Lamps / Mtr.)	1st Day /RMT	22.22	Rupees Twenty Two And Paise Twenty Two Only	22.22
2	1	1st Day /RMT	(B) Series Light. (Minimum 5 Lamps / Mtr.)	1st Day /RMT	4.04	Rupees Four And Paise Four Only	4.04
3	1	1st Day /RMT	(C) Rope Light. (Minimum 15 Lamps. / Mtr.)	1st Day /RMT	7.07	Rupees Seven And Paise Seven Only	7.07
4	1	1st Day /lamp	(D) Decorative LED design light on board	1st Day /lamp	1.01	Rupees One And Paise One Only	1.01
5	1	1st Day /piece	(E) Decorative LED palm piece	1st Day /piece	256.54	Rupees Two Hundred Fifty Six And Paise Fifty Four Only	256.54
6	1	1st Day / No	Hire charges for providing erecting and dismantling temporary illumination, consisting of strip lights complete with holders, bulbs up to 40Watt lamp of different colours complete with necessary lead wires erected and dismantled.	1st Day / No	4.04	Rupees Four And Paise Four Only	4.04
7	1	1st Day / No	Hire charges for providing erecting and dismantling temporary illumination consisting of the LED tube lights 22 watt minimum complete withlead wires	1st Day / No	20.20	Rupees Twenty And Paise Twenty Only	20.20
8	1	1st Day	For use of decorative tube in place of simple tube	1st Day	14.14	Rupees Fourteen And Paise Fourteen Only	14.14
9	1	1st Day /Nos	Hire charges for providing erecting and dismantling temporary illumination consisting of flood light fitting up to 100 Watt complete with holders lead wires, incandescent lamp with different colours with indoor / outdoor type	1st Day /Nos	18.18	Rupees Eighteen And Paise Eighteen Only	18.18
10	1	1st Day /Nos	Hire charges for providing erecting and dismantling temporary illumination consisting of halogen fitting 500 Watt / 85 watt retrofit CFL lamp/60watt LED lamp with suitable size Al. reflector complete with holders tube and lead wires. (outdoor Type)	1st Day /Nos	61.61	Rupees Sixty One And Paise Sixty One Only	61.61
11	1	1st Day /Nos	Hire charges for providing erecting and dismantling temporary illumination consisting of halogen fitting 1000 Watt complete with holders tube and lead wires. (Outdoor Type)	1st Day /Nos	82.82	Rupees Eighty Two And Paise Eighty Two Only	82.82

12			Hire Charges for heavy duty flood light luminaire comprises die cast aluminium body with heat resistant toughened front glass, silicon rubber gasket, electromechanically brightened anodised aluminium reflector, hot deep galvanized M.S. cradle clamp with suitable size of necessary control gear box having choke, capacitor, holder, lamp etc. complete.				
	1	1 St.Day./ no	(A) Suitable for One No. 70 watt HPSV / Metal helide lamp	1 St.Day./ no	198.97	Rupees One Hundred Ninety Eight And Paise Ninety Seven Only	198.97
13	1	1 St.Day./ no	(B) Suitable for One No. 150 watt HPSV / Metal helide lamp	1 St.Day./ no	277.75	Rupees Two Hundred Seventy Seven And Paise Seventy Five Only	277.75
14	1	1 St.Day./ no	(C) Suitable for One No. 250 watt HPSV / Metal helide lamp	1 St.Day./ no	309.06	Rupees Three Hundred Nine And Paise Six Only	309.06
15	1	1 St.Day./ no	(D) Suitable for One No. 400 watt HPSV / Metal helide lamp	1 St.Day./ no	496.92	Rupees Four Hundred Ninety Six And Paise Ninety Two Only	496.92
16			Hire charges for providing erecting and dismantling after use of good running condition for the HPSV street light fitting with necessary accessories and lamps with fixing arrangement as per direction of engineer incharge				
	1	1 St.Day./ no	(A) suitable for 70 watt	1 St.Day./ no	119.18	Rupees One Hundred Nineteen And Paise Eighteen Only	119.18
17	1	1 St.Day./ no	(B) suitable for 150 watt	1 St.Day./ no	141.40	Rupees One Hundred Forty One And Paise Forty Only	141.40
18	1	1 St.Day./ no	(C) suitable for 250 watt	1 St.Day./ no	179.78	Rupees One Hundred Seventy Nine And Paise Seventy Eight Only	179.78
19	1	1 St.Day./ no	(D) suitable for 400 watt	1 St.Day./ no	276.74	Rupees Two Hundred Seventy Six And Paise Seventy Four Only	276.74
20	1	1 St.Day./ no	Hire charges for Providing and fixing chaser to give running erected to strip light and min up to load of 5 KW	1 St.Day./ no	181.80	Rupees One Hundred Eighty One And Paise Eighty Only	181.80

			Hire charges for providing, erecting and dismantling after use in good running condition for temp. arrangement of city colour HMI light with necessary KW capacity Lamps with its control panel and wiring and operating complete.				
21	1	1 St.Day./ no	(A) 2 / 2.50 Kw.	1 St.Day./ no	10734.28	Rupees Ten Thousand Seven Hundred Thirty Four And Paise Twenty Eight Only	10734.28
22	1	1 St.Day./ no	(B) 4.0 Kw.	1 St.Day./ no	17513.40	Rupees Seventeen Thousand Five Hundred Thirteen And Paise Forty Only	17513.40
23	1	1 St.Day./ no	Hire charges for providing, erecting as per direction of Engineer in charge and dismantling after use in good running condition with providing temp illumination by CYBER / SCANNER lights of 1200 watt rotating mechanism controlled by microprocessor base pre programmed controllers with suitable data control. and power cables and connections.	1 St.Day./ no	8473.90	Rupees Eight Thousand Four Hundred Seventy Three And Paise Ninety Only	8473.90
24	1	1 St.Day./ no	Hire charges for providing, erecting & dismantling Sharpy Moving Head light 200-440 w 20R(Beam,Spot,Wash)3-in-1 hybrid with necessary wiring & controller as required and as per instruction of engineer-incharge	1 St.Day./ no	7704.28	Rupees Seven Thousand Seven Hundred Four And Paise Twenty Eight Only	7704.28
25			Hire charges for providing & dismantling temp. three light consisting Neon / LED Light with electronically controlled effects(Par light) complete erected with necessary supports with connection & necessary controller .				
	1	1st. Day Per No.	(A) 50 to 150 Watt	1st. Day Per No.	1027.17	Rupees One Thousand Twenty Seven And Paise Seventeen Only	1027.17
26	1	1st. Day Per No.	(B) above 150 Watt	1st. Day Per No.	1541.26	Rupees One Thousand Five Hundred Forty One And Paise Twenty Six Only	1541.26
27			Hire charges for providing erecting and dismantling after use of good running condition 1200 mm / 1400 mm size ceiling fan with down rod and clamp complete				
	1	1st Day /Nos	(A) For Erection In Bamboo / Metal Type Mandap	1st Day /Nos	103.02	Rupees One Hundred Three And Paise Two Only	103.02

28	1	1st Day /Nos	(B) For Erection In Structure Dome	1st Day /Nos	206.04	Rupees Two Hundred Six And Paise Four Only	206.04
29	1	1st Day /Nos	Hire charges for providing electing and dismantling after use of good running condition of 1200mm /1400 mm size ceiling fan with down rod of 8ft to 20ft height with necessary wiring for germon Structure dome complete with check nuts, fan down road clamp with covered PVC insulation .	1st Day /Nos	496.92	Rupees Four Hundred Ninety Six And Paise Ninety Two Only	496.92
30	1	1st Day /Nos	Higher charges for providing erecting and Removing after use of good running condition 300 mm/ 400 mm size low noise oscillation type pedestal fan of good condition.	1st Day /Nos	295.93	Rupees Two Hundred Ninety Five And Paise Ninety Three Only	295.93
31	1	1st Day /Nos	Hire charges for providing, & erecting and dismantling after use of good running condition 600mm/900mm heavy duty air-circulator pedestal type fan of good running condition.	1st Day /Nos	256.54	Rupees Two Hundred Fifty Six And Paise Fifty Four Only	256.54
32	1	1st Day /Nos	Hire charges for providing erecting and dismantling after use of good running condition Desert Cooler complete with necessary water filling arrangements with stand & 3 core wire with top etc..	1st Day /Nos	514.09	Rupees Five Hundred Fourteen And Paise Nine Only	514.09
33	1	1st Day /Nos	Hire charges for providing for temporary plug point with 5/15Amp plug switch combined, erected in wooden board complete	1st Day /Nos	26.26	Rupees Twenty Six And Paise Twenty Six Only	26.26
34			Hire charges for providing erecting and dismantling after use in good running condition with necessary interconnecting wire/cable on panel board.				
	1	1st Day /Nos	(A) D.P. Switch 16A/32A, 230V	1st Day /Nos	32.32	Rupees Thirty Two And Paise Thirty Two Only	32.32
35	1	1st Day /Nos	(B) T.P. Switch with neutral 16A/32A 440V	1st Day /Nos	41.41	Rupees Forty One And Paise Forty One Only	41.41
36	1	1st Day /Nos	(C) T.P. Switch with neutral 63A/200A 440V	1st Day /Nos	82.82	Rupees Eighty Two And Paise Eighty Two Only	82.82
37	1	1st Day /Nos	(D) TPN Switch 200A/250A, 400V	1st Day /Nos	256.54	Rupees Two Hundred Fifty Six And Paise Fifty Four Only	256.54
38	1	1st Day /Nos	(E) BUSBAR (i) 63 Amp to 100 Amp. Up to 1 Mtr.	1st Day /Nos	123.22	Rupees One Hundred Twenty Three And Paise Twenty Two Only	123.22
39	1	1st Day /Nos	(F) BUSBAR (i) 63 Amp to 100 Amp. Above 1 Mtr.	1st Day /Nos	155.54	Rupees One Hundred Fifty Five And Paise Fifty Four Only	155.54

40	1	1st Day /Nos	(G) BUSBAR (ii) 200 Amp. Up to 1 Mtr.	1st Day /Nos	214.12	Rupees Two Hundred Fourteen And Paise Twelve Only	214.12
41	1	1st Day /Nos	(H) BUSBAR (ii) 200 Amp. Above 1 Mtr.	1st Day /Nos	252.50	Rupees Two Hundred Fifty Two And Paise Fifty Only	252.50
42	1	1st Day /Nos	(I) Change Over Switches 4 Pole 440 V (i) 16 A - 32 A	1st Day /Nos	61.61	Rupees Sixty One And Paise Sixty One Only	61.61
43	1	1st Day /Nos	(J) Change Over Switches 4 Pole 440 V (ii) 63 A	1st Day /Nos	175.74	Rupees One Hundred Seventy Five And Paise Seventy Four Only	175.74
44	1	1st Day /Nos	(K) Change Over Switches 4 Pole 440 V (iii) 100A - 125A	1st Day /Nos	288.86	Rupees Two Hundred Eighty Eight And Paise Eighty Six Only	288.86
45	1	1st Day /Nos	(L) Change Over Switches 4 Pole 440 V (iv) 200A - 300A	1st Day /Nos	462.58	Rupees Four Hundred Sixty Two And Paise Fifty Eight Only	462.58
46	1	1st Day /Nos	(M) Change Over Switches 4 Pole 440 V (v) 400 A	1st Day /Nos	812.04	Rupees Eight Hundred Twelve And Paise Four Only	812.04
47	1	1st Day /Nos	(N) Change Over Switches 4 Pole 440 V (vi) 630A	1st Day /Nos	1264.52	Rupees One Thousand Two Hundred Sixty Four And Paise Fifty Two Only	1264.52
48	1	1st Day /Nos	(O) Change Over Switches 4 Pole 440 V (vii) 800A	1st Day /Nos	1582.67	Rupees One Thousand Five Hundred Eighty Two And Paise Sixty Seven Only	1582.67
49	1	1st Day /Nos	(P) Distribution Boards 3 phase 440V 6A/32A (i) 4 - 6 Way	1st Day /Nos	92.92	Rupees Ninety Two And Paise Ninety Two Only	92.92
50	1	1st Day /Nos	(Q) Distribution Boards 3 phase 440V 6A/32A (ii) 8-12 Way	1st Day /Nos	164.63	Rupees One Hundred Sixty Four And Paise Sixty Three Only	164.63
51	1	1st Day /Nos	(R) MCB Distribution boards Three phase 230V, (i) 4 - 6 - 8 Way	1st Day /Nos	297.95	Rupees Two Hundred Ninety Seven And Paise Ninety Five Only	297.95

52	1	1st Day /Nos	Hire charges for providing erecting and dismantling after use in good running condition. Section pillar fabricated from 16 SWG thick M.S. Sheet with 40 x 40 x 6 mm thick angle iron legs with 12 mm thick bakelite / wooden sheet erected complete with following sizes (b) Section pillar having size 75 x 60 x 45	1st Day /Nos	309.06	Rupees Three Hundred Nine And Paise Six Only	309.06
53	1	1st Day /Nos	Hire charges for providing erecting and dismantling after use in good running condition. Section pillar fabricated from 16 SWG thick M.S. Sheet with 40 x 40 x 6 mm thick angle iron legs with 12 mm thick bakelite / wooden sheet erected complete with following sizes (c) Section pillar having size 60 x 30 x 45	1st Day /Nos	175.74	Rupees One Hundred Seventy Five And Paise Seventy Four Only	175.74
54	1	1st day	Hire charges for providing & dismantling pipe type earthing for temporary electrical installation having G.I. pipe, erected in earth pit with necessary salt & charcoal & necessary earth wire.	1st day	119.18	Rupees One Hundred Nineteen And Paise Eighteen Only	119.18
55			Hire charges for providing, erecting & dismantling after use of good running condition for PVC copper /Aluminium wire mains with suitable copper PVC 1.5 / 2.5 Sq.mm earth wire of following size				
	1	1st. Day /RMT.	(A) 2 wire 1 /1.5 / 2.5 Sq.mm Copper	1st. Day /RMT.	4.04	Rupees Four And Paise Four Only	4.04
56	1	1st. Day /RMT.	(B) 2 wire 1 /1.5 / 2.5 Sq.mm Aluminium	1st. Day /RMT.	1.01	Rupees One And Paise One Only	1.01
57	1	1st. Day /RMT.	(C) 2 wire 4 /6 Sq.mm Copper	1st. Day /RMT.	5.05	Rupees Five And Paise Five Only	5.05
58	1	1st. Day /RMT.	(D) 2 wire 4 /6 Sq.mm Aluminium	1st. Day /RMT.	1.01	Rupees One And Paise One Only	1.01
59	1	1st. Day /RMT.	(E) 4 wire 4 Sq.mm Copper	1st. Day /RMT.	8.08	Rupees Eight And Paise Eight Only	8.08
60	1	1st. Day /RMT.	(F) 4 wire 4 Sq.mm Aluminium	1st. Day /RMT.	2.02	Rupees Two And Paise Two Only	2.02
61	1	1st. Day /RMT.	(G) 4 wire 6 Sq.mm Copper	1st. Day /RMT.	12.12	Rupees Twelve And Paise Twelve Only	12.12
62	1	1st. Day /RMT.	(H) 4 wire 6 Sq.mm Aluminium	1st. Day /RMT.	4.04	Rupees Four And Paise Four Only	4.04
63	1	1st. Day /RMT.	(I) 4 wire 10 Sq.mm Copper	1st. Day /RMT.	13.13	Rupees Thirteen And Paise Thirteen Only	13.13
64	1	1st. Day /RMT.	(J) 4 wire 10 Sq.mm Aluminium	1st. Day /RMT.	5.05	Rupees Five And Paise Five Only	5.05
65			Hire charges for providing erecting as per direction of Engineer in charge dismantling after use of good running condition for temporary power supply the XLPE insulated armoured cable Aluminium conductor of following size.				
	1	1st. Day /RMT.	(A) 2 Core 10 Sq.mm	1st. Day /RMT.	13.13	Rupees Thirteen And Paise Thirteen Only	13.13

66	1	1st. Day /RMT.	(B) 4 Core 4 / 6 / 10 Sq.mm	1st. Day /RMT.	17.17	Rupees Seventeen And Paise Seventeen Only	17.17
67	1	1st. Day /RMT.	(C) 4 Core 16 / 25 Sq.mm	1st. Day /RMT.	19.19	Rupees Nineteen And Paise Nineteen Only	19.19
68	1	1st. Day /RMT.	(D) 3 1/2 Core 35 Sq.mm	1st. Day /RMT.	23.23	Rupees Twenty Three And Paise Twenty Three Only	23.23
69	1	1st. Day /RMT.	(E) 3 1/2 Core 50 / 70 Sq.mm	1st. Day /RMT.	31.31	Rupees Thirty One And Paise Thirty One Only	31.31
70	1	1st. Day /RMT.	(F) 3 1/2 Core 95 / 120 Sq.mm	1st. Day /RMT.	47.47	Rupees Forty Seven And Paise Forty Seven Only	47.47
71	1	1st. Day /RMT.	(G) 3 1/2 Core 150 / 185 Sq.mm	1st. Day /RMT.	62.62	Rupees Sixty Two And Paise Sixty Two Only	62.62
72			Hire charges for providing, erecting as per direction of Engineer-in-charge, dismantling after use of good running condition for temporary power supply, the XLPE insulated armoured. cable multistrand Copper conductor of following size				
	1	1st Day /Mtr.	(A) 3 1/2 Core 35 Sq.mm	1st Day /Mtr.	52.52	Rupees Fifty Two And Paise Fifty Two Only	52.52
73	1	1st Day /Mtr.	(B) 3 1/2 Core 50 Sq.mm	1st Day /Mtr.	77.77	Rupees Seventy Seven And Paise Seventy Seven Only	77.77
74	1	1st Day /Mtr.	(C) 4 Core 16 Sq.mm	1st Day /Mtr.	96.96	Rupees Ninety Six And Paise Ninety Six Only	96.96
75	1	1st Day /Mtr.	(D) 4 Core 25 Sq.mm	1st Day /Mtr.	46.46	Rupees Forty Six And Paise Forty Six Only	46.46
76			Hire charges for providing, erecting with necessary connection and dismantling after user of good running ELCBs/RCCBs conforming to IS 12640 and having sensitivity of 30 Ma and Short circuit withstand capacity of 6 KA and suitable for operation on single phase 240 V having characteristic of quick action & tripping with all advance feature & do not incorporate any electronic component for following Max rating				
	1	1st Day /Nos.	(A) 40 Amps D.P [Cat.II]	1st Day /Nos.	144.43	Rupees One Hundred Forty Four And Paise Forty Three Only	144.43
77	1	1st Day /Nos.	(B) 63 Amps D.P [Cat.II]	1st Day /Nos.	180.79	Rupees One Hundred Eighty And Paise Seventy Nine Only	180.79

78			Hire charges for providing, erecting with necessary connection and dismantling after user of good running ELCBs/RCCBs conforming to IS 12640 and having sensitivity of 30 ma and short circuit withstand capacity of 6 KA and Suitable for operation on 3 Phase and neutral 415V having characteristic of quick action & tripping with all advance feature & do not incorporate any electronic component for following Max rating				
	1	1st Day /Nos.	(A) 40 Amps FP [Cat.II]	1st Day /Nos.	164.63	Rupees One Hundred Sixty Four And Paise Sixty Three Only	164.63
79	1	1st Day /Nos.	(B) 63 Amps FP [Cat.II]	1st Day /Nos.	195.94	Rupees One Hundred Ninety Five And Paise Ninety Four Only	195.94
80	1	1st Day /Nos.	(C) 100 Amps FP (100m A Sensitivity) [Cat.II]	1st Day /Nos.	252.50	Rupees Two Hundred Fifty Two And Paise Fifty Only	252.50
81			Hire charges for providing, erecting with necessary connection and dismantling after user of good running Approved make Four Pole LT Heavy Duty Switch Disconnector Fuse Unit Cubical type for panel mounting complete with operating mechanism suitable to operate on 415 V AC 23A duty with HRC fuses of suitable load confirming to I.S 13947 (Part I & III) of following capacities.				
	1	1st Day /Nos.	(A) 32 Amp [Cat.II]	1st Day /Nos.	128.27	Rupees One Hundred Twenty Eight And Paise Twenty Seven Only	128.27
82	1	1st Day /Nos.	(B) 63 Amp [Cat.II]	1st Day /Nos.	164.63	Rupees One Hundred Sixty Four And Paise Sixty Three Only	164.63
83	1	1st Day /Nos.	(C) 125 Amp [Cat.II]	1st Day /Nos.	256.54	Rupees Two Hundred Fifty Six And Paise Fifty Four Only	256.54
84	1	1st Day /Nos.	(D) 200 Amp [Cat.II]	1st Day /Nos.	359.56	Rupees Three Hundred Fifty Nine And Paise Fifty Six Only	359.56
85	1	1st Day /Nos.	(E) 250 Amp [Cat.II]	1st Day /Nos.	462.58	Rupees Four Hundred Sixty Two And Paise Fifty Eight Only	462.58
86	1	1st Day /Nos.	(F) 315 / 320 Amp [Cat.II]	1st Day /Nos.	514.09	Rupees Five Hundred Fourteen And Paise Nine Only	514.09

87	1	1st Day /Nos.	(G) 400 Amp [Cat.II]	1st Day /Nos.	667.61	Rupees Six Hundred Sixty Seven And Paise Sixty One Only	667.61
88	1	1st Day /Nos.	(H) 630 Amp [Cat.II]	1st Day /Nos.	1018.08	Rupees One Thousand Eighteen And Paise Eight Only	1018.08
89	1	1st Day /Nos.	(I) 800 Amp [Cat.II]	1st Day /Nos.	1181.70	Rupees One Thousand One Hundred Eighty One And Paise Seventy Only	1181.70
90			Hire charges for providing, erecting with necessary connection and dismantling after user of good running Supplying & erecting approved make Four Pole 415V change over switch interior for panel mounting with operating mechanism A.C. 23 duty confirming to I. S.S. for				
	1	1st Day /Nos.	(A) 32 - 40 A [Cat.II]	1st Day /Nos.	134.33	Rupees One Hundred Thirty Four And Paise Thirty Three Only	134.33
91	1	1st Day /Nos.	(B) 63 A [Cat.II]	1st Day /Nos.	185.84	Rupees One Hundred Eighty Five And Paise Eighty Four Only	185.84
92	1	1st Day /Nos.	(C) 100 - 125 A [Cat.II]	1st Day /Nos.	309.06	Rupees Three Hundred Nine And Paise Six Only	309.06
93	1	1st Day /Nos.	(D) 200 A [Cat.II]	1st Day /Nos.	411.07	Rupees Four Hundred Eleven And Paise Seven Only	411.07
94	1	1st Day /Nos.	(E) 315 / 320 A [Cat.II]	1st Day /Nos.	617.11	Rupees Six Hundred Seventeen And Paise Eleven Only	617.11
95	1	1st Day /Nos.	(F) 400 A [Cat.II]	1st Day /Nos.	770.63	Rupees Seven Hundred Seventy And Paise Sixty Three Only	770.63
96	1	1st Day /Nos.	(G) 630 A [Cat.II]	1st Day /Nos.	1131.20	Rupees One Thousand One Hundred Thirty One And Paise Twenty Only	1131.20

97	1	1st Day /Nos.	(H) 1000 A [Cat.II]	1st Day /Nos.	1284.72	Rupees One Thousand Two Hundred Eighty Four And Paise Seventy Two Only	1284.72
98			Hire charges for Providing & erecting weather proof, dust & vermin proof / floor mounted Front operated outdoor type cubical Panel board having IP 64 protection made from 14 SWG thick CRC MS sheet for outer body and doors, 16 SWG thick CRC MS Sheet for internal partition with necessary supporting angles, flats including cutting, bending, drilling, welding, revetting, with internal Partition and cable alley as per requirement & instruction of Engineer in charge with SUPPLY AND ERECTION OF following type switchgears /busbars with suitable size of inter connecting PVC copper wire/ copper strips, rubber grommets, rib, earth bus and earth bolt, foundation flange-bolts - base plates, sufficient Nos. of Hinged doors, handles with locking arrangement & rubber gasket complete. The panel shall be painted with epoxy powder coating and have Cu. Busbar strips. Each bus bar should be insulated by color coded sleeve. WITH PHASE INDICATING Lamps--- Digital Multi function meter - Voltage, Amperes & Frequency only) with CTs coils) Each panel will contain earth bus and earth bolts with danger notice board.				
	1	1st Day /Nos.	[A] Cubical panel with main interior 400 A 4 pole on load Changeover switch and 400 A SFU/MCCB with four nos of 40 A DP MCB and four nos of 40 A FP MCB as standard outgoing. Other outgoing is to be incorporated as demanded by engineer in charge and rate for the same is to be taken extra in addition to this.	1st Day /Nos.	22597.74	Rupees Twenty Two Thousand Five Hundred Ninety Seven And Paise Seventy Four Only	22597.74
99	1	1st Day /Nos.	[B] Cubical panel with main interior 250 A 4 pole on load Changeover switch and 250A SFU/MCCB with four nos of 40 A DP MCB and four nos of 40 A FP MCB as standard outgoing. Other outgoing is to be incorporated as demanded by engineer in charge and rate for the same is to be taken extra in addition to this. (Refer item no 11-1-26 & 11-1-27)	1st Day /Nos.	12326.04	Rupees Twelve Thousand Three Hundred Twenty Six And Paise Four Only	12326.04
100	1	1st Day /Nos.	[C] Power Distribution Cubical Panel with main incomer 125A also with change over switch of 125A TPN MCCB - 1 Nos., 200 A Alum. Busbar, Outgoing 16A SP MCB 10 KA - 6 Nos, [Panel size 800mm H x 600 mm W x 350 mm D]	1st Day /Nos.	8217.36	Rupees Eight Thousand Two Hundred Seventeen And Paise Thirty Six Only	8217.36
101	1	1st Day /Nos.	63/100 A Four Pole Moulded Case Circuit Breaker with spreader terminal and indication lamp mounted on cubical panel with complete proper termination.	1st Day /Nos.	910.01	Rupees Nine Hundred Ten And Paise One Only	910.01
102	1	1st Day /Nos.	200 A Four Pole Moulded Case Circuit Breaker with spreader terminal and indication lamp mounted on cubical panel with complete proper termination.	1st Day /Nos.	1969.50	Rupees One Thousand Nine Hundred Sixty Nine And Paise Fifty Only	1969.50

103	1	1st day / Per Ton	Hire charges for providing erecting and dismantling after use of good running condition Air Conditioning ductable type AC Machine complete with erection, gas charging etc having capacity up to 8.5 Ton	1st day / Per Ton	2363.40	Rupees Two Thousand Three Hundred Sixty Three And Paise Forty Only	2363.40
104	1	1st day / Per Rn.Mtr	Hire charges for providing , erecting and dismantling after use of good running condition 14" flexible 600 GSM,SRF duct for ductable types ac machine one as per instruction of engineer in charge.	1st day / Per Rn.Mtr	334.31	Rupees Three Hundred Thirty Four And Paise Thirty One Only	334.31
105	1	1st day / No.	Hire charges for providing, erecting and dismantling after use 1.0 / 1.5 ton window type Air-conditioning machine complete with temporary frame and fabrication work & required materials to achieve cooling temp.	1st day / No.	837.29	Rupees Eight Hundred Thirty Seven And Paise Twenty Nine Only	837.29
106	1	1st day	Hire charges for providing erecting and dismantling after use of good running condition temporary wooden frame made of teakwood for proper support of provide window AC unit blocking the side openings around the unit by hard wood / plywood & placing the provided unit in approved manner complete.	1st day	709.02	Rupees Seven Hundred Nine And Paise Two Only	709.02
107	1	1st day / No.	Hire charges for providing, erecting and dismantling after use portable type Air-conditioning machine complete with erection ,gas charging and required flexible duct & required drain system etc. for 0.75 /1.0 Ton per one day as per instruction of engineer in charge.	1st day / No.	1952.33	Rupees One Thousand Nine Hundred Fifty Two And Paise Thirty Three Only	1952.33
108	1	1st day / No.	Hire charges for providing erecting and dismantling after use of good running Tower type /Split type Air-Conditioning machine complete with erection gas charging etc. (a) 1.5-2 ton for one day as per instruction of engineer.	1st day / No.	3595.60	Rupees Three Thousand Five Hundred Ninety Five And Paise Sixty Only	3595.60
109	1	1st day / No.	Hire charges for providing erecting and dismantling after use of good running condition Tower type/ split type Air-conditioning machine complete with erection, gas charging etc. (b) 3/4/5 Ton for one day as per instruction of engineer.	1st day / No.	7191.20	Rupees Seven Thousand One Hundred Ninety One And Paise Twenty Only	7191.20
110	1	1st day / No.	Hire Charges for providing 90 Ltr capacity refrigerator complete with M.S. stand if necessary connected with main switchgear & connecting earthing.	1st day / No.	965.56	Rupees Nine Hundred Sixty Five And Paise Fifty Six Only	965.56
111	1	1st day / No.	Hire Charges for providing 165 Ltr capacity refrigerator complete with M.S. stand if necessary connected with main switchgear & connecting earthing.	1st day / No.	1223.11	Rupees One Thousand Two Hundred Twenty Three And Paise Eleven Only	1223.11
112	1	1st day / No.	Hire Charges for providing 250 / 280 Ltr capacity refrigerator complete with M.S. stand if necessary connected with main switchgear & connecting earthing.	1st day / No.	1412.99	Rupees One Thousand Four Hundred Twelve And Paise Ninety Nine Only	1412.99

113	1	1st day / No.	Hire charges for providing 150 Ltr. Capacity water cooler with candle type water filter & M.S. Stand with minor plumbing work, connected with main switchgear and connecting earthing.	1st day / No.	1131.20	Rupees One Thousand One Hundred Thirty One And Paise Twenty Only	1131.20
114	1	Ea.	Hire charges for Supplying and erecting 19 / 20 mm. nominal bore Medium Class M.S. Pipe down rod erected with fan clamp/hook duly painted for fan complete with necessary 24/ O.20, 3 core flexible wire with earthing and installed in proper way to ensure vibration free movement..	Ea.	52.52	Rupees Fifty Two And Paise Fifty Two Only	52.52
115	1	Ea.	For Germon Dom	Ea.	103.02	Rupees One Hundred Three And Paise Two Only	103.02
116	1	Rn Mtr	Hire charges for Supplying and erecting ISI mark Medium class RIGID PVC /Flexible Pipes erected on/in wall or ceiling erected with necessary fittings & boxes fixed with adhesive solution & Clamps in approved manner as directed	Rn Mtr	4.04	Rupees Four And Paise Four Only	4.04
117	1	1st day / No.	Hire Charges for Providing,erecting &,commissioning & dismantling AHU(Air Handling Unit) for circulating air as part of air conditioning system upto 34 ton i.e four units of 8.5 ton.	1st day / No.	15408.56	Rupees Fifteen Thousand Four Hundred Eight And Paise Fifty Six Only	15408.56
118	1	1st day / No.	Hire charges for LED Flood Light Fittings with High Power White LEDs wattage of 1 Watt and above assemble on single MCPCB, efficiency more than 130 lm/w and corrosion free high pressure die cast aluminium housing with smooth finish powder coated and heat sink extruded aluminium with diffuser and Polycarbonate optics/lenses with company mark/name engraved or embossed 120 to 300 V, Power factor more than 0.95, THD<10%, CCT 5000 K to 5700K, Uniformity ratio >0.45, Luminaire efficiency > 85 Lumens/Watt, LED driver efficiency >85%. CREE/OSRAM/PHILLIPS Lumileds /NICHIA/SEOUL/BridgeLux(U.S.A) make LED used for luminaire. (Each fitting required LM-79 & LM-80 Certificates) (B) Flood Light (IP-65), Surge -4KV (e) Above 150 watts to 240 watts Cat-III	1st day / No.	994.85	Rupees Nine Hundred Ninety Four And Paise Eighty Five Only	994.85
119	1	1st day / No.	(A) Above 100watts to 120 watts Cat-III	1st day / No.	668.62	Rupees Six Hundred Sixty Eight And Paise Sixty Two Only	668.62
120	1	1st day / No.	(B) Above 70 watts to 90 watts Cat-III	1st day / No.	561.56	Rupees Five Hundred Sixty One And Paise Fifty Six Only	561.56

121	1	1st day / No.	Hire charges for providing & dismantling earth pit of minimum bore dia.150mm size approved make Earthing Electrode consisting Pipe-in-Pipe Technology as per IS 3043-1987 made of corrosion free G.I.Pipes having Outer pipe dia of 50mm having 80-200 Micron galvanizing, Inner pipe dia of 25 mm having 200-250 Micron galvanizing, connection terminal dia of 12mm with constant ohmic value surrounded by highly conductive compound with high charge dissipation suitable for following type of applications(a) For Electrical Installation up to 440V in normal soil Length of pipe - 1 Mtr Back filling compound - 1 Nos Bag of 15 Kg.	1st day / No.	770.63	Rupees Seven Hundred Seventy And Paise Sixty Three Only	770.63
122	1	1st day / No.	Hire charges for providing erecting and dismantling after use of good running condition Industrial Air Cooler With Water filling erected as per instruction of engineer-in - charge	1st day / No.	2310.88	Rupees Two Thousand Three Hundred Ten And Paise Eighty Eight Only	2310.88
123			Hire charges for 240V A.C generating set following capacity with necessary fuel, mains, switchgears & accessories complete running on load / no load as per requirement. With transportation charges up to 30 kms..				
	1	1 St.Day./ no	[A] 1 KVA to 2 KVA	1 St.Day./ no	1120.09	Rupees One Thousand One Hundred Twenty And Paise Nine Only	1120.09
124	1	1 St.Day./ no	[B] 3 KVA to 10KVA	1 St.Day./ no	4828.81	Rupees Four Thousand Eight Hundred Twenty Eight And Paise Eighty One Only	4828.81
125			Hire charges for 440V A.C generating set following capacity with necessary fuel, mains, switchgears & accessories complete running on load / no load with acoustic sound proof enclosure etc as per requirement. With transportation charges up to 30 kms.				
	1	1 St.Day./ no	[A] 3 KVA to 10KVA	1 St.Day./ no	4828.81	Rupees Four Thousand Eight Hundred Twenty Eight And Paise Eighty One Only	4828.81
126	1	1 St.Day./ no	[B] 11 KVA to 25 KVA (excluding 25 KVA)	1 St.Day./ no	5290.38	Rupees Five Thousand Two Hundred Ninety And Paise Thirty Eight Only	5290.38

127	1	1 St.Day./ no	[C] 25 KVA to 40 KVA	1 St.Day./ no	7704.28	Rupees Seven Thousand Seven Hundred Four And Paise Twenty Eight Only	7704.28
128	1	1 St.Day./ no	[D] 50/62.5 KVA	1 St.Day./ no	9245.54	Rupees Nine Thousand Two Hundred Forty Five And Paise Fifty Four Only	9245.54
129	1	1 St.Day./ no	[E] 75 KVA to 100 KVA	1 St.Day./ no	18489.06	Rupees Eighteen Thousand Four Hundred Eighty Nine And Paise Six Only	18489.06
130	1	1 St.Day./ no	[F] 125 KVA	1 St.Day./ no	24652.08	Rupees Twenty Four Thousand Six Hundred Fifty Two And Paise Eight Only	24652.08
131	1	1 St.Day./ no	[G] 250 KVA	1 St.Day./ no	39032.46	Rupees Thirty Nine Thousand Thirty Two And Paise Forty Six Only	39032.46
132			Hire charges for providing, erecting, and dismantling after use Flexible PVC insulated multistrand multi core 1.1 kv grade ISI marked copper wires for sound system of following size.				
	1	Mtr	(A).2 5 Sq.mm 3 core round I PVC sheathed	Mtr	28.28	Rupees Twenty Eight And Paise Twenty Eight Only	28.28
133	1	Mtr	(B).4.0 Sq mm 3 core round PVC sheathed	Mtr	42.42	Rupees Forty Two And Paise Forty Two Only	42.42
Rupees Two Lakh(s) Seventy Three Thousand Four Hundred Eighty Four And Paise Seventy Seven Only						TOTAL	273484.77

Contractor's signature

Deputy Executive Engineer
Ahmedabad Electrical Sub-Division
R&B Deptt., Ahmedabad.

Name of Work : Annual Rate Contract for Temporary Electrical installations ,Decorative Roshni,DG Set and A.C, Machines for Ahmedabad electrical Division No-1, Ahmedabad (Year 2026-27)

Name of Agency :- M/S. _____

I / We am / are willing to carry out the work at _____ % Below / Above
_____ (should be written in Figures and Words) the tendered amount
mentioned above,Amount of my / our tender work out as under

Put Tender Rs.- 273484.77

Deduct _____ % Rs. _____

Below

Total Rs. _____

In Words. _____

Less for Dismantal Material Rs. _____

Net Rs. _____

In Wards. _____

Put Tender Rs.- 273484.77

Add _____ Rs. _____

Above

Total Rs. _____

In Words. _____

Less for Dismantal Material Rs. _____

Net Rs. _____

In Wards. _____

(A) I / We hereby declare that / We have visited the site and fully requisite my self / our selves with the local situation regarding materials, labour and other factors pertaining to work before submitting tender.

(B) I / We hereby declare that I / We have carefully studied the condition of contract,Detailed specification and other tender document of the work and agree to execute the same accordingly.

NOTES :-

- [1] The Rates are inclusive all taxes,transport charges,octroi duty and storages up to date.
- [2] The materials covered for wiring should be got approved from Dy.Executive Engineer in charge of the work.
- [3] The materials and work shall have to be used and carried out as specification in technical naote.
- [4] All works shall be carried out as per public works Department hand book and other specification of the Division of as directed.
- [5] Rate are inclusive of 1% labour cess in tender amount so 1% of total amount of bill will be deducted from the bill.
- [6] The Agency will have to submit certificate on latter pad that Cable used in the work has been used from ISI certified cable drum as per Note of S.E. (Elect) R.&B. Department,Gandhinagar's No.4241,Date:-23/09/2008.
- [7] Dismenatal value will not be quoted below the estimate rate.

FOR TESTING OF MATERIAL:-

- [1] Material is to be used in work should be got approved by in charge E.E.
Sample of material to be used in the work is required to be tested at L.D.Engineering College of from the approved Government Research Institute,which is must sample required to be submit as per requirement of L.D.Engineering College or the approved Government Research Institute.In case of cable and wire 3 meters of sample and and for fluorescent fitting 5 Nos of ballast with 2 nos fluroscent lamp.may be required for testing no payment will be made on account of sample material consideration while quoting the tender,Actual paid by agency for testing of material will be paid by the department.Agency is requested to contact L.D.Engineering College or from the approved Government Research Institute to understand their requirement for testing of material.

Contracor's Signature.

**Deputy Executive Engineer
Ahmedabad Electrical Sub Division
R.&B.Department,Ahmedabad.**