

Name of Work Repairing and Renovation to Pashu Davakhana building at village:-  
:- Rakhej Ta:- Sutrapada Dist:- Gir Somnath

### CEMENT /STEEL REQUIREMENT STATEMENT

| Sr No. | Item No. of Schedule "B" | Item.   | Qty    | Unit | Rate in K.G. | Per | Cement required as per Rate. |
|--------|--------------------------|---|--------|------|--------------|-----|------------------------------|
| 1      | 3                        | Granite slab 18mm thick slab in risers of steps dedo and pillares laid 10mm thick cement 1:3(1-cement: 3 coarse sand) and jointed with grey cement slurry including rubbing,polishing etc complete.(Granite JAMS & SILL)  | 20.39  | Sqm  | 5.82         | Sqm | 118.67                       |
| 2      | 14                       | Providing and laying broken chine mosaic flooring for terrace using 12 mm to 20 mm broken pieces of glazed tiles to be laid over cement mortar 1:3 to plain or slope and to be tempered to bring mortar creme out upto surface using white cement including rounding off junctions and extending them upto 15 cm along the wall,clearing with water and oxalic acid etc. as directed. | 105.60 | Sqm  | 22.50        | Sqm | 2376.00                      |
| 3      | 20                       | 20mm thick sand faced cement plaster on walls upto height 10 metres above ground level consisting of 12mm thick backing coat of C.M. 1:3 (1-cement : 3-sand) and 8mm thick finishing coat of C.M. 1:1 (1-cement : 1-sand) etc. complete.  | 6.00   | Sqm  | 16.83        | Sqm | 100.98                       |
| 4      | 21                       | Providing Septic tank of size 2.50mtr x 1.50mt x 1.50mt I/I dimension with 0.23mtr thick walls including plastering and filling with brick bats with top slab in CC 1:2:4 (1-cement:2-sand:4-coarse aggregate) including centreing and shuttering and reinforcement and etc complete.   | 1.00   | No   | 860.00       | No  | 860.00                       |
| 5      | 22                       | White Stone Bela mesonry block in course in superstructure with stone of approved quality in Lime Mortar 1:5 (1-Cement :5- course sand) including packing the joints etc. complete.   | 1.44   | Cum  | 65.10        | Cum | 93.74                        |
|        |                          |   |        |      |              |     |                              |
|        |                          |   |        |      |              |     | <b>Total</b>                 |
|        |                          |   |        |      |              |     | <b>3549.39</b>               |
|        |                          |   |        |      |              |     | <b>i.e MT</b>                |
|        |                          |   |        |      |              |     | <b>3.55</b>                  |
|        |                          |   |        |      |              |     | <b>Say MT</b>                |
|        |                          |   |        |      |              |     | <b>4.00</b>                  |

### STEEL REQUIRED

|     |            |       |      |
|-----|------------|-------|------|
|     | Mild steel | 0.00  | M.T. |
| 12/ | TMT steel  | 0.000 | M.T. |

( )  
Deputy Executive Engineer  
Panchayat R.& B. Sub Division  
Veraval

( )  
Executive Engineer  
Panchayat R.& B. Division  
Gir Somnath