

<b>Name of Work :-</b>					
<b>Repairing &amp; Renovation of Gujarat Juhu At Andheri Mumbai (Providing Granite Shelves, Beds, Wooden Doors to Shelevs and Miscellaneous Work)</b>					
<b><u>Bill of Quantities</u></b>					
<b>(A) Percentage Rate Tender (Up to INR 50 Cr. )</b>					
<b>Memorandum showing items of work to be carried out</b>					
Item No.	Item of work	Quantity	Unit	Estimated	Total Amount according to estimated quantities
				In figure Rs. Ps.	
1	2	3	4	5	7
1	Providing Material & Labour charge for making king size bed having size of 1800 mm x 2100 mm made up by 18/19 mm Thk. (double - sandwich) Granite as pheripheral supports at all four sides & horizontal middle support with all necessary proper solution. Having 450 mm high base box made with 19 mm thk marin ply . Top of bed is covered by 19 mm thk marine ply & bottom is covered with 9 mm thk marine ply. Bed corners are supported with 50 mm Ghana Teak Wood round edge wood support finish with vineer melamine polish .Top & bottom ply of bed & inner side ply is covered with 1 mm thk laminate. use of Ghana Teak wood bidding appropriate size at each joints as suggested pattern.Sizes and patterns may be varies as suggested by architect. All fixtures and fastning must be approved by architect/EOI as per given standard make. Complete with all hardwares like MS Nails & SS-304 screws etc. All Details as per shown in detail drawings & as per instructions of architect / incharge engineer. Please see the Attached Make List for Apporoved Makes. Basic rate of ply is 1050.00 rs per sq mt.& Granite is 1500.00 rs per sq mt	16.0	Nos	56117.62	897881.92
2	Providing Material & labour charges for making 1.70 mt x 2.40 mt wardrobe shutter with 75 mm x 75 mm Ghana Teak Wood Frame and depth of 600 mm with suggested nos of drawers having size of 600 mm x 580 mm x 125 mm, rest on telescopic channels. Ward robe Body & Inside shelves made by 19 mm Thk. marine plywood. Back ply of ward robe is 12 mm marine ply. Drawers are made by 18/19 mm Granite & botom of drawer is made by 9 mm marine plywood. All internal surfaces are covered with 1 mm thk laminate of approved shade. All exposed surfaces are covered with 4 mm thk vineer finish with melamine polish. shutters are made with 19mm+6 mm marin ply for conceal handles. or as suggested pattern for handles. External & internal joints covered with teak wood bidding patti complete with melamine polish. All complete with proper hardwares like locks for shutters, 25 mm dia ss pipe with conceal socket, S.S. Screws, Nails, Magnets, 450mm long S.S. Handles of & 100 mm long handles for drawers, etc. Sizes and patterns may be varies as suggested by architect. All fixtures and fastning must be approved by architect/EOI as per given standard make. All Details as per shown in detail drawings & as per instructions of architect / incharge engineer. Contractor has to provided all necessary cut outs for Electrical works & no extra payment shall be made for it. Please see the Attached Make List for Apporoved Makes. Basic rate of ply is 1050.00 rs per sq mt. & Granite 1500 rs per sq, mt	40.30	Sqmt	19108.19	770060.06
				<b>Total</b>	<b>1667941.98</b>
<b>In Words Sixteen Lakh Sixty Seven Thousand Nine Hundred Forty One Rupees And Ninety Eight Paise Only.</b>					

I/We am /are willing to carry out the work at.....% above/below percent (should be written in figures and words) at the estimated rates mentioned above amount of my/your tender works out as under.			
*Estimated Amount			*Estimated Amount
put to Tender Rs.		<b>1667941.98</b>	put to Tender Rs. <b>1667941.98</b>
Deduction ..... % below.....			Add ..... % above Rs. ....
Net Total Rs. ....			Total Rs. ....
In words. ....			In words ....
.....			.....
<b>Note:-</b>			
<b>1</b>	The Contractor shall be exhibit board as per government circular No.BDG/3277/1657 N dated 26/01/1997 S (M.GUJ) with detailed specification and details of work and amount Involved at site without any payment as directed by Engineer-In-Charge.		
<b>2</b>	All work shall be carried out as per public work department hand book and other specifications of Division or as directed.		
<b>3</b>	All columns in the Schedule should be filled in ink & the total of the entries in the last column should be struck by Contractor under his sign.		
<b>4</b>	Rates quoted include clearance of site (Prior commencement of work and its close) in all respects and hold good for work under all condition, site, moisture/ weather etc.		
<b>5</b>	The Boards stating the detailed specification & details of Work shall be provided by the contractor as per Government Resolution T.No.1890-240- Dtd.18/11/1990 and directed by contractor at his own cost immediately on recommending the work order.		
<b>6</b>	Testing of Material Shall be done as per the statement attached with specification, The material IS Tested in GERI by Executive Engineer Surat and Bill for the testing charges shall be paid by Executive Engineer, 1% of the Amount put to Tender.		
<b>7</b>	1% of the Construction Cost Shall be deducted from the bill Amount of the contract as per the Buildig and other Construction works welfare cess at 1996(Labour and Employment Department Letter No CWA-2004-1831-M(3) Dated 9/12/2005 notification Of Labour & Employment department dt.03/01/2005 & Labou & Employment Department Letter no GWA/2004-841M(B) Dt 14/12/2005 & Dt.30/1/2006.		
<b>8</b>	In Case of RCC items Where there is a change in Grade of Mix or Change as per Actual Mix design the cost of difference of Cement Difference shall be deducted from the rate of original item at the rate of star rate mentioned in the tender.		
<b>9</b>	Contractor are advised to visit site before loading tender rate.		
<b>10</b>	Necessary wiring point and drainage point are installed at Site however any modification in electrical installation and drainage & water supply connection and minor correction to perform experienced in Lab shall be done by contractor at his risk and cost.		
<b>11</b>	The Rates are inclusive of all the taxes (Excluding GST), Transport Charges, Octroi duty and storage Charges up to date.		
<b>12</b>	The materials Covered for wiring should be got approved from the Engineer Incharge of the work.		
<b>13</b>	GST and Income tax TDS will be deducted at a source while making payments of bills.		
<b>14</b>	GST will be paid extra as per Govt. amendment.		
<b>15</b>	The Materials on the work shall have to be used and carried out as specified in technical note.		
<b>(A)</b>	I/We hereby Declare that I/we have Visited the site and fully Exquisite myself/ourselves with the local situation regarding materials, Labour and other factors pertaining to work before submitting tender.		
<b>(B)</b>	I/We hereby Declare that I/we have carefully Studied the condition of Contracts, Detailed Specification and other tender Document of this work and agree to execute the same accordingly.		

Signature of Bidder

**Deputy Executive Engineer  
Valsad (R&B) Sub-Division  
Valsad**

**Executive Engineer  
Valsad (R&B) Division  
Valsad**