

Name of Work : Repairing & Renovation of Gujarat Juhu At Andheri Mumbai (Providing Granite Shelves, Beds, Wooden Doors to Shelevs and Miscellaneous Work)

ITEM WISE SPECIFICATIONS

Item No: 1 Providing Material & Labour charge for making king size bed having size of 1800 mm x 2100 mm made up by 18/19 mm Thk. (double - sandwich) Granite as pheripheral supports at all four sides & horizontal middle support with all necessary proper solution. Having 450 mm high base box made with 19 mm thk marin ply . Top of bed is covered by 19 mm thk marine ply & bottom is covered with 9 mm thk marine ply. Bed corners are supported with 50 mm Ghana Teak Wood round edge wood support finish with vineer melamine polish .Top & bottom ply of bed & inner side ply is covered with 1 mm thk laminate. use of Ghana Teak wood bidding appropriate size at each joints as suggested pattern.Sizes and patterns may be varies as suggested by architect. All fixtures and fastning must be approved by architect/EOI as per given standard make. Complete with all hardwares like MS Nails & SS-304 screws etc. All Details as per shown in detail drawings & as per instructions of architect / incharge engineer. Please see the Attached Make List for Apporoved Makes. Basic rate of ply is 1050.00 rs per sq mt.& Granite is 1500.00 rs per sq mt

Item incuding The Item shall Specification:- Providing Material & Labour charge for making king size bed having size of 1800 mm x 2100 mm made up by 18/19 mm Thk. (double - sandwich) Granite as pheripheral supports at all four sides & horizontal middle support with all necessary proper solution. Having 450 mm high base box made with 19 mm thk marin ply . Top of bed is covered by 19 mm thk marine ply & bottom is covered with 9 mm thk marine ply. Bed corners are supported with 50 mm Ghana Teak Wood round edge wood support finish with vineer melamine polish .Top & bottom ply of bed & inner side ply is covered with 1 mm thk laminate. use of Ghana Teak wood bidding appropriate size at each joints as suggested pattern.Sizes and patterns may be varies as suggested by architect. All fixtures and fastning must be approved by architect/EOI as per given standard make. Complete with all hardwares like MS Nails & SS-304 screws etc. All Details as per shown in detail drawings & as per instructions of architect / incharge engineer. Please see the Attached Make List for Apporoved Makes. Basic rate of ply is 1050.00 rs per sq mt.& Granite is 1500.00 rs per sq mt.

Workmanship:

Entire work to be carried out as per drawings, instructions and supervision of the architect.

Mode of measurements:

The Item shall be measured as finished work in Nos basis.

The rate shall be consolidated for all above items. The rate shall include cost of all materials, fixtures, joineries, transport etc. & labour to complete the work satisfactorily as per instruction of Engineer-in charge.

No Extra payment will be given for any of the reasons.

The rate shall be for a per **Nos** basis including wastage.

Item No: 2 Providing Material & labour charges for making 1.70 mt x 2.40 mt wardrobe shutter with 75 mm x 75 mm Ghana Teak Wood Frame and depth of 600 mm with suggested nos of drawers having size of 600 mm x 580 mm x 125 mm, rest on telescopic channels. Ward robe Body & Inside shelves made by 19 mm Thk. marine plywood. Back ply of ward robe is 12 mm marine ply. Drawers are made by 18/19 mm Granite & botom of drawer is made by 9 mm marine plywood. All internal surfaces are covered with 1 mm thk laminate of approved shade. All exposed surfaces are covered with 4 mm thk vineer finish with melamine polish. shutters are made with 19mm+6 mm marin ply for conceal handles. or as suggested pattern for handles. External & internal joints covered with teak wood bidding patti complete with melamine polish. All complete with proper hardware like locks for shutters, 25 mm dia ss pipe with conceal socket, S.S. Screws, Nails, Magnets, 450mm long S.S. Handles of & 100 mm long handles for drawers, etc. Sizes and patterns may be varies as suggested by architect. All fixtures and fastning must be approved by architect/EOI as per given standard make. All Details as per shown in detail drawings & as per instructions of architect / incharge engineer. Contractor has to provided all necessary cut outs for Electrical works & no extra payment shall be made for it. Please see the Attached Make List for Apporoved Makes. Basic rate of ply is 1050.00 rs per sq mt. & Granite 1500 rs per sq, mt

Item including The Item shall Specification:- Providing Material & labour charges for making 1.70 mt x 2.40 mt wardrobe shutter with 75 mm x 75 mm Ghana Teak Wood Frame and depth of 600 mm with suggested nos of drawers having size of 600 mm x 580 mm x 125 mm, rest on telescopic channels. Ward robe Body & Inside shelves made by 19 mm Thk. marine plywood. Back ply of ward robe is 12 mm marine ply. Drawers are made by 18/19 mm Granite & botom of drawer is made by 9 mm marine plywood. All internal surfaces are covered with 1 mm thk laminate of approved shade. All exposed surfaces are covered with 4 mm thk vineer finish with melamine polish. shutters are made with 19mm+6 mm marin ply for conceal handles. or as suggested pattern for handles. External & internal joints covered with teak wood bidding patti complete with melamine polish. All complete with proper hardware like locks for shutters, 25 mm dia ss pipe with conceal socket, S.S. Screws, Nails, Magnets, 450mm long S.S. Handles of & 100 mm long handles for drawers, etc. Sizes and patterns may be varies as suggested by architect. All fixtures and fastning must be approved by architect/EOI as per given standard make. All Details as per shown in detail drawings & as per instructions of architect / incharge engineer. Contractor has to provided all necessary cut outs for Electrical works & no extra payment shall be made for it. Please see the Attached Make List for Apporoved Makes. Basic rate of ply is 1050.00 rs per sq mt. & Granite 1500 rs per sq, mt.

Workmanship:

Entire work to be carried out as per drawings, instructions and supervision of the architect.

Mode of measurements:

The Item shall be measured as finished work in Nos basis.

The rate shall be consolidated for all above items. The rate shall include cost of all materials, fixtures, joineries, transport etc. & labour to complete the work satisfactorily as per instruction of Engineer-in charge.

No Extra payment will be given for any of the reasons.

The rate shall be for a per **Nos** basis including wastage.

Signature of Contractor

**Deputy Executive Engineer
Valsad (R&B) Sub-Division
Valsad**

**Executive Engineer
Valsad (R&B) Division
Valsad**