

Name of Work :- Suvidhapath Yojana Year -2025-26

**Constructing a C.C. road on Barumal Gurudham Dudhabhavan to
Amali Road. Km (0/0 to 0/800) Ta. Dharampur, Dist. Valsad..**

Instruction to Bidders

Only those contractors who fulfill the following qualifying criteria shall be eligible for this work.

- (1) Contractors having registered in **“D” class and above** in State of Gujarat, or equivalent category.
- (2) The contractor must have completed in any last five year, at least one B.T. + C.C. road/ C.C. road work having updated completion cost not less than Rs. **0.39** crores (40% of the amount put to tender of the road work out of which minimum 30 % amount must consist cement concrete pavement or Cement concrete work laid with fixed form/ Slip form paver, i.e. minimum cost of cement concrete pavement completed shall not be less than 12 % of the amount put to tender **i.e. 0.24 Crore**)

Or

At least one work of B.T. road having updated completion cost not less than Rs. **0.39** crores (40% of the amount put to tender) + another work involving cement concrete pavement or Cement concrete work laid with fixed form/ Slip form paver with updated completion cost not less than Rs. **0.12** crores (12% of the amount put to tender)

- (3) Such work must have been completed within last **Five** financial years i.e. from **1/4/ 2020** till the due date of bid for the proposed work.

- (4) The contractor shall have to submit on line

The contractor shall have to submit following documents online.

1. Registration Certificate
2. Solvency Certificate
3. Demand draft for Tender fee
4. Demand draft for EMD or Exemption Certificate/ FDR
5. Form 3A with clearly mentioning cost of C.C. pavement issued by employer to substantiate successful experience of similar work. When employer of similar work is not a government/ Semi Govt body, following need also to be furnished.
 - i. Self attested copy of Work Order.
 - ii. Self attested copy of agreement
 - iii. Self attested copy of Completion certificate.

- iv. Self attested copy of Final Bill
 - v. Self attested copy of TDS certificates
 - vi. Self attested copy of letter of permission given by employer for subletting the work
6. Proof of having ownership of fixed form/ slip form paver and Concrete batching & mixing plant (minimum Capacity 15-30 Cum/ Hour) / or Purchase order of such Machineries/ Hire agreement of such machineries to be deployed on work.

Price bid of only those contractors will be opened who has submitted the above details online in preliminary stage and evaluated as qualified in above criteria.

Deputy Executive Engineer.
Panchayat (R&B) Sub-Division
Dharampur

Executive Engineer
Panchayat (R&B) Division
Valsad

ઈજારદારશ્રીઓની માર્ગદર્શક સુચનાઓ

- (૧) સદર સી.સી. રોડનું કામ (કન્વેન્શનલ) ચીલા-ચાલુ પદ્ધતિથી કરવાનું નથી. આ સી.સી. રોડની કામગીરી બેચ મીક્ષ પ્લાન્ટ (૧૫ થી ૩૦ cmt/hour capacity) અથવા RMC પ્લાન્ટ નજીકમાં હોય તો તેના વડેજ કામગીરી કરવાની છે.
- (૨) સદર કોન્ક્રીટ બેચ મીક્ષ પ્લાન્ટ તથા RMC પ્લાન્ટ પર સરકારના પ્રતિનિધી હાજર હોય ત્યારેજ કામગીરી કરવાની રહેશે.
- (૩) કન્ટ્રોલ્ડ સિમેન્ટ કોન્ક્રીટ કરવાનું છે જેમાં મીક્ષ ડિઝાઈન માં મિનિમમ સિમેન્ટ કન્ટેન્ટ ટેન્ડર સ્પેશીફિકેશન મુજબ જાળવવાની રહેશે.
- (૪) કોન્ક્રીટ પાથરવાની કામગીરી ટેન્ડર કલોઝમાં આપેલ સુચનાઓ મુજબ જ કરવાની છે. તથા ડી.એલ.સી. અને પી.ક્યુ.સી. કોન્ક્રીટને (સ્પેશીફિકેશન કલોઝ ૬૦૨.૮.૩.૩) એપ્રુવડ-ફીક્સ / સ્લીપ ફોર્મ પેવરથી પાથરવાનાં રહેશે.
- (૫) કોન્ક્રીટ પાથરવાની કામગીરી થયા બાદ તરતજ જ્યુટ બેગ (કંતાન) ભીનું કરી પાથરી દેવાનું રહેશે. જેથી Shrinkage crack આવે નહીં.
- (૬) વધુ ગરમીનાં દિવસોમાં સવારે અને સાંજના સમયે કોન્ક્રીટ પાથરવાની કામગીરી કરવી હિતાવહ હોઈ તે પ્રમાણે આયોજન કરવું. સ્પેશીફિકેશન મુજબ ટેમ્પરેચર જાળવી કામગીરી કરવી.
- (૭) ડી.એલ.સી. ક્યો બાદ તેનાં ઉપર સીન્થેટીક ફાઈબર ૧૨૫ માઈક્રોનની પોલીથીન શીટ કીઝ ન પડે તે રીતે પાથરવાની રહેશે. (કલોઝ ૬૦૨.૨.૫ પ્રમાણે) જેના ફોટોગ્રાફ રજૂ ક્યો બાદ આગળની કામગીરી કરવાની રહેશે.
- (૮) ઈજારદારશ્રીએ દરેક સ્ટેજ, દરેક આઈટમ વાઈઝ કામગીરીના ફોટોગ્રાફ રજૂ કરવાની રહેશે. જેની કોઈ અલગ રકમ ચુકવવામાં આવશે નથી. કોન્ક્રીટ પાથરવાની કામગીરી માટે સેમ્પલ સ્ટ્રેચની કામગીરીની વિડીયોગ્રાફી કરી, મંજૂર કરાવી, આગળની કામગીરી કરવાની રહેશે. જેનું કોઈ અલગ ચુકવણું કરવામાં આવશે નહીં.
- (૯) ડોવેલ બાર, ટાઈબાર અને જોઈન્ટ વગેરેના ફોટોગ્રાફ રજૂ કરવાનાં રહેશે. જેનું કોઈ અલગથી ચુકવણું કરવામાં આવશે નહીં.
- (૧૦) કોન્ક્રીટ પાથરવાની કામગીરી માટે ઈજારદારશ્રીએ ઓછામાં ઓછો એક ઈજનેર (બી.ઈ. સીવીલ) આવા પ્રકારના કામનો ૩ વર્ષનો અનુભવ અથવા ડીપ્લોમાં ૫ વર્ષનો અનુભવ ધરાવતો હોય તેમને સતત હાજર રાખવાના રહેશે.
- (૧૧) RMC પ્લાન્ટ ચાલુ હોય ત્યારે પણ એક ઈજનેર (બી.ઈ. સીવીલ) આવા પ્રકારના કામનો ૩ વર્ષનો અનુભવ અથવા ડીપ્લોમાં ૫ વર્ષનો અનુભવ ધરાવતો હોય તેમને સતત હાજર રાખવાના રહેશે.
- (૧૨) ઉપર મુજબના ઈજનેરોની હાજરી વગર કામ કરી શકાશે નહીં.

(૧૩) ઈજારદારશ્રીએ કામના સ્થળે એગ્રીગેટ ટેસ્ટીંગ, કોમ્પ્રેસીવ/ ફ્લેકચરલ સ્ટ્રેન્થ ટેસ્ટીંગ ઈકવીપમેન્ટ અને અન્ય માલસામાન પરીક્ષણના જરૂરી સાધનો સહિતની લેબોરેટરી ફરજિયાતપણે ઉભી કરવાની રહેશે