

<u>VAGODIYA NAGARPALIKA</u>					
<u>VAGODIYA</u>					
Name Of Work :- Paver Block Work At Ward. 02 Mantri House at Vagodiya .					
<u>SCHEDULE-B</u>					
No	Description	Quantity	Total Rate	Per	Amount
1	Box cutting the road surface to proper slope and camber for making a base for road work including removing the excavated stuff and depositing on the road side slope as directed upto 50Mt.lead.	70.20	106.81	Cum.	7498.06
2	Providing and laying cement concrete 1:4:8 (1- Cement : 4- coarse sand : 8- hand broken stone aggregates 40 mmnominal size) and curing complete excluding cost of formwork in (A) Foundation and Plinth	46.80	2747.21	Cum.	128569.43
3	Providing and fixing pre-cast Rubber Dye / steeln Dye inter locking concrete block 60mm thick with grade of concrete M300 pnumatic compressed / vibrated mechanically and as per approved design Confirming to IS 15658 : 2006 including 35 mm Sand layer for levelling and filling the joint with sand in proper line and level as per guidlines of IRC : SP 63-2018 etc. Complete.	468.00	704.07	Sqmt.	329504.76
4	Providing and fixing pre-cast concrete kerb stone of gray cement based concrete block 30cm length,30cm height and 15cm thick of M200 grade concret as per approved design and including excavation for fixing in proper line and level,filling the joint with C:M 1:3 (1cement:3fine sand) etc complete.	32.00	394.59	Mt.	12626.88
				Total :	478199.13
			Add 18% GST :-		86075.84
			Add 3 % Cont. & Superv. :		14345.97
					578620.95
				Say :-	578621.00