



**GUJARAT PAVITRA YATRADHAM VIKAS BOARD
Gandhinagar**

**TENDER DOCUMENT
FOR**

**Development of Shri Tulshishyam Yatradham
Ta. Una Dist. Gir- Somnath**

General Condition

Address: Gujarat Pavitra Yatradham Vikas Board
Block 2-3,
Dr. Jivraj Mehta Bhavan,
Gandhinagar.

Phone No.: +91 79 23252459, 23252468 **Fax No.:** +91 79 23252458

E-mail: gpyvb@yahoo.co.in

General Condition

- As Most of the buildings are new, there are chances that measurement vary from drawing hence contractor will submit measure drawing of all the buildings before commencement of work.
- Contractor to provide detailed survey and total station drawings of the entire site before commencement of work.
- As built drawing is in the scope of contractor.
- Contractor shall take approval of architect/ client before placing order of all the finishing and bought out items.
- Material applied without approval of architect shall be considered as nil and will not be part of bill.
- Damage caused to existing building while renovation / extension to be repaired by contractor.
- No tree to be removed without consent of client and architect.
- Contractor shall submit shop drawing for all fabrication work and architect's consultant will be providing approval for the same.
- Contractor shall submit the shop drawings, 3D/ mock up of the any specific stone work items such as carving work at main gate , stone artwork/ sculptures. The detailing of design and carving shall be prepared based on the theme of Krishna.
- Contractor has to submit the detailed shop drawings with 3D images for the lighting effects at stonework on building façade and other elements such as stone post, parapet, stone gate, jali etc.
- Stone carving work and detailing shall the follow the language of the stone work done at tulsishyam temple, site. The new stone work at Main gate temple must match the quality and finishing of the stone work done at mentioned site.
- Approval shall be given by Architect / Client for the submitted shop drawing / Prototype model, all materials by Bidder.
- After completion of tender work the bidder shall submit structure stability certificate for the all Art & Sculpture work.
- For all type of Sub Estimate work, The rate shall include the cost of all materials, labour, scaffolding, transport , tools , tackles , hardware's , accessories, core cutting, finishing, including As built drawing, shop drawing, etc. to complete the whole work satisfactorily as per instruction of Architect/Client. No extra payment will be given for any of the reasons.
- The contractor shall construct/provide site office handling whole project. The location and plan shall be approved from Engineer-in-charge. Specification for the site office shall be portable type. A project engineer appointed by GPVYB shall also coordinate and handling project from site office set up by contractor