

BILL OF QUANTITIES**(A) Percentage Rate Tender (Up to INR 50 Cr.)**

Name of Work:- Carrying out ROW Validation/Demarcation with respect to Village Map/JM Sheet And Staking out ROW UTM Co-ordinate for Karjan Right Bank Main Canal and Gora Distributary including minors, Ta. Nandod and Garudeshwar, Di. Narmada.

Item No	Description of Item (with brief specification and reference to book of specifications)	Quantity	Unit	Rate In figures	Amount
1	Carrying out ROW Validation/Demarcation with respect to Village Map or JM Sheet And also collection of all map and Existing Field DGPS UTM CO-ordinate Superimpose. Preparation of Final DGPS UTM Co-ordinate.	111.825	km	14800.00	1655010.00
2	Staking out ROW with respect to JM Sheet, Finalization of DGPS UTM Co-ordinate for using DGPS Instruments. Providing and Fixing TBM Stone (Size 230 mm x 230 mm x 1000mm) of ROW at Every 1 Km and Indicator Stone (Size 150 mm x150 mm x450 mm) of ROW at Every 50 Mt Both Stone Painted red on top as per Point Marking and Final DGPS UTM Co-ordinate.	111.825	km	29900.00	3343567.50
				Total	4998577.50

Rupees Forty Nine Lakh Ninety Eight Thousand Five Hundred Seventy Seven and Fifty Paise Only

I/We am/are willing to carry out the work at..... % above/below percent (Should be written in figures and words) of the estimated rate mentioned above.

Amount of my /our tender works out as under.

Estimated amount put to tender

Estimated amount put to tender

Deduct.....% below

Deduct.....% below

Net

Net

In words

In words

- 1 The Contractor shall exhibit a board with brief details of work as directed by the Engineer-In-Charge for which no extra payment shall be made.
- 2 The labour cess will be deducted as per prevailing rules i.e. 1% of the work done.
- 3 GST and Income tax TDS will be deducted at a source while making payments of bills

In all R.C.C. Items in Rate Analysis Standard Cement Consumption has been taken as per Govt. G.R. NO.: MIS102010/17/K1

- 4 Dated:30/07/2018 as stated in S.O.R. therefore in R.C.C. items where there is a change as per actual mix design the cost of difference of cement consumption have been deducted from the rate of original item at the rate of input rate mentioned in all the tender.

Signature of Contractor

**Deputy Executive Engineer
Irrigation Project Subdivision No. 29
Rajpipla**