

RADHANPUR NAGARPALIKA

Construction Work of CC Road in Radhanpur Nagarpalika Various area at Radhnapur Nagarpalika (Second Attempt)

Schedule-B

Sr.No	Qty.	Item	Rate	Units	Amount
1	761.00	Demolition and disposal of unserviceable materials with all lead and lift.(i) Lime concrete.	652.69	Cum	496697.09
2	307.00	Providing and laying cement concrete 1:4:8 (1 Cement : 4 coarse sand :8 hand broken stone aggregates 40 mm nominal size) and curing complete excluding cost of form work in (A) Foundation and plinth	2749.06	Cum	843961.42
3	460.00	Providing and casting in situ ordinary cement concrete 1:1.5:3 (1 Cement :1.5Coarsed Sand : 3 Graded Stone Aggregate 20mm nominal size) for C.C. Road Including Compaction and finishing by trimix process including providing Construction Contraction and expansion joint and filling in joints with Asphalt filler jont etc. completed as directed by engineer in charge.	3945.53	Cum	1814943.80
4	3065.00	Trimix (vaccume, dewatering service) process for road work by using vaccume dewatering equipment flocater surface vibretor incl. making grove and rough finish to surface incl. curing Completion	75.75	Sqm	232173.75
5	34.00	Renivation of manhole by increasing the height at top including cost of excavation refitting of C.I manhole frame and cover curing etc. comletete incl.all carting and providing of materials which is required for the purpose (except manhole frame and cov for all type manhole by providing RCC 1:2:4 partation walls with required reinforcement	3407.74	Nos	115863.16
					3503639.22
			Total amount		3503640.00

I/We am/are willing to carry out the work at% above/below percent (should be

Estimated amount		Estimated amount	
Put to tender Rs.....		Put to tender Rs.....	
Deduct% below Rs.....		Add.....% above Rs.....	
Total Rs.....		Total Rs.....	
In words		In words	

(*Please strike out whichever is not applicable).