

BHABHAR NAGARPALIKA BHABHAR

Name of Work : -Construction Of Rain Basera At-gaytri Girls Hostel Near At Bhabhar Nagarpalika Bhabhar

Schedule-B

Sr.No	Qty.	Item	Rate	Units	Amount
1	7.00	Providing and laying controlled cement concrete M.250 and curing complete excluding the cost of formwork and reinforcement for reinforced concrete work in (A) Foundations, footings, Base of columns and Mass concrete.	6577.99	Cum	46045.93
2	283.00	Providing TMT Bar FE 500 reinforcement for R.C.C. work including bending, binding and placing in position complete upto floor two level	77.29	Kg	21873.07
3	38.00	Steel work, riveted in built up sections framed work including cutting, hoisting, fixing in position and applying a priming coat of read lead paint. (A) In beams and joists, channels angles Tees, flats, with connecting plates or angle cleats as in main and cross beams. Hip and jack rafters, purlins conneted to common rafters and the like.	5889.50	Quaint	223801.00
4	164.00	Providing corrugated G.I. sheet of class-3 roofing fixed with glavanished iron J or L Hooks, Bolts and nuts 8mm diameter with bitumen and G.I. limpet washer or G.I. limpet washer. filled with white lead complete excluding the cost of purlins, Rafters and Trusses.(1) 0.80 mm thick sheet.	734.19	Sq.Mt	120407.16

Total Amount **412127.16**

Add 18.00 % GST 74182.89

Total Amount 486,310.05

Add PMC & TPI Charges @ 3.00 % 14589.3

Total Amount 500,899.35

Say Amount 500,900.00

written in figures and words) of the estimated rates mentioned above. Amount of my/our tender works out as under.

Estimated amount

Put to tender Rs.....

Deduct% below Rs.....

Total Rs.....

In words

(*Please strike out whichever is not applicable).

Estimated amount

Put to tender Rs.....

Add.....% above Rs.....

Total Rs.....

In words

Note PMC & TPI Charges will be deducted from Contractor's Bill