

**Name of Work :- Resurfacing of Various Roads of Taluka Lakhpat (Package No. 01) District Bhuj-Kachchh under
Normal Resurfacing Budget-2024-2025 (Total 2 Roads, Length 1.50 Km.)**

SCHEDULE FOR TESTING OF MATERIALS

For ensuring quality control and workmanship, various tests prescribed below for materials shall be taken at periodical intervals as stipulated below.

The material should be tested in GERI or Private laboratory approved by Govt. of Gujarat. Bill for testing charges should be paid Govt.

Item No. as per Schedule 'B'	Brief Description of materials to be tested.	Qty. of Materials	Unit	Prescription of test which shall be carried out	Frequency @ which test shall be carried out	Total Nos of test to be taken
1	2	3	4	5	6	7
1	45 to 90 MC.Metal	136.73	Cum	*Gradation test	1 to 100 - cum. 1 test	3
				*Impact Value	100 to 500 - cum. 3 test	
				*Flakiness Index of	500 to 1500 - cum. 5 test	
2	40 to 63 M.C.Metal	499.73	Cum	*Gradation test	1 to 100 - cum. 1 test	3
				*Impact Value	100 to 500 - cum. 3 test	
				*Flakiness Index of	500 to 1500 - cum. 5 test	
					1500 to 5000 - cum. 7 test	
3	25 to 40 M.C.Metal	170.00	Cum	*Gradation test	1 to 100 - cum. 1 test	3
				*Impact Value	100 to 500 - cum. 3 test	
				*Flakiness Index of	500 to 1500 - cum. 5 test	
					1500 to 5000 - cum. 7 test	
4	Kapchi 20 mm Nominal	550.00	Cum	*Gradation test	1 to 100 - cum. 1 test	5
				*Impact Value	100 to 500 - cum. 3 test	
				*Flakiness Index of	500 to 1500 - cum. 5 test	
					1500 to 5000 - cum. 7 test	
5	Grit (6 mm)	364.16	Cum	*Gradation test	1 to 100 - cum. 1 test	3
				*Impact Value	100 to 500 - cum. 3 test	
				*Flakiness Index of	500 to 1500 - cum. 5 test	
					1500 to 5000 - cum. 7 test	
6	Grit as Key aggregate (12 mm)	60.00	Cum	*Gradation test	1 to 100 - cum. 1 test	1
				*Impact Value	100 to 500 - cum. 3 test	
				*Flakiness Index of	500 to 1500 - cum. 5 test	

Item No. as per Schedule 'B'	Brief Description of materials to be tested.	Qty. of Materials	Unit	Prescription of test which shall be carried out	Frequency @ which test shall be carried out	Total Nos of test to be taken
1	2	3	4	5	6	7
					1500 to 5000 - cum. 7 test	
7	Supplying of Hard murrum	300.00	Cum	*Gradation,CBR	One test per work	One test per work
8	Supplying of Sand	180.10	Cum	*Silt Content,F.M	One test per work	"
9	Stonedust	104.48	Cum	*Gradation	One test per work	"
10	Selected Soil for Embankment	0.00	Cum	P.I ,CBR,MDB		-
11	Natural GSB	0.00	Cum	*Gradation,P.I,CBR		"
12	Asphalt (VG-30)	27.60	M.T.	Viscosity Test	Tanker test in Geri Lab. Only	1
				as per I.S. 1206	Up to 10 1	
					11 to 20 2	
					20 to 50 3	
					Above 50 one per Tanker	
				Ductility Test	As per I.S. 1208	
				Specification Gravity test	As per I.S. 1202	
				Softening point test	As per I.S. 1204	
				Quality of binder test	3 test per 2 tankers on plant site.	
13	Tack Coat	0.00	Sqmt	*Binder Temperature for application	Irregular close in intervals	
				*Rate of spread of Binder.	2 test per Day.	
14	Carpet & Seal Coat. Mix			Grading	One Test on Individual	
				Temperature of binder in Boiler aggregates in the dryer and mix at the time of laying and rolling. (Binder content vide 45/MD. 2172)	Constituents and mixed aggregates from the dryer for each 100 tonnes of mix subject to minimum of Two tests per plant per day. One Test for each 100 tones of mix subjects to minimum of two per Day.	
				Rate of Spreaded mix materials.	Regular control through checks on layer thickness.	
15	Cement (OPC)	191.00	M.T.	*Consistency,Soundness	1 test @ 50.0 M.T. 100 T 2 tests,	3
				*Setting time,Finessness Test	200 T 3 tests, 300 T 4 tests, 500 T 5 tests,	

Item No. as per Schedule 'B'	Brief Description of materials to be tested.	Qty. of Materials	Unit	Prescription of test which shall be carried out	Frequency @ which test shall be carried out	Total Nos of test to be taken
1	2	3	4	5	6	7
				*Compressive Strength.	800 T 6 tests, 1300 T 7 tests & 8 tests for large consingment.	
16	Steel (TMT)	6.10	M.T.	*Tensile, (TMT)	As per Manual of Quality Control	1
				Yield	1 test/40 tonnes / per category	
				*Elongation		
				Size		
17	C.C.Cube Test 1:2:4			*Compressive Strength.	1 to 5 cmt - 1 No	
	M200	300.00			6 to 15 cmt - 2 No	9
	M150	200.00			16 to 20 cmt - 3 No	7
	M 1:2:4				20 to 50 cmt - 4 No	
	M250	0.00			51 to above - 4 +1 additional sample for each 50 cu.mt. Or part there of.	0
18	Retro Reflective Sheeting for the signage	22.00	Nos.	as per Test schedule attached GR SOR/1018/715/Part file/C-1 Dtd.4/6/19		
19	Road studs / Cat Eyes	168.00	Nos.	as per Test schedule attached GR SOR/1018/715/Part file/C-1 Dtd.4/6/19		
20	Hot Applied Thermoplast Road Marking	450.00	Sqmt	as per Test schedule attached GR SOR/1018/715/Part file/C-1 Dtd.4/6/19		

Note (1) :- In case of excess in quantity. Further more test shall be carried out as per required frequency.

Note (2) :- Apart from above listed materials for carrying out various tests during Road / Structure Construction works, if any other than above mentioned material/s are to be used during road / structure construction work then it must be tested as per prevailing criteria of Govt. of Gujarat (R & B Deptt.) and necessary tests should be carried out as per prevailing norms.

Signature of Contractor

Deputy Executive Engineer
Panchayat (R & B) Sub Division

Executive Engineer
Panchayat (R & B) Division

Item No. as per Schedule 'B'	Brief Description of materials to be tested.	Qty. of Materials	Unit	Prescription of test which shall be carried out	Frequency @ which test shall be carried out	Total Nos of test to be taken
1	2	3	4	5	6	7

Dayapar

Bhuj - Kachchh