

KACHCHH PANCHAYAT R. & B. DIVISION BHUJ

**NAME OF WORK : CONSTRUCTION OF ROAD IN DIFFERENT AREAS OF NANI
NAGALPAR VILLAGE OF TA. ANJAR(DMF/PMKKY/2026)**

SPECIFICATION INDEX

Sr.No.of the Item in schedule-"B"	Brief Description of Item	Page No.
4	Box cutting the road surface to proper slope and camber for making a base for road work including removing the excavated stuff and depositing on the road side slope as directed upto 50Mt.lead.	As per separate sheet attached
5	Providing & Laying cement concrete 1:4:8 (1-Cement 4-Coarse sand 8-machine crushed stone aggregates 40mm nominal size) and curing complete in foundation and plinth.	As per separate sheet attached
6	Proving and laying cement concrete Grade M20 C.C.1:1.5:3(1 Cement:1.5 Coarse Sand:3 stone agg 20mm nominal size) for CC road and curring etc. comp. incl. cost of form work. Finishing the cement concrete road by Tri-mix process inclusive of labour charges for trimix vacume dewatering process on cement conc. road by using vacume dewatering pump, surface floater, including chanelling and making grooves & rough finish to surface, providing expansion joint, construction joint incl. filling the joint with asphalt filler as per direction by engineer in charge as per specification.	As per separate sheet attached

**Deputy Executive Engineer
Panchayat (R&B) Sub-Division
Mundra-Kachchh**