

BOQ for Maintenance of Solar Street Light Installed at various Location in Kanwariya Route starting from from Ajgaivinath Temple to Dumma Border.						
S. No	Ref	Particulars	Unit	Qty.	Rate	Total
1	MR	Supply, Installation, Testing and Commissioning of 20W LED Luminaries with MPPT on Existing Pole with 3 Year Warranty. (Including all accessories required.)	Each	150	3361.45	504217.50
2	MR	Supply, Installation, Testing and Commissioning of 75 Wp PV Module on Existing Pole with 3 Year Warranty. (Including all accessories required.)	Each	150	8739.10	1310865.00
3	MR	Supply, Installation, Testing and Commissioning of 12.8V/24Ah LiFePO4 Battery Pack on Existing Pole with 3 Year Warranty. (Including all accessories required.)	Each	150	3361.45	504217.50
					Total	2319300.00