

MANDVI NAGAR SEVA SADAN,MANDVI

NAME OF WORK : ANNUAL RATE FOR C.C. ROAD REPARING AT MANDVI NAGARPALIKA AREA, MANDVI NAGARPALIKA.

It. No.	QTY	ITEM OF WORK	RATE	UNIT	Total
1	1	Box cutting the road surface to proper slope and camber for making a base for road work including removing the excavated stuff and depositing on the road side slope as directed upto 1km.lead.	215.62	CMT	215.62
2	1	Necessary Excavation up to 1.5 mt. depth	253.88	CMT	253.88
3	1	Earth filling in foundation and plinth with murrum or selected soil	239.07	CMT	239.07
4	1	Providing and laying cement concrete 1:4:8 (1- Cement : 4- coarse sand : 8- hand broken stone aggregates 40 mm nominal size) and curing complete excluding cost of formwork in (A) Foundation and Plinth (upto 10 ton)	2769.69	CMT	2769.69
5	1	Providing and laying cement concrete 1:2:4 (1- Cement : 2- coarse sand : 4- hand broken stone aggregates 20 mm nominal size) and curing complete excluding cost of formwork in (A) Foundation and Plinth (upto 10 ton)	3740.22	CMT	3740.22
6	1	Providing & laying controlled cement concrete M 200 and curing complete excluding the cost of formwork and reinforcement of reinforced concrete work in. (A) Foundation footing, base of columns and mass concrete. Tremix	4500.00	CMT	4500.00
7	1	Demolition including stacking of serviceable materials and disposal of unserviceable materials with all lead and lift. (i) concrete work	1082.35	CMT	1082.35
8	1	Supplying promoulded Bitumious Joint Filler (i) 12mm thick	553.79	CMT	553.79
9	1	Providing TMT Bar FE 500/500D reinforcement for R.C.C work including bending, binding and placing in position complete upto floor two level	77.29	KG	77.29
TOTAL					13431.91

Note: GST Paid as Per Government Rules.

I/We am/are willing to carry out the work @..... % above/below (Percent should be written in figures and words) The tendered amount mentioned above amount of my /our tender works out as under

Tendered amount Rs.....

Add% above Rs.....

Total Rs.....

In words.....

(Please strike out which ever is not applicable)

Note :

1 All work shall be carried out as per public works department handbook and other specifications of division or as directed.

2 Rates quoted inclusive of clearance of sight (prior to commencement of work and at its close) in all respect and hold good for work under all conditions , sight, moisture, weather etc

3 one percent labor cess will be deducted from the valued work done as per ' Bulding and other construction work welfare cess act' G.R. No. GHR - 2005/04/CWA/2004/841/M-3 Dt. 31/01/2005

Signature of the Contractor :