

MANDVI NAGAR SEVA SADAN,MANDVI					
NAME OF WORK : ANNUAL RATE FOR DRAINAGE WORK REPAIRING AT MANDVI NAGARPALIKA AREA, MANDVI NAGARPALIKA.					
It. No.	QTY	ITEM OF WORK	RATE	UNIT	Total
			In figure		
1	1	Excavation for foundation upto 1.5 m depth including sorting out and stacking of useful materials and disposing off the excavated stuff upto 50 Meter lead.(B) Dense or Hard soil	157.33	CMT	157.33
2	1	Filling available excavated earth (excluding rock) in trenches. plinth, sides of foundations etc. in layers not exceeding 20 cm. in depth consolidating each disposed layer by ramming and watering	136.92	CMT	136.92
3	1	Demolition and disposal of unserviceable materials with all lead and lift.(i) Lime concrete.	623.02	CMT	623.02
4	1	Brick work using common burnt clay building bricks having crushing strength not less than 35 kg./Sq.Cm. in foundation and plinth in Cement Mortar 1:5. (1Cement : 5 -fine sand) (A) (Sub/supper structure necessary 9" or 14")	4245.09	CMT	4245.09
5	1	Providing 15mm thick cement plaster in single coat on Rough (Similar)side of single or half brick walls for interior plastering upto floor two level and finished even and smooth in (ii) Cement mortar 1:4 (1- cement :4-sand) (Sub/supper structure necessary)	161.2	SQM	161.20
6	1	Existing manhole/storm water, inspaction chamber, raising work 0.10 meter height	843.5	NOS	843.50
7	1	Existing manhole/storm water, inspaction chamber, raising work 0.30 meter hight	2530.50	NOS	2530.50
8	1	Existing manhole/storm water, inspaction chamber, raising work 0.60 meter hight	5061	NOS	5061.00
9	1	Removal of old sewer line 150 MM	31	RMT	31.00
10	1	Removal of old sewer line 200 MM	42	RMT	42.00
11	1	Removal of old sewer line 250 MM	56	RMT	56.00
12	1	Removal of old sewer line 300 MM	70	RMT	70.00
13	1	Removal of old sewer line 450 MM	102	RMT	102.00
14	1	Drainage line repairing ,pipe fittings etc.for labour work only	500	RMT	500.00
15	1	only fitting of following all size, frame & r.c.c. cover with all type of meterial and labour (excluding supply of manhole cover & frame)	1000	NOS	1000.00
16	1	fixing ISI standard company 110mm dia PVC 6 kg. pipe with all type labour.	21.85	RMT	21.85
17	1	Supply Labour Unskilled	462	NOS	462.00
18	1	Supply Labour skilled	474	NOS	474.00
TOTAL					16517.41
Note: GST Paid is Government Rules.					
<p>I/We am/are willing to carry out the work @..... % above/below (Percent should be written in figures and words) The tendered amount mentioned above amount of my /our tender works out as under</p> <p>Tendered amount Rs.....</p> <p>Add% above Rs.....</p> <p>Total Rs.....</p> <p>In words.....</p> <p style="text-align: center;">(Please strike out which ever is not applicable)</p>					
Note :					
1	All work shall be carried out as per public works department handbook and other specifications of division or as				
2	Rates quoted inclusive of clearance of sight (prior to commencement of work and at its close) in all respect and hold good for work under all conditions , sight, moisture, weather etc				
3	one percent labor cess will be deducted from the valued work done as per ' Bulding and other construction work welfare cess act' G.R. No. GHR - 2005/04/CWA/2004/841/M-3 Dt. 31/01/2005				
Signature of the Contractor :					
Chief Officer Mandvi Nagarpalika					