

MALIYA MIYANA NAGARPALIKA					
Taluka - Maliya			District -Morbi		
SCHEDULE - B					
Name of work : - Resurfacing of existing Road damaged by heavy Rain during monsoon 2026-27 at various place in various area in Maliya Miyana NagarPalika Area at Maliya Miyana.					
Qty. Estimated	Description of Item	RATE		Per	Amount
		In figer	In words		
	Item No.1				
1.00	Box cutting the road surface to proper slope and camber for making a base for road work including removing the excavated stuff and depositing on the road side slope as directed upto 50Mt.lead.	108.16	Rupees One Hunred Eight Paise Sixteen Only	Cum	108.16
	Item No. 2				
1.00	Providing and laying compacted W.B.M 150mm thick of machine crushed B.T metal of size 40mm to 63mm including spreading using 25% sand as filler in two layers of 75mm thick each including spreading watering and consolidating using vibratory roller etc, complete..	1230.87	Rupees One Thousand Two Hundred Thirty Paise Eighty Seven Only	Cum	1230.87
	Item No. 3				
1.00	Repairing work & Uplifting of exesting sewerage chamber to road level up to 0.15 mt hight etc, complete & engineer instruction.	4109.69	Rupees Four Thousand One Hundred Nine Paise Sixty Nine Only	Nos	4109.69
	Item No. 4				
1.00	Demolition including stacking of serviceable materilas and disposal of unserviceable materials with all lead and lift. (i) Lime concrete.	623.02	Rupees Six Hundred Twenty three Paise Two Only	Cum	623.02
	Item No. 5				
1.00	Providing and Laying Cement Concrete 1:4:8 (1: Cement , 4: Course Sand, 8: Crushed Broken Stone aggregate 40 mm nominal size) and Complete curing complete eccluding cost of form work in (A) Foundation and Plinth (3 inch/4 inch)	2925.97	Rupees Two Thousand Nine Hundred Twenty Five Paise Ninety Seven Only	Cum	2925.97
	Item No. 6				
1.00	Providing and laying in position Contro concrete M-200 grade concrete , improve workability without impiring strength and durability as per direction of the engineer-in-charge (Min cement level as per latestiS 456 shall be maintained) (Cement level 360kg) for 150mm thick Trimix CC. Road with trimix vaccum dewatering system work with power trowling sheet form with M.S Channies, surface vibrator with providing road expansion joint having size 6mmx50mm by concrete cutter machine all labour charges complete.	4728.82	Rupees Four Thousand Seven Hundred Twenty Eight Paise Eighty Two Only	Cum	4728.82
	Item No. 7				
1.00	Providing and laying in position Contro concrete M-250 grade concrete , improve workability without impiring strength and durability as per direction of the engineer-in-charge (Min cement level as per latestiS 456 shall be maintained) (Cement level 380kg) for 150mm thick Trimix CC. Road with trimix vaccum dewatering system work with power trowling sheet form with M.S Channies, surface vibrator with providing road expansion joint having size 6mmx50mm by concrete cutter machine all labour charges complete.	4853.05	Rupees Four Thousand Eight Hundred Fifty Three Paise Five Only	Cum	4853.05

Qty. Estimated	Description of Item	RATE		Per	Amount
		In figer	In words		
	Item No. 8				
1.00	Providing and fixing pre-cast Rubber Dye / steel Dye inter locking concrete block 60mm thick with grade of concrete M300 pneumatic compressed / vibrated mechanically and as per approved design Confirming to IS 15658 : 2006 including 35 mm Sand layer for levelling and filling the joint with sand in proper line and level as per guidelines of IRC : SP 63-2018 etc. Complete.	706.93	Rupees Seven Hundred Six Paise Ninety Three Only	Sqm	706.93
	Item No. 9				
1.00	Earthwork for embankment including breaking clods, dressing with all lead and lift (excluding watering and consolidation)(A) From Borrow pits within land width	109.24	Rupees One Hundred Nine Paise Twenty Four Only	Cum	109.24
	Item No. 10				
1.00	Providing and supplying ISI marked only Standard length Stoneware pipes in standard lengths of following class and diameter including all taxes, insurance, transportation, freight charges, octroi, inspection charges, loading, unloading, conveyance to departmental stores, stacking etc. complete. (IS - 651 / 1989) 100mm Dia Class A	113.00	Rupees One Hundred Thirteen Only	Rmt	113.00
	Item No. 11				
1.00	Lowering, laying and jointing Stone Ware pipes in C. M. 1:1 of following diameters in proper position, grade and alignment at all level as directed by Engineer-in-charge including conveyance from stores to site of work, jointing material etc. comp.	66.70	Rupees Sixty Six Paise Seventy Only	Rmt	66.70
	Item No. 12				
1.00	RCC Precast M.H. Frame & cover: RCC Precast M.H. Frame & Cover Manufacture, supply & delivery of store or at site of work precast RCC M200 Frame cover suitable to Drainage M.H. and as per type design and drawing including cost of reinforcement MS Angle or Flat curing mould work etc., Frame suitable for 50cm opening of MH	1121.00	Rupees One Thousand One Hundred Twenty One Only	No	1121.00
	Item No. 13				
1.00	RCC Precast M.H. Frame & cover: RCC Precast M.H. Frame & Cover Manufacture, supply & delivery of store or at site of work precast RCC M200 Frame cover suitable to Drainage M.H. and as per type design and drawing including cost of reinforcement MS Angle or Flat curing mould work etc., Cover suitable for 50cm opening of MH	1173.00	Rupees One Thousand One Hundred Seventy Three Only	No	1173.00
	Item No. 14				
1.00	Supplying and fixing reinforced concrete heavy duty non-pressure pipes with collars for culverts carrying heavy traffic as per IS 458-1991 specifications including setting the pipes in C.M. 1:2 watering and laying (to level or slopes) of class NP3 of following internal diameters.(i) 300mm dia.	659.99	Rupees Six Hundred Fifty Nine Paise Ninety nine Only	Rmt.	659.99
	Item No. 15				
1.00	Supplying and fixing reinforced concrete heavy duty non-pressure pipes with collars for culverts carrying heavy traffic as per IS 458-1991 specifications including setting the pipes in C.M. 1:2 watering and laying (to level or slopes) of class NP3 of following internal diameters.(i) 450 mm dia.	1190.05	Rupees One Thousand One Hundred Ninety Paise Five Only	Rmt.	1190.05
	Item No. 16				
1.00	Providing Pre-moulded asphalt filler joints as per drawings.(A) 12mm	703.53	Rupees Seven Hundred Three Paise Fifty three Only	Sqm	703.53

Qty. Estimated	Description of Item	RATE		Per	Amount
		In figer	In words		
	Item No. 17				
1.00	Preparing surface by Brushing with wire brushes for removing caked mud etc. sweeping with brooms and finally fanning the cleaned surface with gunney bags to remove all loose dirt etc.(i) Water bound macadam surface (New)	29.73	Rupees Twenty Nine Paise Seventy Three Only	Sqm	29.73
Total Amount					24452.75

Note: GST paid as per Government rules.

I/We am/are willing to carry out the work @..... % above/below (Percent should be written in figures and words) The tendered amount mentioned above amount of my /our tender works out as under

Tendered amount Rs.....

Tendered amount Rs.....

Add% above Rs.....

Deduct% Below Rs.....

Total Rs.....

Net Rs.....

In words.....

In words.....

(Please strike out which ever is not applicable)

Note :

- 1 All work shall be carried out as per public works department handbook and other specifications of division or as directed.
- 2 Rates quoted inclusive of clearance of sight (prior to commencement of work and at its close) in all respect and hold good for work under all conditions , sight, moisture, weather etc
- 3 one percent labor cess will be deducted from the valued work done as per ' Bulding and other construction work welfare cess act' G.R. No. GHR - 2005/04/CWA/2004/841/M-3 Dt. 31/01/2005

Signature of the Contractor.

Chief Officer
Maliya-miyana Nagarpalika
Maliya-miyana (Morbi)