

TARAPUR NAGARPALIKA TARAPUR

Name of Work: Annual Rate Contract for Construction of CC & RCC Road in various Area under Road Resurfacing Grant (2026-27) @ TARAPUR Nagarpalika, TARAPUR, Dist: - Anand

SCHEDULE - "B"

Item No.	Quantities Estimated but may be more or less		Item of work	Tender Rate.		Unit	Total Amount according to Estimated Quantities
				In Figures	In Words		
1	1.00	Cmt	Demolition including stacking of serviceable materials and disposal of unserviceable materials with all lead and lift (I) C.C WORK (ii) RCC WORK			Cmt	
2	1.00	Cmt	Providing and supplying Quarry Spell Including Collection carting, staking & Spreading, Quarry Spell on road site including all Labour & Machinerys (JCB Tractore Etc) taxes and etc complete.			Cmt	
3	1.00	Cmt	Providing and laying cement concrete 1:3:6 (1 cement, 3 Coarse sand, 6-hand broken stone agree gate 40 mm nominal) and curing complete excluding cost of formwork in (A) Foundation and plinth.			Cmt	
4	1.00	Cmt	Providing and laying Controlled cement concrete M.200 curing complete excluding cost of form work and reinforcement for reinforced concrete work.			Cmt	
5	1.00	Kg	Providing Thermo Mechanically trated Bars T.M.T.Bar FE - 500/500D Reinforcement for R.C.C. work including, cutting, bending, Binding and placing in position complete for all floor.			Kg	
6	1.00	Smt	Providing & laying M.S. side rail of road thickness with necessary nut bolt plates, fixing as per width, applying plates vibrator, electric or diesel on channel comp, with V.D. system (Trimix)by using the necessary equipments 7 material % Machinery such as running screed vibrator on prelaid M.S channel for leveling vaccum pupms, floating & power trowling etc. compl, also including gruv cutting and filling joint with bituminous every 5 mtr, (incl. harner)			Smt	
7	1.00	Nos	Rising existing mainhole chamber with required all matrials and labour after that refitting mainhole fram and cover as per direction of engineer in charges etc. compete.			Nos	
8	1.00	Nos	R.C.C. precast manhole, frame and cover, manufacture, supply and delivery at store or site of work precast R.C.C. frame and cover (M200), suitable to drainage manhole and as per type design and drawing including cost of reinforcement, MS angles or flat, curing, mold work etc. complete. Frame suitable for opening of MH.			Nos	

9	1.00	Nos	R.C.C. precast manhole, frame and cover, manufacture, supply and delivery at store or site of work precast R.C.C. frame and cover (M200), suitable to drainage manhole and as per type design and drawing including cost of reinforcement, MS angles or flat, curing, mold work etc. complete. Cover suitable for opening of MH			Nos	
10	1.00	Smt	Removing & Refitting Of Paver Blockfor Lavelling And Filling The Joint with sand in proper line and level, carting, loading & unloding etc. complete as per directed by engineer in charge.			Smt	
						Total	
						Say	

(A) Total Tendered Amount Rs.

(A) Rebate on above tendered amount (if any)_____ % (In figures) Rs. _____
(_____ in word.)

(C) Net Tendered Amount (A - B)

in words (Rupees _____)

Note - 1 All work shall be carried out as per Public Works Department Handbook and other Specifications of Division or as directed.

Note - 2 All work columns is schedule should be filled in link and the total of entries in the last column should be struck by the Contractor

Note - 3 Rates quoted include clearance of site (Prior commencement of work and at its close) in all respects and hold good the work

Signature of the Contractor