

NAKHATRANA NAGARPALIKA					
Taluka - Nakhatrana			District -kutch		
SCHEDULE - B					
Name of work : - Annual Rate Contract for Construction of C.C. Road, Interlocking Paver Block Road and Miscellaneous Civil Works in Various Areas of Nakhatrana Nagarpalika, Dist: Kutch (Year 2026-2027)"					
Qty. Estimated	Description of Item		RATE	Per	Amount
		In figer	In words		
	Item No.1				
1.00	Box cutting the road surface to proper slope and camber for making a base for road work including removing the excavated stuff and depositing on the road side slope as directed upto 50Mt.lead.	109.24	Rupees One Hundred Nine Paise Twenty Four Only	Cum	109.24
	Item No. 2				
1.00	Providing, Laying , spreading and compacting graded stone aggregates to wet mix macadam 150 mm thick specification including premixing the material with water at OMC in mechanical mix plant, carraige of mixed material by tippers to site, laying in uniform layers with paver in sub base / base course on well prepared surface and compacting with vibratory roller to achive the desired density	984.50	Rupees Nine Hundred Eighty Four Paise Fifty Only	Cum	984.50
	Item No. 3				
1.00	"Raising / lowering of existing underground sewerage manhole/chamber masonry walls up to road level (up to 0.50 m height) in brickwork/concrete, including plastering, supplying, and fixing precast frame and cover, disposal of debris, and making the surface smooth as per instructions of the Engineer-in-Charge	3875.37	Rupees Three Thousand Eight Hundred Seventy Five Paise Thirty Seven Only	Nos	3875.37
	Item No. 4				
1.00	Demolition including stacking of serviceable materilas and disposal of unserviceable materials with all lead and lift. (i) Lime concrete.	623.02	Rupees Six Hundred Twenty Three Paise Two Only	Cum	623.02
	Item No. 5				
1.00	Providing and Laying Cement Concrete 1:4:8 (1: Cement , 4: Course Sand, 8: Crushed Broken Stone aggregate 40 mm nominal size) and Complete curing complete eccluding cost of form work in (A) Foundation and Plinth (3 inch/4 inch)	2925.97	Rupees Two Thousand Nine Hundred Twenty Five Paise Ninety Seven Only	Cum	2925.97
	Item No. 6				
1.00	Providing and laying in position Contro concrete M-200 grade concrete , improve workability without impiring strength and durability as per direction of the engineer-in-charge (Min cement level as per latestiS 456 shall be maintained) (Cement level 360kg) for 150mm thick Trimix CC. Road with trimix vaccum dewatering system work with power trowling sheet form with M.S Channies, surface vibrator with providing road expansion joint having size 6mmx50mm by concrete cutter machine all labour charges complete.	4478.34	Rupees Four Thousand Four Hundred Seventy Eight Paise Thirty Four Only	Cum	4478.34
	Item No. 7				
1.00	Providing and laying in position Contro concrete M-250 grade concrete , improve workability without impiring strength and durability as per direction of the engineer-in-charge (Min cement level as per latestiS 456 shall be maintained) (Cement level 380kg) for 150mm thick Trimix CC. Road with trimix vaccum dewatering system work with power trowling sheet form with M.S Channies, surface vibrator with providing road expansion joint having size 6mmx50mm by concrete cutter machine all labour charges complete.	4853.05	Rupees Four Thousand Eight Hundred Fifty Three Paise Five Only	Cum	4853.05

Qty. Estimated	Description of Item	RATE		Per	Amount
		In figer	In words		
	Item No. 8				
1.00	Providing and fixing pre-cast Rubber Dye / steel Dye inter locking concrete block 60mm thick with grade of concrete M300 pneumatic compressed / vibrated mechanically and as per approved design Confirming to IS 15658 : 2006 including 35 mm Sand layer for levelling and filling the joint with sand in proper line and level as per guidelines of IRC : SP 63-2018 etc. Complete.	706.93	Rupees Seven Hundred Six Paise Ninety Three Only	Sqm	706.93
	Item No. 9				
1.00	Earthwork for embankment including breaking clods, dressing with all lead and lift (excluding watering and consolidation)(A) From Borrow pits within land width	109.24	Rupees One Hundred Nine Paise Twenty Four Only	Cum	109.24
	Item No. 10				
1.00	Providing and laying (to level or slopes) and jointing with stiff mixture of Cement Mortar in proportion 1:1 Salt glazed stoneware pipes including testing of pipes and joints complete.(A) 100mm dia. (IS - 651 / 1989) 100mm Dia Class A	225.57	Rupees Two Hundred Twenty Five Paise Fifty Seven Only	Rmt	225.57
	Item No. 12				
1.00	RCC Precast M.H. Frame & cover: RCC Precast M.H. Frame & Cover Manufacture,supply & delivery of store or at site of work precast RCC M200 Frame cover suitable to Drainage M.H. and as per type design and drawing including cost of reinforcement MS Angle or Flat curing mould work etc., Frame suitable for 50cm opening of MH	1121.00	Rupees One Thousand One Hundred Twenty One Only	No	1121.00
	Item No. 13				
1.00	RCC Precast M.H. Frame & cover: RCC Precast M.H. Frame & Cover Manufacture,supply & delivery of store or at site of work precast RCC M200 Frame cover suitable to Drainage M.H. and as per type design and drawing including cost of reinforcement MS Angle or Flat curing mould work etc., Cover suitable for 50cm opening of MH	1173.00	Rupees One Thousand One Hundred Seventy Three Only	No	1173.00
	Item No. 14				
1.00	Supplying and fixing reinforced concrete heavy duty non-pressure pipes with collars for culverts carrying heavy traffic as per IS 458-1991 specifications including setting the pipes in C.M. 1:2 watering and laying (to level or slopes) of class NP3 of following internal diameters.(i) 300mm dia.	659.99	Rupees Six Hundred Fifty Nine Paise Ninety Nine Only	Rmt.	659.99
	Item No. 15				
1.00	Supplying and fixing reinforced concrete heavy duty non-pressure pipes with collars for culverts carrying heavy traffic as per IS 458-1991 specifications including setting the pipes in C.M. 1:2 watering and laying (to level or slopes) of class NP3 of following internal diameters.(i) 450 mm dia.	1190.05	Rupees One Thousand One Hundred Ninety Paise Five Only	Rmt.	1190.05
	Item No. 16				
1.00	Providing Pre-moulded asphalt filler joints as per drawings.(A) 12mm	703.53	Rupees Seven Hundred Three Paise Fifty Three Only	Sqm	703.53
	Item No. 17				
1.00	Preparing surface by Brushing with wire brushes for removing caked mud etc. sweeping with brooms and finally fanning the cleaned surface with gunney bags to remove all loose dirt etc.(i)	29.73	Rupees Twenty Nine Paise Seventy Three Only	Sqm	29.73

Qty. Estimated	Description of Item	RATE		Per	Amount
		In figer	In words		
	Item No. 18				
1.00	Supplying only Pre-cast Interlocking Concrete Paver Blocks of Grade M-25, having a thickness of 60mm, of approved shape, color, and design, manufactured as per IS:15658 standards, including loading, transportation, unloading, and stacking at designated sites/stores within Nakhatrana Nagarpalika area, as directed by the Engineer-in-Charge.	377.12	Rupees Three Hundred Seventy Seven Paise Twelve Only	Smt	377.12
	Item No. 19				
1.00	Providing and fixing Barbed Wire Fencing 1.20 m high, with 2.0 m long Mild Steel (M.S.) angle posts of size 40mm x 40mm x 6mm, spaced at 2.50 m center-to-center. The fencing shall consist of 5 horizontal lines and 2 diagonal lines of Galvanized Iron (G.I.) barbed wire weighing not less than 9.38 Kg per 100 meters, properly strained and secured to posts with G.I. staples. The M.S. posts shall be firmly embedded in the ground within Cement Concrete blocks of size 0.50m x 0.50m x 0.50m of mix 1:5:10 (1 cement : 5 coarse sand : 10 graded stone aggregate), and all exposed surfaces of M.S. posts shall be finished with 3 coats of approved quality oil paint, including excavation, refilling, and disposal of surplus earth, etc. complete as directed by the Engineer-in-Charge."	391.93	Rupees Three Hundred Ninety One Paise Ninety Three Only	Rmt	391.93
	Item No. 20				
1.00	Supplying only clean, sharp, and hard Stone Dust (Crusher Dust) free from clay, loam, organic matter, or any other deleterious substances, obtained from approved quarries, including loading, transportation, unloading, and stacking at designated sites/stores within Nakhatrana Nagarpalika area, as directed by the Engineer-in-Charge."	158.68	Rupees One Hundred Fifty Eight Paise Sixty Eight Only	Cmt	158.68
Total Amount					24696.26

Note: GST paid as per Government rules.

I/We am/are willing to carry out the work @..... % above/below (Percent should be written in figures and words) The tendered amount mentioned above amount of my /our tender works out as under

Tendered amount Rs.....

Tendered amount Rs.....

Add% above Rs.....

Deduct% Below Rs.....

Total Rs.....

Net Rs.....

In words.....

In words.....

(Please strike out which ever is not applicable)

Note :

- 1 All work shall be carried out as per public works department handbook and other specifications of division or as directed.
- 2 Rates quoted inclusive of clearance of sight (prior to commencement of work and at its close) in all respect and hold good for work under all conditions , sight, moisture, weather etc
- 3 one percent labor cess will be deducted from the valued work done as per ' Bulding and other construction work welfare cess act' G.R. No. GHR - 2005/04/CWA/2004/841/M-3 Dt. 31/01/2005

Signature of the Contractor.

Chief Officer
Nakhatrana Nagarpalika
Nakhatrana -kutch