

TARAPUR NAGARPALIKA TARAPUR

Name of Work: - Annual Rate Contract for Construction of Bituminous Road in various Area Under Road Resurfacing Grant (2026-27) @ TARAPUR Nagarpalika, TARAPUR Dist:- Anand

SCHEDULE - "B"

Item No.	Quantities Estimated but may be more or less		Item of work	Tender Rate.		Unit	Total Amount according to Estimated Quantities
				In Figures	In Words		
1	1.00	Smt	Scarifying gravelled macadam or bitumen macadam surface 6 cm to 10 cm.depth including stacking useful materials on road side and disposing off remaining stuff.			Smt	
2	1.00	Cmt	Demolition including stacking of serviceable materials and disposal of unserviceable materials with all lead and lift (I) C.C WORK (ii) RCC WORK			Cmt	
3	1.00	Cmt	Providing and supplying Quarry Spell including collection carting, staking Spreading, Quarry spell on Road site including all Lbour machiney (JCB Tractore Etc) taxes and etc. complete.			Cmt	
4	1.00	Cmt	Providing and laying Compacted WBM (Grade II) with BT crushed metal of size 40mm to 63mm) including using 20% stone Screening grit 0.16 cum and stone dust 0.08 cum as filler including for spreading, watering & consolidation by vibrator power road roller 8 tone to 12 tone etc. complete as per morth clause 404.			Cmt	
5	1.00	Cmt	Providing and Laying W.M.M mm thick with M.C BT chips as per required gradation mixing with required optimum quantity of water Including spreding watering consolidation using power and roller etc. complete.			Cmt	
6	1.00	Smt	Preparing surface by Brushing with wire brushes for removing caked mud etc. sweeping with broom sand finally fanning the cleaned surface with gunney bags to remove all loose dirtetc. (ii) Black top surface.			Smt	
7	1.00	M.T	Providing & laying Bituminous Grout compacted with (VG10) asphalt 60/70 grade at the rate of 1.99 % by weight of mix for mixing and tack coat at 2.5k/10sq.m, emulsion on B.T surface using B.T chips of required gradation including cleaning and heating asphalt by continuous batching of drum mix plant and spreding the same by paver finisher one layer and consolidation work with vibratory roller including providing all materials, equipment, tools and plant, oil, kerosene, firewood labour charges etc. complete using contractor own machinaries Drum mix plant and paver finisher etc. complete			M.T	

8	1.00	M.T	Providing & Laying 37.50 mm thick Bituminous Macadam with B.T. Aggregate as per MORT & H specification & asphalt grade (VG-30/60-70) for tack coat @ 2.5 Kg. / 10 Sq.m. on B.T surface With Mechanical Sprayer & Bitumen Grade (VG-30) for mixing @ 34.00 Kg. / M.T. i.e. 3.40 % of total weight of mix including heating & mixing the aggregate & asphalt in drum mix plant and spreading the same by paver finisher & consolidation with vibratory roller including providing all materials equipments, tools & plants, fire wood, oil, kerosene, labour charges etc. complete using contractor's own machinery drum mix plant & paver finisher etc. complete.			M.T	
9	1.00	M.T	Providing and Laying 25 mm thick Semi Dense Bituminous Carpet (Seal Coat) with B.T. aggregate as per M.O.R.T. & H. gradation and bitumen grade (VG-30) for mixing @ 50.00 Kg/M.T. i.e. 5.0% by weight of total mix including heating & mixing the aggregate and asphalt by of drum mix plant and spreading the same by paver finisher and consolidation with power roller, including providing all materials equipments, tools and plants, oil, kerosene, firewood, labour charges etc. complete using contractor's own machineries drum mix plant and paver finisher etc. complete.			M.T	
10	1.00	Smt	Providing & Applying Ashphalt pinting by spraying asphalt 80 / 100 grade of 5kg / 10 smt. & than spreading sand at a rate 0.03 cmt / 10 smt. Including preparing surface heating asphalt etc. complete as directed			Smt	
11	1.00	M.T	Supply of hot mix material for patch work with gradation of B.T. materials same as per gradation of semi dense carpet including using asphalt Grade : VG-30 for mixing @ 47.6 KG / M.T. including heating the asphalt and aggregate by continuous batching of hot mix plant and supplying hot mix materials at site of work by dumper as and where directed within 50 Km from plant site including providing all materials equipment T.&P. oil, kerosene, labour charges etc. complete using contractor's own hot mix plant and dumper etc. complete.			M.T	
12	1.00	M.T	Supply of readymade bituminous Cold mix pothole patching material for B.T. surface patch using Medium curing cut back Bitumen MC-800 at the rate of 5.6% of total mix and it shall be conforming to IS : 217 Specification, including heating the material as specified in section 4 and materials stacked at site of work by contractor's own dumper as and where directed within 50 Km lead, including providing all materials equipment T.&P. oil, kerosene, labour charges etc. complete			M.T	

13	1.00	Nos	Rising existing mainhole chamber with required all materials and labour after that refitting mainhole frame and cover as per direction of engineer in charges etc. complete.			Nos	
14	1.00	Nos	R.C.C. precast manhole, frame and cover, manufacture, supply and delivery at store or site of work precast R.C.C. frame and cover (M200), suitable to drainage manhole and as per type design and drawing including cost of reinforcement, MS angles or flat, curing, mold work etc. complete. Frame suitable for opening of MH.			Nos	
15	1.00	Nos	R.C.C. precast manhole, frame and cover, manufacture, supply and delivery at store or site of work precast R.C.C. frame and cover (M200), suitable to drainage manhole and as per type design and drawing including cost of reinforcement, MS angles or flat, curing, mold work etc. complete. Cover suitable for opening of MH			Nos	
16	1.00	Smt	Removing & Refitting Of Paver Block for Levelling And Filling The Joint with sand in proper line and level, carting, loading & unloading etc. complete as per directed by engineer in charge.			Smt	
						Total	
						Say	

(A) Total Tendered Amount Rs.

(A) Rebate on above tendered amount (if any) _____% (In figures) Rs. _____
(_____ in word.)

(C) Net Tendered Amount (A - B)

in words (Rupees _____)

Note - 1 All work shall be carried out as per Public Works Department Handbook and other Specifications of Division or as directed.

Note - 2 All work columns in schedule should be filled in link and the total of entries in the last column should be struck by the Contractor

Note - 3 Rates quoted include clearance of site (Prior commencement of work and at its close) in all respects and hold good the work

Signature of the Contractor