

DHOLKA NAGARPALIKA - DHOLKA					
NAME OF WORK: -					
Annual Rate Contract of C.C. Road at Various Location at Dholka Nagarpalika , Dholka (7th Attempt)					
ABSTRACT SHEET					
Sr. No	Qty.	Item	Rate	Units	Amount
1	1.00	Demolition and disposal of unserviceable materials with all lead and lift.(i) Cement concrete.		Cu.Mt	
2	1.00	Box cutting the road surface to proper slope and camber for making a base for road work including removing the excavated stuff and depositing on the road side slope as directed upto 50Mt.lead.		Cu.Mt	
3	1.00	Providing and laying cement concrete 1:4:8 (1 cement : 3 coarse sand : 6 Crushed stone aggregates 40 mm nominal size) and curing etc complete excluding cost of form work in (A) Foundation & Plinth.		Cu.Mt	
4	1.00	Providing and laying controlled cement concrete M.200 and curing complete excluding the cost of formwork and reinforcement for reinforced concrete work in (A) Foundations, footings, Base of columns and Mass concrete		Cu.Mt	
5	1.00	Raising of I.C. Chamber av 0.180 mtrs Height with Brick Masonary in C.M 1:6 at top including cost of excavation refitting of frame & cover in C.C. 1:2:4, Plastering in C.M 1:3 curing % Disposal of Dismantling Material from site etc. Completed incl. all carting and providing of materials which is required for the purpose (except frame and Cover)		Nos	
6	1.00	Trimix process for road work by using equipment floater surface vibrator incl. making grove and rough finish to surface incl. curing comp.		Sq.Mt	
7	1.00	Providing and fixing pre-cast Rubber Dye inter locking concrete block 60mm thick with grade of concrete M300 pneumatic compressed by mechanically pressed and as per approved design confirming to IS 15658:2006 including 35mm Sand layer for levelling and filling the joint with sand in proper line and level as per guidelines of IRC SP 63 -2018 etc. complete.		Sq.Mt	
8	1.00	Providing and fixing pre-cast concrete kerb stone of gray cement based concrete block 30cm length,30cm height and 15cm thick of M200 grade concrete as per approved design and including excavation for fixing in proper line and level,filling the joint with C:M 1:3 (1cement:3fine sand) etc complete		R.Mt	
9	1.00	Providing and Supplying, graded stone aggregate to wet mix macadam as per MORT & H specification including premixing the material at OMC in mechanical mix plant carriage of mixed materially tipper to site		Tone	
10	1.00	Providing and Supplying Quarry Spell Including Collection carting, Staking , Quarry Spell tipper to site Including Royaltie, etc.		Tone	
Total Amount					