

Name of work :-**Repairing of Existing Godown Of Gujrat Sheep And Wool Development Corp At Mankuva dis.Kutch****SPECIFICATION INDEX**

It. No.	Description of Item	Specification No. as per General Technical Specification booklet of approved by R&B Deptt.		Remarks
		Item no.	Page no.	
1	2	3	4	5
1	Providing 15mm thick cement plaster in single coat on Rough (Similar)side of single or half brick walls for interior plastering upto floor two level and finished even and smooth in (i) Cement mortar 1:3 (1-cement:3-sand)	17.58(ii)	120	Plaster work shall be carrid out in 15 mm instead of 10mm
2	Providing 20 mm thick cement plaster by using Ready Mix Mortar for plaster in single coat on single or half brick walls for interior plastering upto floor two level and finished even and smooth in Cement mortar 1:3 (1 Cement : 3 sand)	17.58(iii)	120	Plaster work shall be carrid out in 15 mm instead of 10mm (by using Ready mix Mortrar Plaster)
3	Precast concrete block masonry (including quoin blocks jamb blocks closer etc.) with solid concrete blocks of approved size made of cement concrete 1:3:6 mix (1- Cement : 3 coarse sand: 6- graded stone aggregates of 20 mm and down grade) in foundation and plinth cement mortar 1:6	7.75	60	
4	Providing and Fixing 6 mm thick Lexan Polycarbonate multi wall roofing sheet fixed with hilti screw and rubber silicon sealer and alluminium strip of size 50 x 3 mm etc complete as directed by Engineer in charge.	As Per Seperate Sheet Attached		
5	Steel work, welded in built up sections framed work including cutting, hoisting, fixing in position and applying a priming coat of red lead paint. (A)In beams and joists, channels angles Tees, flats, with connecting plates or angle cleats as in main and cross beams. Hip and jack rafters, purlins conneted to common rafters and the like	11.4(A)	80	
6	Providing and fixing rolling shutters of approved make made of 80 mm wide M.S. laths inter-locked together through their entire length and jointed together at the ends by end locks mounted on specially designed pipe shaft with bracket plates, guide channels and arrangements for inside and outside locking with push-pull operation including the cost of hood cover and spring etc. complete.(A) Shutters having width below 3.5 M.	M-32	17	
7	Wall painting (two coats) with plastic emulsion paint of approved brand and manufacture on undecorated wall surface to give an even shade including thoroughly brushing the surface free from mortar droppings and other foreign matter and sand papered smooth.	18.57.	136	

It. No.	Description of Item	Specification No. as per General Technical Specification booklet of approved by R&B Deptt.		Remarks
		Item no.	Page no.	
1	2	3	4	5

8	Painting two coats (including priming coat) on new steel and other metal surface with enamel paint, brushing, interior to give an even shade including cleaning the surface an even shade including cleanicn the surface of all dirt, dust and other foreign matter.	19.7. 19.12	138 139	
9	Finishing wall with weather proof exterior emulsion paint on wall surface (two coats) to give an required shape even shade after thoroughly brushing the surface to remove all dirt, and remains of loose powdered materials.etc complete	As Per Seperate Sheet Attached		
10	Providing and laying cement concrete 1:2:4 (1 Cement : 2 coarse sand : 4 Machine Crushed stone aggregates 20m.m. nominal size) and curring complete excluding cost of form work in : PCC For Footing And Plinth Beams	5.3.13(A)	40	
11	Providing upto floor two level precast cement concrete jali or grill 1:2:4 mix (1- Cement : 2- coarse sand : 4- graded stone aggregate 6mm nominal size) reinforced with 1.6 mm dia. Mild steel wire including roughening,cleaning, fixing and finishing in cement mortar 1:3 and curing complete. (A) 50mm thick	5.6.2.(A)	46	
12	Providing and erecting main with 1.1Kv Grade FRLS PVC insulated isi marked stranded copper conductor wire in following typeof pipe 2 wire 2.5Sqmm	Work shall be carried out as per Item description and instruction by engineer in charge.		
13	providing and erecting 415V MCB double pole Switch for lighting load having 10Ka breaking capacity confirms to is 8828in existing box having following capacity	Work shall be carried out as per Item description and instruction by engineer in charge.		

Signature of Contractor

**Deputy Executive Engineer,
R&B Sub Division, Bhuj**