

Name Of Work :- SR to Electrical Split A.C & Water Cooler Work in Trauma Center, 1200bed hospital, Spine hospital at Civil Hospital Asarwa Ahmedabad.

SCHEDULE - B

Memorandum showing items of works to be carried out

It No.	Quantities estimated but may be	Item of Work	Estimated Rates		Unit	Total Amount According to estimated
			In Figure Rs. Ps.	In Words		
1.00	2.00	3.00	4.00	5.00	6.00	7.00
1		Providing and erecting <u>Inverter</u> based approved make split air-conditioning unit consisting of condensing unit with variable speed fan motor, inverter type hermetically sealed rotary compressor with accessories etc. duly connected separately erected evaporating unit and blower motor with its accessories by means of extra supplied proper insulated copper tubing, drain PVC pipes suitable for (cost includes Eco Friendly green gas charging and 15A plug top & Remote Control & MS Stand) with necessary core cutting.				
		(1)For ISEER Range (KWH/KWH)(3.1 to 3.99)				
	2	(B) for 1.5 ton capacity	45898.44	Rupees Forty Five Thousand Eight hundred Ninety Eight Paise Forty Four Only	Ea.	91796.88
2	7	Supplying and erecting insulated pair of soft copper tubing open or concealed including power and control cable, necessary PVC drain pipes for Split/Cassette AC machine up to 4 TR capacity	1158.47	Rupees Five Thousand Four hundred Thirty Four Paise Eighty One Only	Rmt.	8109.29
3	11	Providing and erecting water cooler having storage capacity 80Ltr. & cooling capacity 40 Ltr.per hour @ an ambient temp of 45° C. The outlet temp. of the water should drop by 15° C within a hour, The water cooler should be comprising of hermetically sealed compressor, fan motor, condensing unit, water tank surrounded by evaporating coil, thermostats, relay etc. complete with necessary inlet & outlet connection. The body of water cooler will be made from Stainless Steel. and ISI Certified.	54515.76	Rupees Nineteen Thousand One hundred Ninety Four Paise Four Only	Ea.	599673.36

4	2	Providing & erecting water cooler having storage capacity 150 Ltr. & cooling capacity 150 Ltr.per hour @ an ambient temp of 45° C. The outlet temp. of the water should drop by 15°C within a hour, The water cooler should be comprising of hermetically sealed compressor, fan motor, condensing unit, water tank surrounded by evaporating, coil, thermostats, relay etc.complete with necessary inlet & outlet connection. The body of water cooler will be made from Stainless Steel and ISI Certified.	61482.74	Rupees Twelve Thousand Four hundred Ten Paise Eighty Eight Only	Ea.	122965.48		
					Total Amount	822545.01		
I/We am / are willing to carry out the work at % above / / below percent (should be writtern in figures and words) of the estimated rate mentioned above. Amount of my / out tender works out as under.								
<table border="0" style="width: 100%;"> <tr> <td style="width: 50%; vertical-align: top;"> Estimated Amount Put to tender Rs. Deduct % below Rs. Net Rs. In Words </td> <td style="width: 50%; vertical-align: top;"> Estimated Amount Put to tender Rs. Add % above Rs. Total Rs. In Words </td> </tr> </table> <p>(* Plase strike out whichever is not applicable.)</p>							Estimated Amount Put to tender Rs. Deduct % below Rs. Net Rs. In Words	Estimated Amount Put to tender Rs. Add % above Rs. Total Rs. In Words
Estimated Amount Put to tender Rs. Deduct % below Rs. Net Rs. In Words	Estimated Amount Put to tender Rs. Add % above Rs. Total Rs. In Words							
Note - 1	All works shall be carried out as per public works department handbook and other specification of division or as Directed							
નોંધ - ૧	બધુંજ કામ બાંધકામ વિભાગની પુસ્તિકા અને ડિવિઝનની બીજી ખાસ વિગત મુજબ અથવા સૂચના પ્રમાણે કરી આપવાનું રહેશે.							
Note - 2	All the columns in Schedule should be filled in ink and the total of the entries in the last column should be struck by the contractor under his singature.							
નોંધ - ૨	અનુસૂચિમાં બધા ખાનાની વિગતો સહીથી ભરવી અને છેલ્લા ખાનાની નોંધોનો સરવાળો કરી કંટ્રાક્ટરે પોતાની સહી કરવી.							
Note - 3	Rate quoted include clearance of site(prior commencement of work and at its close) in all respects and hold good for work under all condition, site, moisture, weather etc.							
નોંધ - ૩	ટાંકેલા દરમાં, સ્થળની (કામના આરંભે અને પુરુ થાય તે વખતે) દરેક રીતે સાફ સૂકી કરવાનો સમાવેશ થાય છે અને તે દર તમામ પરિસ્થિતિ, સ્થળ, ભેજ, હવામાન વગેરે હેઠળ કામ માટે અમલમાં રહેશે.							
Note - 4	To be continued on additional sheets, if found necessary.							
નોંધ - ૪	જરૂર જણાય વધારાના કાગળો જોડી ચાલું રાખવું.							
Note - 5	Dismenta Material of Rs.59764.41 Will Be Deducted From 1R.A. Bill or F & F Bill.							
Deputy Executive Engineer (Elect.) PIU, Asarwa, Ahmedabad			Executive Engineer (Elect.) PIU, Asarwa, Ahmedabad					